

STORMWATER MANAGEMENT REPORT

FOR

Meridian Furniture, Inc.

LOCATED AT

**300-356 Enterprise Ave.
City of Trenton
Block 23203, Lot 1
Block 23102 Lots 2 & 9
Township of Lawrence
Block 602, Lots 1 & 2
Mercer County, New Jersey**

PREPARED: September 19, 2025
REVISED: December 15, 2025



GREGORY J. REDINGTON
NJ PROFESSIONAL ENGINEER LICENSE No. 37543



433 North Avenue East, Westfield, NJ 07090
T: (908) 233-4030 F: (908) 233-8837
Redcomllc.com

TABLE OF CONTENTS

1. DESCRIPTION OF PROJECT

- 1.1. INTRODUCTION
- 1.2. SOILS AND TOPOGRAPHY
- 1.3. METHODOLOGY
- 1.4. PRE-DEVELOPMENT CONDITIONS
- 1.5. POST-DEVELOPMENT CONDITIONS
- 1.6. STORMWATER COLLECTION SYSTEM
- 1.7. GROUNDWATER RECHARGE ANALYSIS
- 1.8. WATER QUALITY ANALYSIS
- 1.9. GREEN INFRASTRUCTURE STANDARDS
- 1.10. SOIL EROSION AND SEDIMENT CONTROL
- 1.11. CONCLUSION

2. EXISTING & PROPOSED RUNOFF MODELS

3. RUNOFF & HYDROGRAPH ANALYSIS: EXISTING AND DISTURBED CONDITIONS

- 3.1 2-YEAR ADJUSTED STORM EVENT
- 3.2 10-YEAR ADJUSTED STORM EVENT
- 3.3 100-YEAR ADJUSTED STORM EVENT
- 3.4 2-YEAR STORM EVENT YEAR 2100 PROJECTION
- 3.5 10-YEAR STORM EVENT YEAR 2100 PROJECTION
- 3.6 100-YEAR STORM EVENT YEAR 2100 PROJECTION

4. RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED CONDITIONS

- 4.1 2-YEAR ADJUSTED STORM EVENT
- 4.2 10-YEAR ADJUSTED STORM EVENT
- 4.3 25-YEAR ADJUSTED STORM EVENT
- 4.4 100-YEAR ADJUSTED STORM EVENT
- 4.5 2-YEAR STORM EVENT YEAR 2100 PROJECTION
- 4.6 10-YEAR STORM EVENT YEAR 2100 PROJECTION
- 4.7 100-YEAR STORM EVENT YEAR 2100 PROJECTION

5. STORM MANAGEMENT DESIGN

- 5.1 POND ROUTINGS (2, 10 AND 100-YEAR STORM EVENTS)
- 5.2 STORM STORAGE DESIGN
- 5.3 BASIN SECTION
- 5.4 T_c CALCULATIONS EXISTING AND PROPOSED

6. STORM PIPE CAPACITY CALCULATIONS

7. EMERGENCY SPILLWAY CALCULATIONS

8. MAPS & DIAGRAMS

- 8.1 TAX MAP (City of Trenton. Sheet 231 & 232 ; Township of Lawrence Sheet 6)
- 8.2 FLOOD INSURANCE RATE MAP (FEMA FIRM MAP)
- 8.3 AREA MAP, LEGEND & SOIL DESCRIPTION (SOIL MAP)
- 8.4 POLICY MAP OF THE STATE DEVELOPMENT PLAN

9. CHARTS & TABLES

- 9.1 RUNOFF COEFFICIENTS (CN VALUES)
- 9.2 POINT PRECIPITATION FREQUENCY ESTIMATES AS PER NOAA

10. SUBSURFACE SOIL INVESTIGATION & REPORT

Prepared by SESI Consulting Engineers., Dated June 5, 2025.

INSET POCKET

- ED-1: EXISTING DRAINAGE AREA MAP (Dated: 09/16/2025)
- PD-1: PROPOSED DRAINAGE AREA MAP (Dated: 09/17/2025)

1. DESCRIPTION OF PROJECT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

1.1 INTRODUCTION

This Stormwater Management Report has been prepared for Meridian Furniture, Inc. as a requirement for the proposed development project. The property in question is located at 300-356 Enterprise Ave, City of Trenton, Block 23203, LOT 1, Block 23102 Lots 2 & 9 and Township of Lawrence, Block 602, Lots 1 & 2, Mercer County, New Jersey.

A set of plans entitled “Preliminary/Final Major Site Plan prepared for Meridian Furniture inc. 300- 356 Enterprise Avenue, City of Trenton and township of Lawrence, Mercer County, New Jersey.”, dated 09/19/2025 by Gregory J. Redington P.E., is being submitted in conjunction with this report.

This Stormwater Management Report has been designed in accordance with Land Development Ordinance Article XVI: “Stormwater Management Controls” of the City of Trenton and Lawrence Township, New Jersey Stormwater Management Rules at N.J.A.C. 7:8 and Soil Erosion and Sediment Control Act, N.J.S.A. 4:24-39. This project follows the latest July 2023 NJ Stormwater Best Management Practices Manual release.

This project will disturb more than one (1) Acre of land; therefore, because of this condition the project is classified as Major Development and it falls within the jurisdictional thresholds of the Storm Management Rules N.J.A.C. 7:8.

The drainage area analyzed in this report contains 12.116 acres.

1.2 SOILS AND TOPOGRAPHY

According to NRCS/USDA’s Soil Survey of Mercer County, New Jersey, soils in the area are identified as follows:

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
UdgB	Udorthents, gravelly substratum, 0 to 8 percent slopes	D	18.6	80.8%
UdstB	Udorthents, stratified substratum, 0 to 8 percent slopes	D	0.1	0.4%
WATER	Water		4.3	18.8%
Totals for Area of Interest			23.0	100.0%

Boundary and areas of soils are shown on a map attached in the *Maps & Diagrams* section of this report.

Specific site soil conditions were evaluated by SESI Consulting Engineers and recorded in a Subsurface Soil Investigation and report prepared on June 5, 2025; attached at the end of this report.

1.3 METHODOLOGY

This report will address the design of the Stormwater collection, detention and conveyance system. Runoff and volume values have been calculated under both pre and post development conditions in accordance with the USDA Natural Resources Conservation Service methodology as described in Chapter 5 of New Jersey Stormwater Best Management Practices Manual and described in the Urban Hydrology for Small Watersheds (TR-55) publication.

Runoff curve numbers (CN Values) have been established by use of the hydrologic soil groupings associated with the soils found on the NRCS Online Soil Survey. A composite soil survey map is provided for review of the general soil characteristics and it is attached to this report in section Maps and Charts. Run-off coefficients Table 2-1a: Runoff curve numbers for urban areas (CN Values) as per USDA Urban Hydrology for Small Watersheds TR-55. Values can be found in *Charts and Tables* section of this report.

One (1) existing point of analysis have been delineated and the time of concentration has been computed using the McCuen-Spiess limitation for each sub drainage area within the drainage areas. The drainage area E-DA as shown on the Existing Drainage Area Map is attached to the inset pocket located at the end of this report. Times of concentration have been calculated using TR-55 methodology with maximum sheet flow lengths of 100 feet.

Storm analysis and calculations were performed with HydroCAD Stormwater modeling version 10.20-6a the storm flows for the 2, 10 and 100-year recurrence interval storms were analyzed for the pre and post development conditions. Stormwater outfall will not exceed of the 2, 10 and 100-year peak existing values respectfully.

The rainfall amounts used in the calculations for quantity and quality design storms were as found per NOAA Point Precipitation Frequency Estimates data attached in the *Charts & Tables* section of this report and summarized as follows:

Design Storm Recurrence Interval	Inches of Rainfall	Adjustment Factor	Adjusted Rainfall Depth
NJ WQ Design Storm	1.25 in (*)	---	1.25 in
2-Year Event	3.33 in	1.01	3.36 in
10-Year Event	5.00 in	1.02	5.10 in
25-Year Event	6.13 in	---	---
100-Year Event	8.19 in	1.04	8.51 in
<i>(*) The 1-year storm event used is based on the New Jersey Department of Environmental Protection 1.25 inch/2-Hour Stormwater Quality Design Storm.</i>			

Calculation of the water quality storm discharges for a 1.25-inch rainfall in 2 hours and computations of stormwater discharge rates and volumes for 2-year, 10-year, and 100-year storm events were obtained by using the latest NCRS 24 Hour Design Rainfall Depths for a NOAA Type C rainfall distribution.

The existing and proposed rainfall depth was retrieved from the NOAA Point Precipitation Frequency Estimates. Additionally, the applicable multiplier as set forth in Table 5-6 of N.J.A.C. 7:8-5.7 to adjust the precipitation values. The proposed depth of flow, multiplier and adjusted depth of flow are summarized below:

Proposed Design Storm Recurrence Interval (Year 2100 Rainfall Data)	Inches of Rainfall	Adjustment Factor	Adjusted Rainfall Depth
2-Year Event	3.33 in	1.16	3.86 in
10-Year Event	5.00 in	1.17	5.85 in
100-Year Event	8.19 in	1.36	11.14 in

1.4 PRE-DEVELOPMENT CONDITIONS

The property in question has a total area of 12.116 acres as per survey of existing conditions prepared by Insite Surveying, LLC last revised 07/15/2025 in which the property contains a demolished and capped industrial site, now consisting of natural grass and wooded areas. Offsite drainage areas consisting of buildings, asphalt, grass and wooded regions also are calculated in the existing conditions as these regions also convey to a Point of Analysis.

A summary of existing coverage areas is shown as follows:

EXISTING AREA COVERAGES				
Imp. Concrete/ Asphalt	18,621.12	S.F.	0.427	Ac. 3.52%
Water, HSG D	39,293.28	S.F.	0.902	Ac. 7.44%
Wood/Grass. Good, HSG D	421,905.89	S.F.	9.686	Ac. 79.96%
50-75% Grass , Good, HSG D	47,968.77	S.F.	1.101	Ac. 9.09%
TOTAL DRAINAGE AREA...	527,789.06	S.F.	12.116	Ac. 100.00%

As shown on the *Existing Drainage Area Map* supplied with this report (see inset pocket) the Pre-development drainage area has been detailed below:

Existing Drainage Area E-DA Onsite (12.116 Ac.): This is mostly covered by grass and woods/grass areas, with a small amount of impervious asphalt. The runoff from this area primarily sheet flows northeast towards a yard inlet located in the back of the property above the retaining

wall, where it is collected and discharges out of a 36" CMP pipe at the edge of the Assunpink Creek.

Allowable peak runoffs to respective point of analysis have been calculated and summarized below:

Allowable Peak Flow Analysis at Point "POA-1"						
ADJUSTED						
	Existing P.O.A. "E-DA"	Existing disturbed Area Runoff	Existing calculated undisturbed Area Runoff	Reduction Factor	Allowable Disturbed	Allowable P.O.A. "E-DA"
	<i>A</i>	<i>B</i>	<i>C = A - B</i>	<i>D</i>	<i>E = (B x D)</i>	<i>(C + E)</i>
2-Year	13.68 cfs	10.95 cfs	2.73 cfs	50%	5.48 cfs	8.21 cfs
10-Year	26.36 cfs	21.78 cfs	4.58 cfs	75%	16.34 cfs	20.92 cfs
100-Year	52.56 cfs	44.37 cfs	8.19 cfs	80%	35.50 cfs	43.69 cfs

Allowable Peak Flow Analysis at Point "POA-1"						
PROJECTED YEAR 2100						
	Existing P.O.A. "E-DA"	Existing disturbed Area Runoff	Existing calculated undisturbed Area Runoff	Reduction Factor	Allowable Disturbed	Allowable P.O.A. "E-DA"
	<i>A</i>	<i>B</i>	<i>C = A - B</i>	<i>D</i>	<i>E = (B x D)</i>	<i>(C + E)</i>
2-Year	17.78 cfs	14.41 cfs	3.37 cfs	50%	7.51 cfs	10.88 cfs
10-Year	33.08 cfs	27.53 cfs	5.55 cfs	75%	21.19 cfs	26.74 cfs
100-Year	75.07 cfs	63.83 cfs	11.24 cfs	80%	51.66 cfs	62.90 cfs

1.5 POST-DEVELOPMENT CONDITIONS

The applicant proposes to construct a 221,902 sf. warehouse building. In addition to the proposed buildings, there will be accompanying loading docks of various lengths, car parking areas, and associated landscaping and lighting amenities. The disturbance due to construction has been limited to 12.11 Acres of the current area; this includes a portion that is within the right-of-way of Enterprise Drive.

A summary of post development areas is shown below:

PROPOSED AREA COVERAGES				
Imp. Asphalt	77,6690	S.F.	1.783	Ac. 14.72%
Imp. Concrete	19,592	S.F.	0.450	Ac. 3.71%
Imp. Roof	221,902	S.F.	5.094	Ac. 42.05%
Water, HSG D	39,293	S.F.	0.902	Ac. 3.47%
< 50% Grass, Poor, HSG D	169,214	S.F.	3.885	Ac. 32.07%
TOTAL DRAINAGE AREA...	527,670	S.F.	12.114	Ac. 100.00%

As shown on the *Proposed Drainage Area Map* supplied with this report (See inset pocket), the Post-development drainage area has been detailed below:

Proposed Drainage Area P-DA (12.114 Ac.): This area is composed generally by existing undisturbed pervious areas, roofs, grass, overland brush, and wooded areas. It is also composed of proposed roofs, grassy areas, and proposed motor vehicle surfaces in the form of pedestrian parking, drive aisles, truck parking, and loading docks.

The western portion of the roof runoff from the proposed building is conveyed via a roof-leader system and is pretreated with leaf-screens before discharging into a large-scale bioretention basin. While the runoff from the western portion of the captured Motor Vehicle Surface is collected and pretreated via a small-scale bioretention basin and discharges into the same large-scale bioretention basin as the roof. The large-scale bioretention basin discharges into the existing drainage system that discharges into the Assunpink Creek.

The eastern portion of the roof runoff from the proposed building is conveyed via a roof-leader system and is pretreated with leaf-screens before discharging into a large-scale bioretention basin. While the runoff from the eastern portion of the captured Motor Vehicle Surface is collected and pretreated via a small-scale bioretention basin and discharges into the same large-scale bioretention basin as the roof. The large-scale bioretention basin discharges into the other existing drainage system that discharges into the Assunpink Creek.

Portions of onsite pervious and onsite impervious areas sheet flow into inlets within the Enterprise Drive right-of-way, which then discharges into the stormwater system that has been relocated through the subject property before discharging into the Assunpink Creek. The Time of Concentration used for this area has been calculated utilizing the McCuen-Spiess formula for each individual sub-area.

Proposed Analysis With Rainfall Adjustment Factor			
STORM EVENT	POINT OF ANALYSIS "POA-1"		
	ALLOWABLE	PROPOSED	COMPLY
2-Year	8.21 cfs	5.85 cfs	YES
10-Year	20.92 cfs	10.74 cfs	YES
100-Year	43.69 cfs	30.55 cfs	YES

Proposed Analysis With Rainfall 2100 Projected Factor			
STORM EVENT	POINT OF ANALYSIS "POA-1"		
	ALLOWABLE	PROPOSED	COMPLY
2-Year	10.88 cfs	7.25 cfs	YES
10-Year	26.74 cfs	13.13 cfs	YES
100-Year	62.90 cfs	61.95 cfs	YES

1.6 STORMWATER COLLECTION SYSTEM

The stormwater collection system consists of proposed stormwater inlets and other structures connected by high density polyethylene (HDPE) pipes. All storm sewer pipes upstream of the detention basin have been sized to pass the peak flow rates of a 25-year storm; and there are storm sewer pipes downstream of the detention facility which acts as the discharge pipe sized for the 100-year storm.

Pipe Capacity calculations can be found in section 6 of this report.

1.7 GROUNDWATER RECHARGE ANALYSIS

The development analyzed in this report is within the "Urban Redevelopment Area" and can be found within the Metropolitan Planning Area (PA-1) as a predeveloped site. According to N.J.A.C. 7:8-5.4.b.2: "This groundwater recharge requirement does not apply to projects within the "urban redevelopment area", therefore groundwater recharge analysis is not required for this site.

1.8 WATER QUALITY STANDARDS

The water quality design is based on a 1.25", 2-hour design storm, in accordance with NJDEP Stormwater Management Regulations. The TR-55 method was utilized for the water quality analysis in accordance with the NJDEP Best Management Practices Manual.

This major development project requires a minimum of 80% TSS Removal of the total proposed motor vehicle surface area, and a minimum of 50% of the total Redeveloped area. This requirement is achieved by directing the western portion of regulated motor vehicle surface area, 1.146 ac, and a total area of 1.455 ac through a small-scale bioretention basin. The eastern portion of regulated motor vehicle surface area (and total area) of 0.695 ac is conveyed through a second small-scale bioretention basin. Each of the small-scale bioretention basins provide 80% TSS removal.

The design criteria for the proposed Small-scale Bioretention Basin as described in the NJ BMP manual chapter 9.7 is summarized as follows:

CRITERIA	PROPOSED Small-scale Bioretention Basin #112	PROPOSED Small-scale Bioretention Basin #206
TSS Removal Rate	80%	80%
Design Parameters	• See Construction Details	• See Construction Details
Total Area Tributary	1.397 Ac.	0.773 Ac.
Pavement Area to be treated	1.128 Ac.	0.638 Ac.
Wq. Volume Capacity	4,683 ft ³	2,640 ft ³
Maximum Storage (100-yr)	13,929 ft ³	6,069 ft ³
Wq. Elevation	45.80	45.82
Overflow Elevation	48.50	48.50
Groundwater Recharge	No	No
Infiltration rate	N/A	N/A
Bottom Elevation	44.83	44.83
Bottom Area	2,461 ft ²	1,435 ft ²
Time to empty	6.528 hrs	6.312 hrs

All hydrograph calculations using the NJ Quality Storm ($i=1.25''$ in 2 hours) and details have been attached under Water Quality section 8 in this report.

The water quality design is based on a 1.25'', 2-hour design storm, in accordance with NJDEP Stormwater Management Regulations. The TR-55 method was utilized for the water quality analysis in accordance with the NJDEP Best Management Practices Manual.

1.9 GREEN INFRASTRUCTURE STANDARDS

Per N.J.A.C. 7:8-5.2(a), The minimum design and performance standards for groundwater recharge, stormwater runoff quality, and stormwater runoff quantity at N.J.A.C. 7:8-5.4, 5.5, and 5.6 shall be met by incorporating green infrastructure in accordance with N.J.A.C. 7:8- 5.3. As described above, the proposed improvements are exempt from groundwater recharge and but must meet stormwater runoff quality standards. As such, Green Infrastructure is required in the design to address stormwater quality standards. The proposed improvements incorporate two (2) small-scale bioretention basins as part of the stormwater quality design and two (2) large-scale bioretention basins as part of the stormwater quantity design; which are Green Infrastructure components in accordance with the standards

1.10 SOIL EROSION AND SEDIMENT CONTROL

The Soil Erosion and Sediment Control Measures for this project include appropriately installed perimeter silt fencing, inlet filters, and permanent seeding and mulching. All provisions are to be

in accordance with the “Standards for Soil Erosion and Sediment Control in New Jersey, last revised 2014”.

The Soil Erosion and Sediment Control Measures for this project include appropriately installed perimeter silt fencing, inlet filters, and permanent seeding and mulching. All provisions are to be in accordance with the “Standards for Soil Erosion and Sediment Control in New Jersey, last revised 2014”.

Conduit outlet protection has been designed per Standards for Soil Erosion and Sediment Control in New Jersey Engineering Standards 12-1 for Flared End Sections. Calculations and details are provided on Section 8 of this report.

Emergency Spillways have been designed to perform under the Adjusted 100 Year Storm plus 50%. As stated in the Standards for Soil Erosion and sediment control in New Jersey table 11-1, the allowable velocity for clay and fine gravel is 5.0 ft/s. It was confirmed that the velocities at the spillway were acceptable and that water elevation remained well below the top of berm elevations. These calculations are shown in Section 7 of the Appendix and can be summarized as follows:

Basin 104: 50'X 7' Spillway; velocity=1.55 fps

Basin 112: 20' X 8' Spillway; velocity= 1.07 fps

Basin 203: 50'X 7' Spillway; velocity= 1.40 fps

Basin 206: 16'X 6' Spillway; velocity= 0.33 fps

1.11 CONCLUSION

This Stormwater Management Plan report has been prepared to describe the existing and proposed development conditions of the site in question.

The project uses different engineering practices to meet the standards for groundwater recharge, water quality, and green infrastructure as set forth in N.J.A.C. 7:8. Compliance with these standards is designed to minimize the impact of development on the receiving drainage areas.

2. EXISTING & PROPOSED RUNOFF MODELS

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.

CITY OF TRENTON



BLOCK 23203, LOT 1

BLOCK 23102 LOTS 2 & 9

TOWNSHIP OF LAWRENCE

BLOCK 602, LOTS 1 & 2


MERCER COUNTY, NEW JERSEY



Subcat



Reach






Pond



Link

Routing Diagram for 2025.08.19 Existing Conditions

Prepared by REDCOM Engineering & Const, Printed 9/16/2025
HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC



Routing Diagram for 2025.09.14 Proposed Conditions
 Prepared by REDCOM Engineering & Const, Printed 9/23/2025
 HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

3.1 RUNOFF & HYDROGRAPH ANALYSIS: EXISTING 2-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 9

Summary for Subcatchment 1AOiD: POA-1AOi (Disturbed)

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 1.95 cfs @ 12.09 hrs, Volume= 0.124 af, Depth> 2.89"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct

Subcatchment 1AOiD: POA-1AOi (Disturbed)



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 10


Summary for Subcatchment 1AOpD: POA-1AOp (Disturbed)

Runoff = 10.56 cfs @ 12.39 hrs, Volume= 1.097 af, Depth> 1.32"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
308,492	79	Woods/grass comb., Good, HSG D
47,960	80	>75% Grass cover, Good, HSG D
78,103	80	>75% Grass cover, Good, HSG D
434,555	79	Weighted Average
434,555		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpD: POA-1AOp (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 11


Summary for Subcatchment 1AOpU: POA-1AOp (Undisturbed)

Runoff = 2.74 cfs @ 12.37 hrs, Volume= 0.291 af, Depth> 2.15"
Routed to Link 1AOn : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
31,494	79	Woods/grass comb., Good, HSG D
39,291	98	Water Surface, 0% imp, HSG D
70,785	90	Weighted Average
70,785		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpU: POA-1AOp (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 12

Summary for Link 1AOn: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 1.50" for Adj - 2 Yr event


Inflow = 13.68 cfs @ 12.39 hrs, Volume= 1.511 af

Primary = 13.68 cfs @ 12.39 hrs, Volume= 1.511 af, Atten= 0%, Lag= 0.0 min

Routed to Link Adj : Total Point of Analysis

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 1AOn: POA-1 Onsite



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 13

Summary for Link 4L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 1.40" for Adj - 2 Yr event

Inflow = 10.95 cfs @ 12.39 hrs, Volume= 1.221 af


Primary = 10.95 cfs @ 12.39 hrs, Volume= 1.221 af, Atten= 0%, Lag= 0.0 min

Routed to Link 1AOn : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 4L: Disturbed

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 14

Summary for Link Adj: Total Point of Analysis


Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 1.50" for Adj - 2 Yr event

Inflow = 13.68 cfs @ 12.39 hrs, Volume= 1.511 af

Primary = 13.68 cfs @ 12.39 hrs, Volume= 1.511 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link Adj: Total Point of Analysis



3.2 RUNOFF & HYDROGRAPH ANALYSIS: EXISTING 10-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 15

Summary for Subcatchment 1AOiD: POA-1AOi (Disturbed)

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 2.98 cfs @ 12.09 hrs, Volume= 0.191 af, Depth> 4.45"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct

Subcatchment 1AOiD: POA-1AOi (Disturbed)



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 16


Summary for Subcatchment 1AOpD: POA-1AOp (Disturbed)

Runoff = 21.17 cfs @ 12.38 hrs, Volume= 2.202 af, Depth> 2.65"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
308,492	79	Woods/grass comb., Good, HSG D
47,960	80	>75% Grass cover, Good, HSG D
78,103	80	>75% Grass cover, Good, HSG D
434,555	79	Weighted Average
434,555		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpD: POA-1AOp (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 17


Summary for Subcatchment 1AOpU: POA-1AOp (Undisturbed)

Runoff = 4.59 cfs @ 12.37 hrs, Volume= 0.501 af, Depth> 3.70"
Routed to Link 1AOn : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
31,494	79	Woods/grass comb., Good, HSG D
39,291	98	Water Surface, 0% imp, HSG D
70,785	90	Weighted Average
70,785		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpU: POA-1AOp (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 18

Summary for Link 1AOn: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 2.87" for Adj - 10 Yr event


Inflow = 26.36 cfs @ 12.38 hrs, Volume= 2.894 af

Primary = 26.36 cfs @ 12.38 hrs, Volume= 2.894 af, Atten= 0%, Lag= 0.0 min

Routed to Link Adj : Total Point of Analysis

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 1AOn: POA-1 Onsite



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 19


Summary for Link 4L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 2.74" for Adj - 10 Yr event
Inflow = 21.78 cfs @ 12.38 hrs, Volume= 2.393 af
Primary = 21.78 cfs @ 12.38 hrs, Volume= 2.393 af, Atten= 0%, Lag= 0.0 min
Routed to Link 1AOn : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 4L: Disturbed

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025


Page 20

Summary for Link Adj: Total Point of Analysis

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 2.87" for Adj - 10 Yr event
Inflow = 26.36 cfs @ 12.38 hrs, Volume= 2.894 af
Primary = 26.36 cfs @ 12.38 hrs, Volume= 2.894 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link Adj: Total Point of Analysis



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 21


Summary for Subcatchment 1AOiD: POA-1AOi (Disturbed)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.58 cfs @ 12.09 hrs, Volume= 0.231 af, Depth> 5.38"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct

Subcatchment 1AOiD: POA-1AOi (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 22


Summary for Subcatchment 1AOpD: POA-1AOp (Disturbed)

Runoff = 27.76 cfs @ 12.38 hrs, Volume= 2.908 af, Depth> 3.50"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
308,492	79	Woods/grass comb., Good, HSG D
47,960	80	>75% Grass cover, Good, HSG D
78,103	80	>75% Grass cover, Good, HSG D
434,555	79	Weighted Average
434,555		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpD: POA-1AOp (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 23


Summary for Subcatchment 1AOpU: POA-1AOp (Undisturbed)

Runoff = 5.69 cfs @ 12.37 hrs, Volume= 0.627 af, Depth> 4.63"
Routed to Link 1AOn : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
31,494	79	Woods/grass comb., Good, HSG D
39,291	98	Water Surface, 0% imp, HSG D
70,785	90	Weighted Average
70,785		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpU: POA-1AOp (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 24

Summary for Link 1AOn: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 3.73" for Adj - 25 Yr event


Inflow = 34.23 cfs @ 12.37 hrs, Volume= 3.766 af

Primary = 34.23 cfs @ 12.37 hrs, Volume= 3.766 af, Atten= 0%, Lag= 0.0 min

Routed to Link Adj : Total Point of Analysis

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 1AOn: POA-1 Onsite



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 25

Summary for Link 4L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 3.59" for Adj - 25 Yr event

Inflow = 28.54 cfs @ 12.37 hrs, Volume= 3.139 af


Primary = 28.54 cfs @ 12.37 hrs, Volume= 3.139 af, Atten= 0%, Lag= 0.0 min

Routed to Link 1AOn : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 4L: Disturbed

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 26

Summary for Link Adj: Total Point of Analysis


Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 3.73" for Adj - 25 Yr event

Inflow = 34.23 cfs @ 12.37 hrs, Volume= 3.766 af

Primary = 34.23 cfs @ 12.37 hrs, Volume= 3.766 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link Adj: Total Point of Analysis



3.3 RUNOFF & HYDROGRAPH ANALYSIS: EXISTING 100-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 27

Summary for Subcatchment 1AOiD: POA-1AOi (Disturbed)

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 4.98 cfs @ 12.09 hrs, Volume= 0.322 af, Depth> 7.50"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct

Subcatchment 1AOiD: POA-1AOi (Disturbed)



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 28


Summary for Subcatchment 1AOpD: POA-1AOp (Disturbed)

Runoff = 43.32 cfs @ 12.37 hrs, Volume= 4.615 af, Depth> 5.55"
Routed to Link 4L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
308,492	79	Woods/grass comb., Good, HSG D
47,960	80	>75% Grass cover, Good, HSG D
78,103	80	>75% Grass cover, Good, HSG D
434,555	79	Weighted Average
434,555		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpD: POA-1AOp (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 29


Summary for Subcatchment 1AOpU: POA-1AOp (Undisturbed)

Runoff = 8.19 cfs @ 12.37 hrs, Volume= 0.921 af, Depth> 6.80"
Routed to Link 1AOn : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
31,494	79	Woods/grass comb., Good, HSG D
39,291	98	Water Surface, 0% imp, HSG D
70,785	90	Weighted Average
70,785		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
26.6					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
26.6	100	Total			

Subcatchment 1AOpU: POA-1AOp (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 30

Summary for Link 1AOn: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 5.80" for Adj - 100 Yr event


Inflow = 52.56 cfs @ 12.37 hrs, Volume= 5.858 af

Primary = 52.56 cfs @ 12.37 hrs, Volume= 5.858 af, Atten= 0%, Lag= 0.0 min

Routed to Link Adj : Total Point of Analysis

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 1AOn: POA-1 Onsite



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 31


Summary for Link 4L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 5.65" for Adj - 100 Yr event
Inflow = 44.37 cfs @ 12.37 hrs, Volume= 4.937 af
Primary = 44.37 cfs @ 12.37 hrs, Volume= 4.937 af, Atten= 0%, Lag= 0.0 min
Routed to Link 1AOn : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 4L: Disturbed

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025


Page 32

Summary for Link Adj: Total Point of Analysis

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 5.80" for Adj - 100 Yr event
Inflow = 52.56 cfs @ 12.37 hrs, Volume= 5.858 af
Primary = 52.56 cfs @ 12.37 hrs, Volume= 5.858 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link Adj: Total Point of Analysis



3.4 RUNOFF & HYDROGRAPH ANALYSIS: EXISTING 2-YEAR STORM EVENT YEAR 2100 PROJECTION

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 3

Summary for Subcatchment 10iD: POA-10i (Disturbed)

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 2.25 cfs @ 12.09 hrs, Volume= 0.143 af, Depth> 3.34"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4					Direct Entry,

Subcatchment 10iD: POA-10i (Disturbed)



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 4


Summary for Subcatchment 1OpD: POA-1Op (Disturbed)

Runoff = 13.93 cfs @ 12.37 hrs, Volume= 1.400 af, Depth> 1.68"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (ac)	CN	Description
7.082	79	Woods/grass comb., Good, HSG D
1.101	80	>75% Grass cover, Good, HSG D
1.793	80	>75% Grass cover, Good, HSG D
9.976	79	Weighted Average
9.976		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 1OpD: POA-1Op (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 5


Summary for Subcatchment 10pU: POA-10p (Undisturbed)

Runoff = 3.37 cfs @ 12.35 hrs, Volume= 0.351 af, Depth> 2.59"
Routed to Link 1On : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (ac)	CN	Description
0.723	79	Woods/grass comb., Good, HSG D
0.902	98	Water Surface, 0% imp, HSG D
1.625	90	Weighted Average
1.625		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 10pU: POA-10p (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 6

Summary for Link 10n: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 1.88" for Yr 2100 - 2 Yr event

Inflow = 17.78 cfs @ 12.36 hrs, Volume= 1.894 af

Primary = 14.22 cfs @ 12.36 hrs, Volume= 1.515 af, Atten= 20%, Lag= 0.0 min


Routed to Link 2100 : Total Point of Analysis

Secondary = 3.56 cfs @ 12.36 hrs, Volume= 0.379 af

Routed to Link 2100 : Total Point of Analysis

Primary outflow = Inflow x 0.80, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10n: POA-1 Onsite



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025


Page 7

Summary for Link 5L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 1.77" for Yr 2100 - 2 Yr event
Inflow = 14.41 cfs @ 12.36 hrs, Volume= 1.543 af
Primary = 14.41 cfs @ 12.36 hrs, Volume= 1.543 af, Atten= 0%, Lag= 0.0 min
Routed to Link 1On : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Disturbed



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025


Page 8

Summary for Link 2100: Total Point of Analysis

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 1.88" for Yr 2100 - 2 Yr event
Inflow = 17.78 cfs @ 12.36 hrs, Volume= 1.894 af
Primary = 17.78 cfs @ 12.36 hrs, Volume= 1.894 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 2100: Total Point of Analysis



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 9


Summary for Subcatchment 10iD: POA-10i (Disturbed)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.43 cfs @ 12.09 hrs, Volume= 0.220 af, Depth> 5.12"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4					Direct Entry,

Subcatchment 10iD: POA-10i (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 10


Summary for Subcatchment 1OpD: POA-1Op (Disturbed)

Runoff = 26.78 cfs @ 12.36 hrs, Volume= 2.715 af, Depth> 3.27"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (ac)	CN	Description
7.082	79	Woods/grass comb., Good, HSG D
1.101	80	>75% Grass cover, Good, HSG D
1.793	80	>75% Grass cover, Good, HSG D
9.976	79	Weighted Average
9.976		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 1OpD: POA-1Op (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 11


Summary for Subcatchment 10pU: POA-10p (Undisturbed)

Runoff = 5.55 cfs @ 12.35 hrs, Volume= 0.593 af, Depth> 4.38"
Routed to Link 1On : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (ac)	CN	Description
0.723	79	Woods/grass comb., Good, HSG D
0.902	98	Water Surface, 0% imp, HSG D
1.625	90	Weighted Average
1.625		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 10pU: POA-10p (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 12

Summary for Link 10n: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 3.49" for Yr 2100 - 10 Yr event

Inflow = 33.08 cfs @ 12.35 hrs, Volume= 3.528 af

Primary = 26.46 cfs @ 12.35 hrs, Volume= 2.823 af, Atten= 20%, Lag= 0.0 min

Routed to Link 2100 : Total Point of Analysis


Secondary = 6.62 cfs @ 12.35 hrs, Volume= 0.706 af

Routed to Link 2100 : Total Point of Analysis

Primary outflow = Inflow x 0.80, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10n: POA-1 Onsite

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 13


Summary for Link 5L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 3.36" for Yr 2100 - 10 Yr event
Inflow = 27.53 cfs @ 12.35 hrs, Volume= 2.935 af
Primary = 27.53 cfs @ 12.35 hrs, Volume= 2.935 af, Atten= 0%, Lag= 0.0 min
Routed to Link 1On : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Disturbed

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 14

Summary for Link 2100: Total Point of Analysis


Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 3.49" for Yr 2100 - 10 Yr event

Inflow = 33.08 cfs @ 12.35 hrs, Volume= 3.528 af

Primary = 33.08 cfs @ 12.35 hrs, Volume= 3.528 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 2100: Total Point of Analysis



2025.11.21 Existing Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 15


Summary for Subcatchment 10iD: POA-10i (Disturbed)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 6.55 cfs @ 12.09 hrs, Volume= 0.423 af, Depth> 9.85"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4					Direct Entry,

Subcatchment 10iD: POA-10i (Disturbed)

2025.11.21 Existing Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 16


Summary for Subcatchment 1OpD: POA-1Op (Disturbed)

Runoff = 62.36 cfs @ 12.35 hrs, Volume= 6.568 af, Depth> 7.90"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (ac)	CN	Description
7.082	79	Woods/grass comb., Good, HSG D
1.101	80	>75% Grass cover, Good, HSG D
1.793	80	>75% Grass cover, Good, HSG D
9.976	79	Weighted Average
9.976		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 1OpD: POA-1Op (Disturbed)

2025.11.21 Existing Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 17


Summary for Subcatchment 10pU: POA-10p (Undisturbed)

Runoff = 11.24 cfs @ 12.35 hrs, Volume= 1.245 af, Depth> 9.20"
Routed to Link 1On : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (ac)	CN	Description
0.723	79	Woods/grass comb., Good, HSG D
0.902	98	Water Surface, 0% imp, HSG D
1.625	90	Weighted Average
1.625		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 10pU: POA-10p (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025


Page 18

Summary for Link 10n: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 8.16" for Yr 2100 - 100 Yr event
Inflow = 75.07 cfs @ 12.35 hrs, Volume= 8.236 af
Primary = 60.05 cfs @ 12.35 hrs, Volume= 6.589 af, Atten= 20%, Lag= 0.0 min
Routed to Link 2100 : Total Point of Analysis
Secondary = 15.01 cfs @ 12.35 hrs, Volume= 1.647 af
Routed to Link 2100 : Total Point of Analysis

Primary outflow = Inflow x 0.80, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10n: POA-1 Onsite




Summary for Link 5L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 8.00" for Yr 2100 - 100 Yr event
 Inflow = 63.83 cfs @ 12.35 hrs, Volume= 6.990 af
 Primary = 63.83 cfs @ 12.35 hrs, Volume= 6.990 af, Atten= 0%, Lag= 0.0 min
 Routed to Link 1On : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Disturbed




Summary for Link 2100: Total Point of Analysis

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 8.16" for Yr 2100 - 100 Yr event
 Inflow = 75.07 cfs @ 12.35 hrs, Volume= 8.236 af
 Primary = 75.07 cfs @ 12.35 hrs, Volume= 8.236 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 2100: Total Point of Analysis



3.5 RUNOFF & HYDROGRAPH ANALYSIS: EXISTING 10-YEAR STORM EVENT YEAR 2100 PROJECTION

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 9

Summary for Subcatchment 10iD: POA-10i (Disturbed)

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 3.43 cfs @ 12.09 hrs, Volume= 0.220 af, Depth> 5.12"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4					Direct Entry,

Subcatchment 10iD: POA-10i (Disturbed)



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 10


Summary for Subcatchment 1OpD: POA-1Op (Disturbed)

Runoff = 26.78 cfs @ 12.36 hrs, Volume= 2.715 af, Depth> 3.27"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (ac)	CN	Description
7.082	79	Woods/grass comb., Good, HSG D
1.101	80	>75% Grass cover, Good, HSG D
1.793	80	>75% Grass cover, Good, HSG D
9.976	79	Weighted Average
9.976		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 1OpD: POA-1Op (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 11


Summary for Subcatchment 10pU: POA-10p (Undisturbed)

Runoff = 5.55 cfs @ 12.35 hrs, Volume= 0.593 af, Depth> 4.38"
Routed to Link 1On : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (ac)	CN	Description
0.723	79	Woods/grass comb., Good, HSG D
0.902	98	Water Surface, 0% imp, HSG D
1.625	90	Weighted Average
1.625		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 10pU: POA-10p (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025


Page 12

Summary for Link 10n: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 3.49" for Yr 2100 - 10 Yr event
Inflow = 33.08 cfs @ 12.35 hrs, Volume= 3.528 af
Primary = 26.46 cfs @ 12.35 hrs, Volume= 2.823 af, Atten= 20%, Lag= 0.0 min
Routed to Link 2100 : Total Point of Analysis
Secondary = 6.62 cfs @ 12.35 hrs, Volume= 0.706 af
Routed to Link 2100 : Total Point of Analysis

Primary outflow = Inflow x 0.80, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10n: POA-1 Onsite



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 13


Summary for Link 5L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 3.36" for Yr 2100 - 10 Yr event
Inflow = 27.53 cfs @ 12.35 hrs, Volume= 2.935 af
Primary = 27.53 cfs @ 12.35 hrs, Volume= 2.935 af, Atten= 0%, Lag= 0.0 min
Routed to Link 1On : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Disturbed

Hydrograph



2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025


Page 14

Summary for Link 2100: Total Point of Analysis

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 3.49" for Yr 2100 - 10 Yr event
Inflow = 33.08 cfs @ 12.35 hrs, Volume= 3.528 af
Primary = 33.08 cfs @ 12.35 hrs, Volume= 3.528 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 2100: Total Point of Analysis



3.6 RUNOFF & HYDROGRAPH ANALYSIS: EXISTING 100-YEAR STORM EVENT YEAR 2100 PROJECTION

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 15


Summary for Subcatchment 10iD: POA-10i (Disturbed)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 6.55 cfs @ 12.09 hrs, Volume= 0.423 af, Depth> 9.85"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (ac)	CN	Description
0.515	98	Paved parking, HSG D
0.515		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4					Direct Entry,

Subcatchment 10iD: POA-10i (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 16


Summary for Subcatchment 1OpD: POA-1Op (Disturbed)

Runoff = 62.36 cfs @ 12.35 hrs, Volume= 6.568 af, Depth> 7.90"
Routed to Link 5L : Disturbed

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (ac)	CN	Description
7.082	79	Woods/grass comb., Good, HSG D
1.101	80	>75% Grass cover, Good, HSG D
1.793	80	>75% Grass cover, Good, HSG D
9.976	79	Weighted Average
9.976		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 1OpD: POA-1Op (Disturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 17


Summary for Subcatchment 10pU: POA-10p (Undisturbed)

Runoff = 11.24 cfs @ 12.35 hrs, Volume= 1.245 af, Depth> 9.20"
Routed to Link 1On : POA-1 Onsite

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (ac)	CN	Description
0.723	79	Woods/grass comb., Good, HSG D
0.902	98	Water Surface, 0% imp, HSG D
1.625	90	Weighted Average
1.625		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
25.1					Direct Entry, Tc Direct
0.0	100	0.7350	80.90	571.82	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
25.1	100	Total			

Subcatchment 10pU: POA-10p (Undisturbed)

2025.11.21 Existing Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025


Page 18

Summary for Link 10n: POA-1 Onsite

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 8.16" for Yr 2100 - 100 Yr event
Inflow = 75.07 cfs @ 12.35 hrs, Volume= 8.236 af
Primary = 60.05 cfs @ 12.35 hrs, Volume= 6.589 af, Atten= 20%, Lag= 0.0 min
Routed to Link 2100 : Total Point of Analysis
Secondary = 15.01 cfs @ 12.35 hrs, Volume= 1.647 af
Routed to Link 2100 : Total Point of Analysis

Primary outflow = Inflow x 0.80, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10n: POA-1 Onsite




Summary for Link 5L: Disturbed

Inflow Area = 10.491 ac, 4.91% Impervious, Inflow Depth > 8.00" for Yr 2100 - 100 Yr event
 Inflow = 63.83 cfs @ 12.35 hrs, Volume= 6.990 af
 Primary = 63.83 cfs @ 12.35 hrs, Volume= 6.990 af, Atten= 0%, Lag= 0.0 min
 Routed to Link 1On : POA-1 Onsite

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 5L: Disturbed




Summary for Link 2100: Total Point of Analysis

Inflow Area = 12.116 ac, 4.25% Impervious, Inflow Depth > 8.16" for Yr 2100 - 100 Yr event
 Inflow = 75.07 cfs @ 12.35 hrs, Volume= 8.236 af
 Primary = 75.07 cfs @ 12.35 hrs, Volume= 8.236 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 2100: Total Point of Analysis



4.1 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 2-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 27

Summary for Subcatchment 1S: west Roof to Basin #104

[47] Hint: Peak is 2335% of capacity of segment #2

[47] Hint: Peak is 1084% of capacity of segment #3

[47] Hint: Peak is 598% of capacity of segment #4

[47] Hint: Peak is 411% of capacity of segment #5

[47] Hint: Peak is 227% of capacity of segment #6

[47] Hint: Peak is 125% of capacity of segment #7

Runoff = 9.26 cfs @ 12.13 hrs, Volume= 0.705 af, Depth> 3.12"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

	Area (sf)	CN	Description		
*	117,968	98	bldg		
	117,968		100.00% Impervious Area		

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	2.87	2.25	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	3.33	4.09	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.4	952	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 28

Subcatchment 1S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 29

Summary for Subcatchment 9S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

Runoff = 2.58 cfs @ 12.08 hrs, Volume= 0.169 af, Depth> 3.13"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.1	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 30

Subcatchment 9S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 31

Summary for Subcatchment 10S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

Runoff = 4.43 cfs @ 12.08 hrs, Volume= 0.295 af, Depth> 3.13"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, RCP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.6	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 32

Subcatchment 10S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 33

Summary for Subcatchment 22S: east Roof to Basin #203

[47] Hint: Peak is 2067% of capacity of segment #2

[47] Hint: Peak is 960% of capacity of segment #3

[47] Hint: Peak is 529% of capacity of segment #4

[47] Hint: Peak is 326% of capacity of segment #5

[47] Hint: Peak is 180% of capacity of segment #6

[47] Hint: Peak is 180% of capacity of segment #7

Runoff = 8.20 cfs @ 12.13 hrs, Volume= 0.621 af, Depth> 3.12"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

	Area (sf)	CN	Description
*	103,932	98	bldg
	103,932		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.2	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 34

Subcatchment 22S: east Roof to Basin #203



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 35

Summary for Subcatchment 27S: PATH

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 1.77 cfs @ 12.06 hrs, Volume= 0.117 af, Depth> 3.13"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct

Subcatchment 27S: PATH



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 36

Summary for Subcatchment 28S: Rest of the grass

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 4.28 cfs @ 12.10 hrs, Volume= 0.253 af, Depth> 1.53"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Direct

Subcatchment 28S: Rest of the grass



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 37


Summary for Subcatchment 29S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.78 cfs @ 12.10 hrs, Volume= 0.049 af, Depth> 2.23"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	287	Total			

Subcatchment 29S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 38


Summary for Subcatchment 30S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.49 cfs @ 12.10 hrs, Volume= 0.155 af, Depth> 2.23"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	257	Total			

Subcatchment 30S: Grass in basin

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 39


Summary for Subcatchment 31S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.00 cfs @ 12.10 hrs, Volume= 0.124 af, Depth> 2.23"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	263	Total			

Subcatchment 31S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 40

Summary for Subcatchment 39S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.36 cfs @ 12.10 hrs, Volume= 0.023 af, Depth> 2.23"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 41

Subcatchment 39S: Grass in basin



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 42

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.26' @ 23.90 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 2.63" for Adj - 2 Yr event
 Inflow = 12.10 cfs @ 12.13 hrs, Volume= 1.084 af
 Outflow = 0.21 cfs @ 21.88 hrs, Volume= 0.151 af, Atten= 98%, Lag= 584.9 min
 Primary = 0.21 cfs @ 21.88 hrs, Volume= 0.151 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.24' @ 21.88 hrs Surf.Area= 20,611 sf Storage= 40,754 cf

Plug-Flow detention time= 664.4 min calculated for 0.151 af (14% of inflow)
 Center-of-Mass det. time= 378.7 min (1,174.5 - 795.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 43

Primary OutFlow Max=0.21 cfs @ 21.88 hrs HW=46.24' (Free Discharge)


- ↑ 1=Culvert (Passes 0.21 cfs of 9.87 cfs potential flow)
- ↑ 3=Orifice/Grate (Controls 0.00 cfs)
- ↑ 4=Orifice/Grate (Controls 0.00 cfs)
- ↑ 5=Orifice/Grate (Orifice Controls 0.21 cfs @ 2.43 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- ↑ 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 39P: Basin 104

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 44

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 0.38' @ 18.45 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 2.74" for Adj - 2 Yr event
 Inflow = 10.89 cfs @ 12.12 hrs, Volume= 0.875 af
 Outflow = 0.26 cfs @ 17.17 hrs, Volume= 0.216 af, Atten= 98%, Lag= 302.5 min
 Primary = 0.26 cfs @ 17.17 hrs, Volume= 0.216 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.35' @ 17.17 hrs Surf.Area= 15,084 sf Storage= 30,152 cf

Plug-Flow detention time= 529.0 min calculated for 0.216 af (25% of inflow)
 Center-of-Mass det. time= 329.4 min (1,110.1 - 780.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 45


Primary OutFlow Max=0.26 cfs @ 17.17 hrs HW=46.35' (Free Discharge)

- 1=Culvert (Passes 0.26 cfs of 29.46 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.01 cfs @ 0.73 fps)
- 5=Orifice/Grate (Orifice Controls 0.25 cfs @ 2.89 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 46

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 2.98" for Adj - 2 Yr event
 Inflow = 2.93 cfs @ 12.08 hrs, Volume= 0.192 af
 Outflow = 1.00 cfs @ 12.22 hrs, Volume= 0.129 af, Atten= 66%, Lag= 8.2 min
 Primary = 1.00 cfs @ 12.22 hrs, Volume= 0.129 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.93' @ 12.22 hrs Surf.Area= 1,603 sf Storage= 4,298 cf

Plug-Flow detention time= 211.0 min calculated for 0.129 af (67% of inflow)
 Center-of-Mass det. time= 111.4 min (871.0 - 759.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 47

Primary OutFlow Max=0.99 cfs @ 12.22 hrs HW=46.93' (Free Discharge)


- 1=Culvert (Passes 0.99 cfs of 7.45 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.58 cfs @ 2.97 fps)
- 5=Orifice/Grate (Orifice Controls 0.41 cfs @ 4.68 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 43P: Basin 206

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 48

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 2.96" for Adj - 2 Yr event
 Inflow = 5.20 cfs @ 12.09 hrs, Volume= 0.344 af
 Outflow = 0.92 cfs @ 12.48 hrs, Volume= 0.224 af, Atten= 82%, Lag= 23.5 min
 Primary = 0.92 cfs @ 12.48 hrs, Volume= 0.224 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.95' @ 12.48 hrs Surf.Area= 3,654 sf Storage= 8,596 cf

Plug-Flow detention time= 252.2 min calculated for 0.224 af (65% of inflow)
 Center-of-Mass det. time= 149.7 min (911.0 - 761.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 49

Primary OutFlow Max=0.92 cfs @ 12.48 hrs HW=46.94' (Free Discharge)


- 1=Culvert (Passes 0.92 cfs of 7.52 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.51 cfs @ 2.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.41 cfs @ 4.71 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 44P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 50

Summary for Link 2A: POA 1 (Adj)


Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 0.79" for Adj - 2 Yr event

Inflow = 5.85 cfs @ 12.09 hrs, Volume= 0.738 af

Primary = 5.85 cfs @ 12.09 hrs, Volume= 0.738 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 2A: POA 1 (Adj)



4.2 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 10-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 51

Summary for Subcatchment 1S: west Roof to Basin #104

[47] Hint: Peak is 3566% of capacity of segment #2

[47] Hint: Peak is 1656% of capacity of segment #3

[47] Hint: Peak is 913% of capacity of segment #4

[47] Hint: Peak is 628% of capacity of segment #5

[47] Hint: Peak is 346% of capacity of segment #6

[47] Hint: Peak is 190% of capacity of segment #7

Runoff = 14.15 cfs @ 12.13 hrs, Volume= 1.096 af, Depth> 4.86"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

	Area (sf)	CN	Description
*	117,968	98	bldg
	117,968		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	2.87	2.25	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	3.33	4.09	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.4	952	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 52

Subcatchment 1S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 53

Summary for Subcatchment 9S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

Runoff = 3.94 cfs @ 12.08 hrs, Volume= 0.264 af, Depth> 4.86"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.1	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 54

Subcatchment 9S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 55

Summary for Subcatchment 10S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 147% of capacity of segment #2

[47] Hint: Peak is 105% of capacity of segment #3

Runoff = 6.77 cfs @ 12.08 hrs, Volume= 0.459 af, Depth> 4.86"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, RCP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.6	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 56

Subcatchment 10S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 57

Summary for Subcatchment 22S: east Roof to Basin #203

[47] Hint: Peak is 3157% of capacity of segment #2

[47] Hint: Peak is 1466% of capacity of segment #3

[47] Hint: Peak is 808% of capacity of segment #4

[47] Hint: Peak is 497% of capacity of segment #5

[47] Hint: Peak is 274% of capacity of segment #6

[47] Hint: Peak is 274% of capacity of segment #7

Runoff = 12.52 cfs @ 12.13 hrs, Volume= 0.966 af, Depth> 4.86"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

	Area (sf)	CN	Description
*	103,932	98	bldg
	103,932		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.2	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 58

Subcatchment 22S: east Roof to Basin #203



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 59

Summary for Subcatchment 27S: PATH

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 2.70 cfs @ 12.06 hrs, Volume= 0.182 af, Depth> 4.86"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct

Subcatchment 27S: PATH



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 60

Summary for Subcatchment 28S: Rest of the grass

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 8.29 cfs @ 12.10 hrs, Volume= 0.494 af, Depth> 2.98"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Direct

Subcatchment 28S: Rest of the grass



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 61


Summary for Subcatchment 29S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.32 cfs @ 12.10 hrs, Volume= 0.085 af, Depth> 3.87"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	287	Total			

Subcatchment 29S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 62


Summary for Subcatchment 30S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 4.20 cfs @ 12.10 hrs, Volume= 0.269 af, Depth> 3.87"
Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	257	Total			

Subcatchment 30S: Grass in basin

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 63


Summary for Subcatchment 31S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.37 cfs @ 12.10 hrs, Volume= 0.216 af, Depth> 3.87"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	263	Total			

Subcatchment 31S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 64

Summary for Subcatchment 39S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.61 cfs @ 12.10 hrs, Volume= 0.039 af, Depth> 3.87"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 65

Subcatchment 39S: Grass in basin



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 66

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.44' @ 21.65 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 4.34" for Adj - 10 Yr event
 Inflow = 19.36 cfs @ 12.12 hrs, Volume= 1.786 af
 Outflow = 2.12 cfs @ 13.57 hrs, Volume= 0.749 af, Atten= 89%, Lag= 86.7 min
 Primary = 2.12 cfs @ 13.57 hrs, Volume= 0.749 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.72' @ 13.57 hrs Surf.Area= 20,991 sf Storage= 50,681 cf

Plug-Flow detention time= 367.4 min calculated for 0.749 af (42% of inflow)
 Center-of-Mass det. time= 218.3 min (1,005.2 - 786.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 67

Primary OutFlow Max=2.08 cfs @ 13.57 hrs HW=46.72' (Free Discharge)


- 1=Culvert (Passes 2.08 cfs of 11.94 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 0.94 cfs @ 0.86 fps)
- 4=Orifice/Grate (Orifice Controls 0.78 cfs @ 2.08 fps)
- 5=Orifice/Grate (Orifice Controls 0.36 cfs @ 4.12 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 39P: Basin 104

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 68

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 0.70' @ 15.30 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 4.45" for Adj - 10 Yr event
 Inflow = 17.12 cfs @ 12.12 hrs, Volume= 1.421 af
 Outflow = 1.48 cfs @ 13.35 hrs, Volume= 0.713 af, Atten= 91%, Lag= 73.8 min
 Primary = 1.48 cfs @ 13.35 hrs, Volume= 0.713 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.02' @ 13.35 hrs Surf.Area= 16,110 sf Storage= 40,717 cf

Plug-Flow detention time= 340.5 min calculated for 0.713 af (50% of inflow)
 Center-of-Mass det. time= 214.3 min (985.6 - 771.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices	
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf	
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78	
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 69

Primary OutFlow Max=1.48 cfs @ 13.35 hrs HW=47.02' (Free Discharge)


- 1=Culvert (Passes 1.48 cfs of 30.96 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.05 cfs @ 3.01 fps)
- 5=Orifice/Grate (Orifice Controls 0.43 cfs @ 4.90 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 41P: Basin 203

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 70

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 4.70" for Adj - 10 Yr event
 Inflow = 4.53 cfs @ 12.08 hrs, Volume= 0.303 af
 Outflow = 1.63 cfs @ 12.21 hrs, Volume= 0.239 af, Atten= 64%, Lag= 7.6 min
 Primary = 1.63 cfs @ 12.21 hrs, Volume= 0.239 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.81' @ 12.21 hrs Surf.Area= 1,745 sf Storage= 5,763 cf

Plug-Flow detention time= 174.2 min calculated for 0.238 af (79% of inflow)
 Center-of-Mass det. time= 93.4 min (844.6 - 751.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 71

Primary OutFlow Max=1.63 cfs @ 12.21 hrs HW=47.81' (Free Discharge)


- 1=Culvert (Passes 1.63 cfs of 11.90 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.06 cfs @ 5.40 fps)
- 5=Orifice/Grate (Orifice Controls 0.57 cfs @ 6.50 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 43P: Basin 206

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 72

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 4.67" for Adj - 10 Yr event
 Inflow = 8.06 cfs @ 12.09 hrs, Volume= 0.544 af
 Outflow = 1.67 cfs @ 12.37 hrs, Volume= 0.420 af, Atten= 79%, Lag= 16.8 min
 Primary = 1.67 cfs @ 12.37 hrs, Volume= 0.420 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.95' @ 12.37 hrs Surf.Area= 4,060 sf Storage= 12,458 cf

Plug-Flow detention time= 213.9 min calculated for 0.419 af (77% of inflow)
 Center-of-Mass det. time= 130.2 min (883.1 - 752.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 73

Primary OutFlow Max=1.66 cfs @ 12.37 hrs HW=47.95' (Free Discharge)


- 1=Culvert (Passes 1.66 cfs of 12.32 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.08 cfs @ 5.48 fps)
- 5=Orifice/Grate (Orifice Controls 0.59 cfs @ 6.74 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 44P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 74

Summary for Link 2A: POA 1 (Adj)

Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 2.29" for Adj - 10 Yr event


Inflow = 10.74 cfs @ 12.09 hrs, Volume= 2.139 af

Primary = 10.74 cfs @ 12.09 hrs, Volume= 2.139 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 2A: POA 1 (Adj)

Hydrograph



4.3 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 25-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 75

Summary for Subcatchment 1S: west Roof to Basin #104

[47] Hint: Peak is 4293% of capacity of segment #2

[47] Hint: Peak is 1993% of capacity of segment #3

[47] Hint: Peak is 1099% of capacity of segment #4

[47] Hint: Peak is 756% of capacity of segment #5

[47] Hint: Peak is 417% of capacity of segment #6

[47] Hint: Peak is 229% of capacity of segment #7

Runoff = 17.03 cfs @ 12.13 hrs, Volume= 1.328 af, Depth> 5.89"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

	Area (sf)	CN	Description
*	117,968	98	bldg
	117,968		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	2.87	2.25	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	3.33	4.09	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.4	952	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 76

Subcatchment 1S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 77

Summary for Subcatchment 9S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 104% of capacity of segment #2

Runoff = 4.74 cfs @ 12.08 hrs, Volume= 0.319 af, Depth> 5.89"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.1	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 78

Subcatchment 9S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 79

Summary for Subcatchment 10S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 177% of capacity of segment #2

[47] Hint: Peak is 126% of capacity of segment #3

[47] Hint: Peak is 110% of capacity of segment #4

Runoff = 8.15 cfs @ 12.08 hrs, Volume= 0.556 af, Depth> 5.89"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, RCP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.6	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 80

Subcatchment 10S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 81

Summary for Subcatchment 22S: east Roof to Basin #203

[47] Hint: Peak is 3800% of capacity of segment #2

[47] Hint: Peak is 1765% of capacity of segment #3

[47] Hint: Peak is 973% of capacity of segment #4

[47] Hint: Peak is 598% of capacity of segment #5

[47] Hint: Peak is 330% of capacity of segment #6

[47] Hint: Peak is 330% of capacity of segment #7

Runoff = 15.08 cfs @ 12.13 hrs, Volume= 1.170 af, Depth> 5.89"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

	Area (sf)	CN	Description
*	103,932	98	bldg
	103,932		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.2	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 82

Subcatchment 22S: east Roof to Basin #203



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 83

Summary for Subcatchment 27S: PATH

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 3.25 cfs @ 12.06 hrs, Volume= 0.221 af, Depth> 5.89"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct

Subcatchment 27S: PATH



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 84

Summary for Subcatchment 28S: Rest of the grass

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 10.73 cfs @ 12.10 hrs, Volume= 0.647 af, Depth> 3.90"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Direct

Subcatchment 28S: Rest of the grass



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 85


Summary for Subcatchment 29S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.64 cfs @ 12.10 hrs, Volume= 0.107 af, Depth> 4.86"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	287	Total			

Subcatchment 29S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 86


Summary for Subcatchment 30S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 5.20 cfs @ 12.10 hrs, Volume= 0.338 af, Depth> 4.86"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	257	Total			

Subcatchment 30S: Grass in basin

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 87


Summary for Subcatchment 31S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 4.18 cfs @ 12.10 hrs, Volume= 0.272 af, Depth> 4.86"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	263	Total			

Subcatchment 31S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 88

Summary for Subcatchment 39S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.76 cfs @ 12.10 hrs, Volume= 0.050 af, Depth> 4.86"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 89

Subcatchment 39S: Grass in basin



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 90

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.44' @ 23.30 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 5.35" for Adj - 25 Yr event
 Inflow = 26.91 cfs @ 12.14 hrs, Volume= 2.204 af
 Outflow = 5.18 cfs @ 12.60 hrs, Volume= 1.155 af, Atten= 81%, Lag= 27.5 min
 Primary = 5.18 cfs @ 12.60 hrs, Volume= 1.155 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.82' @ 12.60 hrs Surf.Area= 21,075 sf Storage= 52,886 cf

Plug-Flow detention time= 290.2 min calculated for 1.155 af (52% of inflow)
 Center-of-Mass det. time= 162.1 min (943.8 - 781.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 91

Primary OutFlow Max=5.15 cfs @ 12.60 hrs HW=46.82' (Free Discharge)


- 1=Culvert (Passes 5.15 cfs of 12.25 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 3.79 cfs @ 1.36 fps)
- 4=Orifice/Grate (Orifice Controls 0.98 cfs @ 2.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.38 cfs @ 4.41 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 39P: Basin 104

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 92

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 1.01' @ 14.05 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 5.47" for Adj - 25 Yr event
 Inflow = 20.62 cfs @ 12.12 hrs, Volume= 1.746 af
 Outflow = 2.07 cfs @ 13.26 hrs, Volume= 1.023 af, Atten= 90%, Lag= 68.4 min
 Primary = 2.07 cfs @ 13.26 hrs, Volume= 1.023 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.49' @ 13.26 hrs Surf.Area= 16,816 sf Storage= 48,385 cf

Plug-Flow detention time= 315.6 min calculated for 1.023 af (59% of inflow)
 Center-of-Mass det. time= 202.6 min (970.3 - 767.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 93

Primary OutFlow Max=2.07 cfs @ 13.26 hrs HW=47.49' (Free Discharge)


- 1=Culvert (Passes 2.07 cfs of 31.96 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.55 cfs @ 4.45 fps)
- 5=Orifice/Grate (Orifice Controls 0.52 cfs @ 5.90 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 41P: Basin 203

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 94

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 5.73" for Adj - 25 Yr event
 Inflow = 5.47 cfs @ 12.08 hrs, Volume= 0.369 af
 Outflow = 2.04 cfs @ 12.20 hrs, Volume= 0.304 af, Atten= 63%, Lag= 7.2 min
 Primary = 2.04 cfs @ 12.20 hrs, Volume= 0.304 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.22' @ 12.21 hrs Surf.Area= 1,818 sf Storage= 6,497 cf

Plug-Flow detention time= 161.7 min calculated for 0.304 af (82% of inflow)
 Center-of-Mass det. time= 88.4 min (836.4 - 748.0)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 95


Primary OutFlow Max=2.00 cfs @ 12.20 hrs HW=48.22' (Free Discharge)

- 1=Culvert (Passes 2.00 cfs of 13.10 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 0.15 cfs @ 0.47 fps)
- 4=Orifice/Grate (Orifice Controls 1.22 cfs @ 6.22 fps)
- 5=Orifice/Grate (Orifice Controls 0.63 cfs @ 7.20 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 96

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 5.70" for Adj - 25 Yr event
 Inflow = 9.75 cfs @ 12.09 hrs, Volume= 0.663 af
 Outflow = 6.17 cfs @ 12.17 hrs, Volume= 0.537 af, Atten= 37%, Lag= 4.7 min
 Primary = 6.17 cfs @ 12.17 hrs, Volume= 0.537 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.15' @ 12.17 hrs Surf.Area= 4,193 sf Storage= 13,277 cf

Plug-Flow detention time= 195.4 min calculated for 0.537 af (81% of inflow)
 Center-of-Mass det. time= 118.2 min (867.7 - 749.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 97

Primary OutFlow Max=5.60 cfs @ 12.17 hrs HW=48.13' (Free Discharge)


- 1=Culvert (Passes 5.60 cfs of 12.83 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 3.84 cfs @ 1.37 fps)
- 4=Orifice/Grate (Orifice Controls 1.15 cfs @ 5.85 fps)
- 5=Orifice/Grate (Orifice Controls 0.61 cfs @ 7.04 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 44P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 25 Yr Rainfall=6.13"

Printed 12/12/2025

Page 98

Summary for Link 2A: POA 1 (Adj)

Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 3.26" for Adj - 25 Yr event


Inflow = 13.97 cfs @ 12.09 hrs, Volume= 3.045 af

Primary = 13.97 cfs @ 12.09 hrs, Volume= 3.045 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 2A: POA 1 (Adj)

Hydrograph



4.4 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 100-YEAR ADJUSTED STORM EVENT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 99

Summary for Subcatchment 1S: west Roof to Basin #104

[47] Hint: Peak is 5970% of capacity of segment #2

[47] Hint: Peak is 2772% of capacity of segment #3

[47] Hint: Peak is 1529% of capacity of segment #4

[47] Hint: Peak is 1051% of capacity of segment #5

[47] Hint: Peak is 580% of capacity of segment #6

[47] Hint: Peak is 319% of capacity of segment #7

Runoff = 23.69 cfs @ 12.13 hrs, Volume= 1.865 af, Depth> 8.26"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

	Area (sf)	CN	Description
*	117,968	98	bldg
	117,968		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	2.87	2.25	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0040	3.33	4.09	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.4	952	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 100

Subcatchment 1S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 101

Summary for Subcatchment 9S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 144% of capacity of segment #2

Runoff = 6.60 cfs @ 12.08 hrs, Volume= 0.448 af, Depth> 8.27"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.1	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 102

Subcatchment 9S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 103

Summary for Subcatchment 10S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 246% of capacity of segment #2

[47] Hint: Peak is 175% of capacity of segment #3

[47] Hint: Peak is 153% of capacity of segment #4

Runoff = 11.33 cfs @ 12.08 hrs, Volume= 0.780 af, Depth> 8.27"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, RCP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.6	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 104

Subcatchment 10S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 105

Summary for Subcatchment 22S: east Roof to Basin #203

[47] Hint: Peak is 5285% of capacity of segment #2

[47] Hint: Peak is 2454% of capacity of segment #3

[47] Hint: Peak is 1353% of capacity of segment #4

[47] Hint: Peak is 832% of capacity of segment #5

[47] Hint: Peak is 459% of capacity of segment #6

[47] Hint: Peak is 459% of capacity of segment #7

[47] Hint: Peak is 131% of capacity of segment #8

Runoff = 20.97 cfs @ 12.13 hrs, Volume= 1.643 af, Depth> 8.26"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

	Area (sf)	CN	Description		
*	103,932	98	bldg		
	103,932		100.00% Impervious Area		

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.1					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.2	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 106

Subcatchment 22S: east Roof to Basin #203



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 107

Summary for Subcatchment 27S: PATH

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 4.52 cfs @ 12.06 hrs, Volume= 0.310 af, Depth> 8.27"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.9					Direct Entry, Tc Direct

Subcatchment 27S: PATH



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 108

Summary for Subcatchment 28S: Rest of the grass

[49] Hint: $T_c < 2dt$ may require smaller dt


Runoff = 16.44 cfs @ 12.10 hrs, Volume= 1.013 af, Depth> 6.10"
Routed to Link 2A : POA 1 (Adj)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Direct

Subcatchment 28S: Rest of the grass



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 109


Summary for Subcatchment 29S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.36 cfs @ 12.10 hrs, Volume= 0.158 af, Depth> 7.18"
 Routed to Pond 44P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	287	Total			

Subcatchment 29S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 110


Summary for Subcatchment 30S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 7.50 cfs @ 12.10 hrs, Volume= 0.500 af, Depth> 7.18"
 Routed to Pond 39P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36"
					36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75'
					n= 0.013 Corrugated PE, smooth interior
4.1	257	Total			

Subcatchment 30S: Grass in basin

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 111


Summary for Subcatchment 31S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 6.02 cfs @ 12.10 hrs, Volume= 0.402 af, Depth> 7.18"
 Routed to Pond 41P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.1	263	Total			

Subcatchment 31S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 112

Summary for Subcatchment 39S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 1.09 cfs @ 12.10 hrs, Volume= 0.073 af, Depth> 7.18"
 Routed to Pond 43P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.5					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.2	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 113

Subcatchment 39S: Grass in basin



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 114

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.42' @ 23.95 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 7.71" for Adj - 100 Yr event
 Inflow = 42.71 cfs @ 12.12 hrs, Volume= 3.173 af
 Outflow = 13.93 cfs @ 12.32 hrs, Volume= 2.098 af, Atten= 67%, Lag= 12.1 min
 Primary = 13.93 cfs @ 12.32 hrs, Volume= 2.098 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.43' @ 12.32 hrs Surf.Area= 21,564 sf Storage= 65,808 cf

Plug-Flow detention time= 216.8 min calculated for 2.094 af (66% of inflow)
 Center-of-Mass det. time= 112.3 min (885.1 - 772.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 115


Primary OutFlow Max=13.92 cfs @ 12.32 hrs HW=47.43' (Free Discharge)

- 1=Culvert (Inlet Controls 13.92 cfs @ 7.88 fps)
- 3=Orifice/Grate (Passes < 35.81 cfs potential flow)
- 4=Orifice/Grate (Passes < 1.71 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.50 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 116

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 1.20' @ 14.20 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 7.83" for Adj - 100 Yr event
 Inflow = 34.27 cfs @ 12.11 hrs, Volume= 2.500 af
 Outflow = 11.00 cfs @ 12.32 hrs, Volume= 1.750 af, Atten= 68%, Lag= 12.1 min
 Primary = 11.00 cfs @ 12.32 hrs, Volume= 1.750 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.00' @ 12.32 hrs Surf.Area= 17,601 sf Storage= 57,107 cf

Plug-Flow detention time= 257.5 min calculated for 1.746 af (70% of inflow)
 Center-of-Mass det. time= 162.2 min (923.0 - 760.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 117


Primary OutFlow Max=10.86 cfs @ 12.32 hrs HW=47.99' (Free Discharge)

- 1=Culvert (Passes 10.86 cfs of 33.00 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 8.30 cfs @ 1.77 fps)
- 4=Orifice/Grate (Orifice Controls 1.96 cfs @ 5.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.60 cfs @ 6.82 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 118

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 8.10" for Adj - 100 Yr event
 Inflow = 7.65 cfs @ 12.08 hrs, Volume= 0.521 af
 Outflow = 7.94 cfs @ 12.11 hrs, Volume= 0.456 af, Atten= 0%, Lag= 1.7 min
 Primary = 7.94 cfs @ 12.11 hrs, Volume= 0.456 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.44' @ 12.11 hrs Surf.Area= 1,858 sf Storage= 6,896 cf

Plug-Flow detention time= 137.2 min calculated for 0.456 af (87% of inflow)
 Center-of-Mass det. time= 76.2 min (819.1 - 742.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 119

Primary OutFlow Max=7.22 cfs @ 12.11 hrs HW=48.42' (Free Discharge)


- 1=Culvert (Passes 7.22 cfs of 13.63 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 5.28 cfs @ 1.52 fps)
- 4=Orifice/Grate (Orifice Controls 1.29 cfs @ 6.58 fps)
- 5=Orifice/Grate (Orifice Controls 0.66 cfs @ 7.51 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 43P: Basin 206

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 120

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 8.06" for Adj - 100 Yr event
 Inflow = 13.64 cfs @ 12.09 hrs, Volume= 0.938 af
 Outflow = 12.39 cfs @ 12.11 hrs, Volume= 0.808 af, Atten= 9%, Lag= 1.5 min
 Primary = 12.39 cfs @ 12.11 hrs, Volume= 0.808 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.30' @ 12.11 hrs Surf.Area= 4,311 sf Storage= 13,929 cf

Plug-Flow detention time= 164.0 min calculated for 0.806 af (86% of inflow)
 Center-of-Mass det. time= 99.8 min (844.2 - 744.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 121


Primary OutFlow Max=12.12 cfs @ 12.11 hrs HW=48.29' (Free Discharge)

- 1=Culvert (Passes 12.12 cfs of 13.29 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 10.27 cfs @ 1.90 fps)
- 4=Orifice/Grate (Orifice Controls 1.21 cfs @ 6.16 fps)
- 5=Orifice/Grate (Orifice Controls 0.64 cfs @ 7.30 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 44P: Basin 112



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 122

Summary for Link 2A: POA 1 (Adj)

Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 5.53" for Adj - 100 Yr event


Inflow = 30.55 cfs @ 12.28 hrs, Volume= 5.171 af

Primary = 30.55 cfs @ 12.28 hrs, Volume= 5.171 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 2A: POA 1 (Adj)

Hydrograph



4.5 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 2-YEAR STORM EVENT YEAR 2100 PROJECTION

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment11S: WEST CAR/TRUCK Runoff Area=49,320 sf 100.00% Impervious Runoff Depth>3.62"
 Flow Length=507' Tc=2.5 min CN=98 Runoff=5.13 cfs 0.342 af

Subcatchment14S: PATH Runoff Area=19,609 sf 100.00% Impervious Runoff Depth>3.63"
 Tc=0.8 min CN=98 Runoff=2.03 cfs 0.136 af

Subcatchment15S: Rest of the grass Runoff Area=86,744 sf 0.00% Impervious Runoff Depth>1.93"
 Tc=3.3 min CN=80 Runoff=5.46 cfs 0.320 af

Subcatchment16S: Grass in basin and Runoff Area=11,513 sf 0.00% Impervious Runoff Depth>2.69"
 Flow Length=287' Slope=0.0050 '/' Tc=4.0 min CN=89 Runoff=0.95 cfs 0.059 af

Subcatchment17S: Grass in basin Runoff Area=36,400 sf 0.00% Impervious Runoff Depth>2.69"
 Flow Length=257' Slope=0.0050 '/' Tc=3.9 min CN=89 Runoff=3.01 cfs 0.187 af

Subcatchment41S: east Roof to Basin Runoff Area=103,932 sf 100.00% Impervious Runoff Depth>3.62"
 Flow Length=898' Tc=6.0 min CN=98 Runoff=9.48 cfs 0.720 af

Subcatchment42S: EAST TRUCK MVS Runoff Area=28,332 sf 100.00% Impervious Runoff Depth>3.63"
 Flow Length=405' Tc=2.0 min CN=98 Runoff=2.98 cfs 0.196 af

Subcatchment43S: west Roof to Basin Runoff Area=117,968 sf 100.00% Impervious Runoff Depth>3.62"
 Flow Length=892' Slope=0.0050 '/' Tc=5.7 min CN=98 Runoff=10.75 cfs 0.818 af

Subcatchment44S: Grass in basin Runoff Area=5,332 sf 0.00% Impervious Runoff Depth>2.69"
 Flow Length=279' Tc=4.0 min CN=89 Runoff=0.44 cfs 0.027 af

Subcatchment45S: Grass in basin Runoff Area=29,224 sf 0.00% Impervious Runoff Depth>2.69"
 Flow Length=263' Tc=3.9 min CN=89 Runoff=2.41 cfs 0.150 af

Pond 47P: Basin 112 Peak Elev=47.24' Storage=9,699 cf Inflow=6.05 cfs 0.401 af
 Primary=1.20 cfs 0.280 af Secondary=0.00 cfs 0.000 af Outflow=1.20 cfs 0.280 af

Pond 48P: Basin 104 Peak Elev=46.46' Storage=45,291 cf Inflow=14.63 cfs 1.285 af
 Primary=0.36 cfs 0.272 af Secondary=0.00 cfs 0.000 af Outflow=0.36 cfs 0.272 af

Pond 49P: Basin 203 Peak Elev=46.55' Storage=33,213 cf Inflow=12.85 cfs 1.031 af
 Primary=0.51 cfs 0.348 af Secondary=0.00 cfs 0.000 af Outflow=0.51 cfs 0.348 af

Pond 51P: Basin 206 Peak Elev=47.22' Storage=4,761 cf Inflow=3.40 cfs 0.224 af
 Primary=1.24 cfs 0.160 af Secondary=0.00 cfs 0.000 af Outflow=1.24 cfs 0.160 af

Link 24L: POA 1 (2100) Inflow=7.25 cfs 1.076 af
 Primary=7.25 cfs 1.076 af

Total Runoff Area = 11.212 ac Runoff Volume = 2.956 af Average Runoff Depth = 3.16"
34.65% Pervious = 3.885 ac 65.35% Impervious = 7.327 ac

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 8

Summary for Subcatchment 11S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 111% of capacity of segment #2

Runoff = 5.13 cfs @ 12.08 hrs, Volume= 0.342 af, Depth> 3.62"
 Routed to Pond 47P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.5	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 9

Subcatchment 11S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 10


Summary for Subcatchment 14S: PATH[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.03 cfs @ 12.06 hrs, Volume= 0.136 af, Depth> 3.63"
Routed to Link 24L : POA 1 (2100)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct

Subcatchment 14S: PATH

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 11


Summary for Subcatchment 15S: Rest of the grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 5.46 cfs @ 12.10 hrs, Volume= 0.320 af, Depth> 1.93"
Routed to Link 24L : POA 1 (2100)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct

Subcatchment 15S: Rest of the grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 12


Summary for Subcatchment 16S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.95 cfs @ 12.10 hrs, Volume= 0.059 af, Depth> 2.69"
 Routed to Pond 47P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.0	287	Total			

Subcatchment 16S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 13


Summary for Subcatchment 17S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.01 cfs @ 12.10 hrs, Volume= 0.187 af, Depth> 2.69"
Routed to Pond 48P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
3.9	257	Total			

Subcatchment 17S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 14

Summary for Subcatchment 41S: east Roof to Basin #203

[47] Hint: Peak is 2388% of capacity of segment #2

[47] Hint: Peak is 1109% of capacity of segment #3

[47] Hint: Peak is 612% of capacity of segment #4

[47] Hint: Peak is 376% of capacity of segment #5

[47] Hint: Peak is 207% of capacity of segment #6

[47] Hint: Peak is 207% of capacity of segment #7

Runoff = 9.48 cfs @ 12.13 hrs, Volume= 0.720 af, Depth> 3.62"
 Routed to Pond 49P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

	Area (sf)	CN	Description
*	103,932	98	bldg
	103,932		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.0	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 15

Subcatchment 41S: east Roof to Basin #203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 16

Summary for Subcatchment 42S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

Runoff = 2.98 cfs @ 12.08 hrs, Volume= 0.196 af, Depth> 3.63"
 Routed to Pond 51P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.0	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 17

Subcatchment 42S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 18

Summary for Subcatchment 43S: west Roof to Basin #104

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 2709% of capacity of segment #2

[47] Hint: Peak is 694% of capacity of segment #3

[47] Hint: Peak is 427% of capacity of segment #4

[47] Hint: Peak is 235% of capacity of segment #5

[47] Hint: Peak is 145% of capacity of segment #6

Runoff = 10.75 cfs @ 12.12 hrs, Volume= 0.818 af, Depth> 3.62"
 Routed to Pond 48P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

	Area (sf)	CN	Description
*	117,968	98	bldg
	117,968		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
5.7	892	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 19

Subcatchment 43S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 20

Summary for Subcatchment 44S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.44 cfs @ 12.10 hrs, Volume= 0.027 af, Depth> 2.69"
 Routed to Pond 51P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.0	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 21

Subcatchment 44S: Grass in basin



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 22


Summary for Subcatchment 45S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.41 cfs @ 12.10 hrs, Volume= 0.150 af, Depth> 2.69"
Routed to Pond 49P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
3.9	263	Total			

Subcatchment 45S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 23

Summary for Pond 47P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 3.45" for Yr 2100 - 2 Yr event
 Inflow = 6.05 cfs @ 12.09 hrs, Volume= 0.401 af
 Outflow = 1.20 cfs @ 12.38 hrs, Volume= 0.280 af, Atten= 80%, Lag= 17.5 min
 Primary = 1.20 cfs @ 12.38 hrs, Volume= 0.280 af
 Routed to Pond 48P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 48P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.24' @ 12.38 hrs Surf.Area= 3,773 sf Storage= 9,699 cf

Plug-Flow detention time= 235.4 min calculated for 0.279 af (70% of inflow)
 Center-of-Mass det. time= 140.1 min (898.3 - 758.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf
#2	Secondary	48.50'	20.0' long + 0.3 '/' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 24

Primary OutFlow Max=1.20 cfs @ 12.38 hrs HW=47.24' (Free Discharge)


- 1=Culvert (Passes 1.20 cfs of 9.18 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.73 cfs @ 3.71 fps)
- 5=Orifice/Grate (Orifice Controls 0.47 cfs @ 5.40 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 47P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 25

Summary for Pond 48P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 47P by 0.42' @ 21.65 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 3.12" for Yr 2100 - 2 Yr event
 Inflow = 14.63 cfs @ 12.12 hrs, Volume= 1.285 af
 Outflow = 0.36 cfs @ 18.21 hrs, Volume= 0.272 af, Atten= 98%, Lag= 365.8 min
 Primary = 0.36 cfs @ 18.21 hrs, Volume= 0.272 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.46' @ 18.21 hrs Surf.Area= 20,785 sf Storage= 45,291 cf

Plug-Flow detention time= 563.8 min calculated for 0.272 af (21% of inflow)
 Center-of-Mass det. time= 338.1 min (1,130.1 - 792.0)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 26

Primary OutFlow Max=0.36 cfs @ 18.21 hrs HW=46.46' (Free Discharge)


- 1=Culvert (Passes 0.36 cfs of 11.13 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.07 cfs @ 0.79 fps)
- 5=Orifice/Grate (Orifice Controls 0.29 cfs @ 3.32 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 48P: Basin 104

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 27

Summary for Pond 49P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 51P by 0.50' @ 16.35 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 3.23" for Yr 2100 - 2 Yr event
 Inflow = 12.85 cfs @ 12.12 hrs, Volume= 1.031 af
 Outflow = 0.51 cfs @ 14.89 hrs, Volume= 0.348 af, Atten= 96%, Lag= 166.1 min
 Primary = 0.51 cfs @ 14.89 hrs, Volume= 0.348 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.55' @ 14.89 hrs Surf.Area= 15,385 sf Storage= 33,213 cf

Plug-Flow detention time= 447.3 min calculated for 0.347 af (34% of inflow)
 Center-of-Mass det. time= 284.1 min (1,061.3 - 777.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices	
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf	
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78	
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 28

Primary OutFlow Max=0.51 cfs @ 14.89 hrs HW=46.55' (Free Discharge)


- 1=Culvert (Passes 0.51 cfs of 29.91 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.20 cfs @ 1.69 fps)
- 5=Orifice/Grate (Orifice Controls 0.31 cfs @ 3.60 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 49P: Basin 203

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 29

Summary for Pond 51P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 3.48" for Yr 2100 - 2 Yr event
 Inflow = 3.40 cfs @ 12.08 hrs, Volume= 0.224 af
 Outflow = 1.24 cfs @ 12.20 hrs, Volume= 0.160 af, Atten= 63%, Lag= 7.4 min
 Primary = 1.24 cfs @ 12.20 hrs, Volume= 0.160 af
 Routed to Pond 49P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 49P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.22' @ 12.20 hrs Surf.Area= 1,647 sf Storage= 4,761 cf

Plug-Flow detention time= 197.0 min calculated for 0.160 af (72% of inflow)
 Center-of-Mass det. time= 103.5 min (860.1 - 756.5)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 30


Primary OutFlow Max=1.24 cfs @ 12.20 hrs HW=47.22' (Free Discharge)

- 1=Culvert (Passes 1.24 cfs of 9.00 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.77 cfs @ 3.93 fps)
- 5=Orifice/Grate (Orifice Controls 0.47 cfs @ 5.34 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 51P: Basin 206



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 31

Summary for Link 24L: POA 1 (2100)


Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 1.15" for Yr 2100 - 2 Yr event

Inflow = 7.25 cfs @ 12.09 hrs, Volume= 1.076 af

Primary = 7.25 cfs @ 12.09 hrs, Volume= 1.076 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 24L: POA 1 (2100)



4.6 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 10-YEAR STORM EVENT YEAR 2100 PROJECTION

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 32

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment11S: WEST CAR/TRUCK Runoff Area=49,320 sf 100.00% Impervious Runoff Depth>5.61"
 Flow Length=507' Tc=2.5 min CN=98 Runoff=7.81 cfs 0.529 af

Subcatchment14S: PATH Runoff Area=19,609 sf 100.00% Impervious Runoff Depth>5.61"
 Tc=0.8 min CN=98 Runoff=3.10 cfs 0.211 af

Subcatchment15S: Rest of the grass Runoff Area=86,744 sf 0.00% Impervious Runoff Depth>3.64"
 Tc=3.3 min CN=80 Runoff=10.17 cfs 0.605 af

Subcatchment16S: Grass in basin and Runoff Area=11,513 sf 0.00% Impervious Runoff Depth>4.59"
 Flow Length=287' Slope=0.0050 '/' Tc=4.0 min CN=89 Runoff=1.57 cfs 0.101 af

Subcatchment17S: Grass in basin Runoff Area=36,400 sf 0.00% Impervious Runoff Depth>4.59"
 Flow Length=257' Slope=0.0050 '/' Tc=3.9 min CN=89 Runoff=4.97 cfs 0.319 af

Subcatchment41S: east Roof to Basin Runoff Area=103,932 sf 100.00% Impervious Runoff Depth>5.61"
 Flow Length=898' Tc=6.0 min CN=98 Runoff=14.43 cfs 1.115 af

Subcatchment42S: EAST TRUCK MVS Runoff Area=28,332 sf 100.00% Impervious Runoff Depth>5.61"
 Flow Length=405' Tc=2.0 min CN=98 Runoff=4.53 cfs 0.304 af

Subcatchment43S: west Roof to Basin Runoff Area=117,968 sf 100.00% Impervious Runoff Depth>5.61"
 Flow Length=892' Slope=0.0050 '/' Tc=5.7 min CN=98 Runoff=16.37 cfs 1.265 af

Subcatchment44S: Grass in basin Runoff Area=5,332 sf 0.00% Impervious Runoff Depth>4.59"
 Flow Length=279' Tc=4.0 min CN=89 Runoff=0.73 cfs 0.047 af

Subcatchment45S: Grass in basin Runoff Area=29,224 sf 0.00% Impervious Runoff Depth>4.59"
 Flow Length=263' Tc=3.9 min CN=89 Runoff=3.99 cfs 0.256 af

Pond 47P: Basin 112 Peak Elev=48.08' Storage=13,017 cf Inflow=9.34 cfs 0.630 af
 Primary=4.34 cfs 0.506 af Secondary=0.00 cfs 0.000 af Outflow=4.34 cfs 0.506 af

Pond 48P: Basin 104 Peak Elev=46.79' Storage=52,109 cf Inflow=24.00 cfs 2.090 af
 Primary=3.94 cfs 1.044 af Secondary=0.00 cfs 0.000 af Outflow=3.94 cfs 1.044 af

Pond 49P: Basin 203 Peak Elev=47.36' Storage=46,223 cf Inflow=19.80 cfs 1.658 af
 Primary=1.92 cfs 0.939 af Secondary=0.00 cfs 0.000 af Outflow=1.92 cfs 0.939 af

Pond 51P: Basin 206 Peak Elev=48.12' Storage=6,316 cf Inflow=5.23 cfs 0.351 af
 Primary=1.80 cfs 0.286 af Secondary=0.00 cfs 0.000 af Outflow=1.80 cfs 0.286 af

Link 24L: POA 1 (2100) Inflow=13.13 cfs 2.798 af
 Primary=13.13 cfs 2.798 af

Total Runoff Area = 11.212 ac Runoff Volume = 4.753 af Average Runoff Depth = 5.09"
34.65% Pervious = 3.885 ac 65.35% Impervious = 7.327 ac

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 33

Summary for Subcatchment 11S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 169% of capacity of segment #2

[47] Hint: Peak is 121% of capacity of segment #3

[47] Hint: Peak is 105% of capacity of segment #4

Runoff = 7.81 cfs @ 12.08 hrs, Volume= 0.529 af, Depth> 5.61"
 Routed to Pond 47P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.5	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 34

Subcatchment 11S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 35


Summary for Subcatchment 14S: PATH[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.10 cfs @ 12.06 hrs, Volume= 0.211 af, Depth> 5.61"
Routed to Link 24L : POA 1 (2100)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct

Subcatchment 14S: PATH

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 36


Summary for Subcatchment 15S: Rest of the grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 10.17 cfs @ 12.09 hrs, Volume= 0.605 af, Depth> 3.64"
Routed to Link 24L : POA 1 (2100)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct

Subcatchment 15S: Rest of the grass

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 37


Summary for Subcatchment 16S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.57 cfs @ 12.10 hrs, Volume= 0.101 af, Depth> 4.59"
 Routed to Pond 47P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.0	287	Total			

Subcatchment 16S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 38


Summary for Subcatchment 17S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 4.97 cfs @ 12.10 hrs, Volume= 0.319 af, Depth> 4.59"
Routed to Pond 48P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
3.9	257	Total			

Subcatchment 17S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 39

Summary for Subcatchment 41S: east Roof to Basin #203

[47] Hint: Peak is 3637% of capacity of segment #2

[47] Hint: Peak is 1689% of capacity of segment #3

[47] Hint: Peak is 931% of capacity of segment #4

[47] Hint: Peak is 573% of capacity of segment #5

[47] Hint: Peak is 316% of capacity of segment #6

[47] Hint: Peak is 316% of capacity of segment #7

Runoff = 14.43 cfs @ 12.13 hrs, Volume= 1.115 af, Depth> 5.61"
 Routed to Pond 49P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

	Area (sf)	CN	Description
*	103,932	98	bldg
	103,932		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
6.0	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 40

Subcatchment 41S: east Roof to Basin #203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 41

Summary for Subcatchment 42S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

Runoff = 4.53 cfs @ 12.08 hrs, Volume= 0.304 af, Depth> 5.61"
 Routed to Pond 51P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.0	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 42

Subcatchment 42S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 43

Summary for Subcatchment 43S: west Roof to Basin #104

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 4126% of capacity of segment #2

[47] Hint: Peak is 1057% of capacity of segment #3

[47] Hint: Peak is 650% of capacity of segment #4

[47] Hint: Peak is 358% of capacity of segment #5

[47] Hint: Peak is 220% of capacity of segment #6

Runoff = 16.37 cfs @ 12.12 hrs, Volume= 1.265 af, Depth> 5.61"
 Routed to Pond 48P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

	Area (sf)	CN	Description
*	117,968	98	bldg
	117,968		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
5.7	892	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 44

Subcatchment 43S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 45

Summary for Subcatchment 44S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.73 cfs @ 12.10 hrs, Volume= 0.047 af, Depth> 4.59"
 Routed to Pond 51P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.0	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 46

Subcatchment 44S: Grass in basin



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 47


Summary for Subcatchment 45S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.99 cfs @ 12.10 hrs, Volume= 0.256 af, Depth> 4.59"
Routed to Pond 49P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
3.9	263	Total			

Subcatchment 45S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 48

Summary for Pond 47P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 5.42" for Yr 2100 - 10 Yr event
 Inflow = 9.34 cfs @ 12.09 hrs, Volume= 0.630 af
 Outflow = 4.34 cfs @ 12.19 hrs, Volume= 0.506 af, Atten= 54%, Lag= 6.2 min
 Primary = 4.34 cfs @ 12.19 hrs, Volume= 0.506 af
 Routed to Pond 48P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 48P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.08' @ 12.19 hrs Surf.Area= 4,145 sf Storage= 13,017 cf

Plug-Flow detention time= 200.2 min calculated for 0.506 af (80% of inflow)
 Center-of-Mass det. time= 121.1 min (871.4 - 750.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 49

Primary OutFlow Max=4.18 cfs @ 12.19 hrs HW=48.08' (Free Discharge)


- 1=Culvert (Passes 4.18 cfs of 12.71 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 2.44 cfs @ 1.18 fps)
- 4=Orifice/Grate (Orifice Controls 1.13 cfs @ 5.76 fps)
- 5=Orifice/Grate (Orifice Controls 0.61 cfs @ 6.97 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 47P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 50

Summary for Pond 48P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 47P by 0.44' @ 22.85 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 5.08" for Yr 2100 - 10 Yr event
 Inflow = 24.00 cfs @ 12.13 hrs, Volume= 2.090 af
 Outflow = 3.94 cfs @ 12.81 hrs, Volume= 1.044 af, Atten= 84%, Lag= 40.7 min
 Primary = 3.94 cfs @ 12.81 hrs, Volume= 1.044 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.79' @ 12.81 hrs Surf.Area= 21,045 sf Storage= 52,109 cf

Plug-Flow detention time= 306.7 min calculated for 1.044 af (50% of inflow)
 Center-of-Mass det. time= 174.1 min (956.7 - 782.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 51

Primary OutFlow Max=3.94 cfs @ 12.81 hrs HW=46.79' (Free Discharge)


- 1=Culvert (Passes 3.94 cfs of 12.14 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 2.65 cfs @ 1.21 fps)
- 4=Orifice/Grate (Orifice Controls 0.91 cfs @ 2.44 fps)
- 5=Orifice/Grate (Orifice Controls 0.38 cfs @ 4.31 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 48P: Basin 104

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 52

Summary for Pond 49P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 51P by 0.90' @ 14.15 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 5.19" for Yr 2100 - 10 Yr event
 Inflow = 19.80 cfs @ 12.12 hrs, Volume= 1.658 af
 Outflow = 1.92 cfs @ 13.27 hrs, Volume= 0.939 af, Atten= 90%, Lag= 68.9 min
 Primary = 1.92 cfs @ 13.27 hrs, Volume= 0.939 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.36' @ 13.27 hrs Surf.Area= 16,619 sf Storage= 46,223 cf

Plug-Flow detention time= 318.9 min calculated for 0.937 af (56% of inflow)
 Center-of-Mass det. time= 203.7 min (972.1 - 768.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices	
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf	
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78	
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 53


Primary OutFlow Max=1.93 cfs @ 13.27 hrs HW=47.36' (Free Discharge)

- 1=Culvert (Passes 1.93 cfs of 31.68 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.43 cfs @ 4.10 fps)
- 5=Orifice/Grate (Orifice Controls 0.49 cfs @ 5.64 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 49P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 54

Summary for Pond 51P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 5.45" for Yr 2100 - 10 Yr event
 Inflow = 5.23 cfs @ 12.08 hrs, Volume= 0.351 af
 Outflow = 1.80 cfs @ 12.21 hrs, Volume= 0.286 af, Atten= 66%, Lag= 8.0 min
 Primary = 1.80 cfs @ 12.21 hrs, Volume= 0.286 af
 Routed to Pond 49P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 49P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.12' @ 12.21 hrs Surf.Area= 1,799 sf Storage= 6,316 cf

Plug-Flow detention time= 165.8 min calculated for 0.286 af (82% of inflow)
 Center-of-Mass det. time= 89.7 min (838.4 - 748.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 55


Primary OutFlow Max=1.80 cfs @ 12.21 hrs HW=48.12' (Free Discharge)

- 1=Culvert (Passes 1.80 cfs of 12.81 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.18 cfs @ 6.03 fps)
- 5=Orifice/Grate (Orifice Controls 0.61 cfs @ 7.03 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond 51P: Basin 206



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 56

Summary for Link 24L: POA 1 (2100)


Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 3.00" for Yr 2100 - 10 Yr event

Inflow = 13.13 cfs @ 12.09 hrs, Volume= 2.798 af

Primary = 13.13 cfs @ 12.09 hrs, Volume= 2.798 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 24L: POA 1 (2100)



4.7 RUNOFF & HYDROGRAPH ANALYSIS: PROPOSED 100-YEAR STORM EVENT YEAR 2100 PROJECTION

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 57

Time span=0.00-24.00 hrs, dt=0.05 hrs, 481 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment11S: WEST CAR/TRUCK Runoff Area=49,320 sf 100.00% Impervious Runoff Depth>10.90"
Flow Length=507' Tc=2.5 min CN=98 Runoff=14.91 cfs 1.028 af

Subcatchment14S: PATH Runoff Area=19,609 sf 100.00% Impervious Runoff Depth>10.90"
Tc=0.8 min CN=98 Runoff=5.91 cfs 0.409 af

Subcatchment15S: Rest of the grass Runoff Area=86,744 sf 0.00% Impervious Runoff Depth>8.61"
Tc=3.3 min CN=80 Runoff=22.93 cfs 1.429 af

Subcatchment16S: Grass in basin and Runoff Area=11,513 sf 0.00% Impervious Runoff Depth>9.78"
Flow Length=287' Slope=0.0050 '/' Tc=4.0 min CN=89 Runoff=3.18 cfs 0.215 af

Subcatchment17S: Grass in basin Runoff Area=36,400 sf 0.00% Impervious Runoff Depth>9.78"
Flow Length=257' Slope=0.0050 '/' Tc=3.9 min CN=89 Runoff=10.09 cfs 0.681 af

Subcatchment41S: east Roof to Basin Runoff Area=103,932 sf 100.00% Impervious Runoff Depth>10.89"
Flow Length=898' Tc=6.0 min CN=98 Runoff=27.56 cfs 2.165 af

Subcatchment42S: EAST TRUCK MVS Runoff Area=28,332 sf 100.00% Impervious Runoff Depth>10.90"
Flow Length=405' Tc=2.0 min CN=98 Runoff=8.65 cfs 0.591 af

Subcatchment43S: west Roof to Basin Runoff Area=117,968 sf 100.00% Impervious Runoff Depth>10.89"
Flow Length=892' Slope=0.0050 '/' Tc=5.7 min CN=98 Runoff=31.26 cfs 2.458 af

Subcatchment44S: Grass in basin Runoff Area=5,332 sf 0.00% Impervious Runoff Depth>9.78"
Flow Length=279' Tc=4.0 min CN=89 Runoff=1.47 cfs 0.100 af

Subcatchment45S: Grass in basin Runoff Area=29,224 sf 0.00% Impervious Runoff Depth>9.78"
Flow Length=263' Tc=3.9 min CN=89 Runoff=8.10 cfs 0.547 af

Pond 47P: Basin 112 Peak Elev=48.48' Storage=14,729 cf Inflow=18.03 cfs 1.243 af
Primary=13.98 cfs 1.105 af Secondary=0.00 cfs 0.000 af Outflow=13.98 cfs 1.105 af

Pond 48P: Basin 104 Peak Elev=48.32' Storage=85,305 cf Inflow=54.87 cfs 4.244 af
Primary=16.07 cfs 3.146 af Secondary=0.00 cfs 0.000 af Outflow=16.07 cfs 3.146 af

Pond 49P: Basin 203 Peak Elev=48.36' Storage=63,575 cf Inflow=44.33 cfs 3.335 af
Primary=30.74 cfs 2.561 af Secondary=0.00 cfs 0.000 af Outflow=30.74 cfs 2.561 af

Pond 51P: Basin 206 Peak Elev=48.48' Storage=6,973 cf Inflow=10.07 cfs 0.690 af
Primary=9.78 cfs 0.624 af Secondary=0.00 cfs 0.000 af Outflow=9.78 cfs 0.624 af

Link 24L: POA 1 (2100) Inflow=61.95 cfs 7.545 af
Primary=61.95 cfs 7.545 af

Total Runoff Area = 11.212 ac Runoff Volume = 9.622 af Average Runoff Depth = 10.30"
34.65% Pervious = 3.885 ac 65.35% Impervious = 7.327 ac

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 58

Summary for Subcatchment 11S: WEST CAR/TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 323% of capacity of segment #2

[47] Hint: Peak is 230% of capacity of segment #3

[47] Hint: Peak is 201% of capacity of segment #4

Runoff = 14.91 cfs @ 12.08 hrs, Volume= 1.028 af, Depth>10.90"
 Routed to Pond 47P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
49,320	98	Paved roads w/curbs & sewers, HSG D
49,320		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct
0.4	89	0.0051	3.76	4.61	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.6	131	0.0038	3.66	6.48	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
2.5	507	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 59

Subcatchment 11S: WEST CAR/TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 60


Summary for Subcatchment 14S: PATH[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 5.91 cfs @ 12.06 hrs, Volume= 0.409 af, Depth>10.90"
Routed to Link 24L : POA 1 (2100)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
19,609	98	Paved roads w/curbs & sewers, HSG D
19,609		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct

Subcatchment 14S: PATH

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 61


Summary for Subcatchment 15S: Rest of the grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 22.93 cfs @ 12.09 hrs, Volume= 1.429 af, Depth> 8.61"
Routed to Link 24L : POA 1 (2100)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
86,744	80	>75% Grass cover, Good, HSG D
86,744		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct

Subcatchment 15S: Rest of the grass

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 62


Summary for Subcatchment 16S: Grass in basin and surrounding grass[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.18 cfs @ 12.10 hrs, Volume= 0.215 af, Depth> 9.78"
 Routed to Pond 47P : Basin 112

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
11,513	89	<50% Grass cover, Poor, HSG D
11,513		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.1	30	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.0	287	Total			

Subcatchment 16S: Grass in basin and surrounding grass

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 63


Summary for Subcatchment 17S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 10.09 cfs @ 12.10 hrs, Volume= 0.681 af, Depth> 9.78"
Routed to Pond 48P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
36,400	89	<50% Grass cover, Poor, HSG D
36,400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
3.9	257	Total			

Subcatchment 17S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 64

Summary for Subcatchment 41S: east Roof to Basin #203

[47] Hint: Peak is 6945% of capacity of segment #2

[47] Hint: Peak is 3225% of capacity of segment #3

[47] Hint: Peak is 1779% of capacity of segment #4

[47] Hint: Peak is 1094% of capacity of segment #5

[47] Hint: Peak is 603% of capacity of segment #6

[47] Hint: Peak is 603% of capacity of segment #7

[47] Hint: Peak is 172% of capacity of segment #8

Runoff = 27.56 cfs @ 12.13 hrs, Volume= 2.165 af, Depth>10.89"
 Routed to Pond 49P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

	Area (sf)	CN	Description			
*	103,932	98	bldg			
	103,932		100.00% Impervious Area			
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	1.9					Direct Entry, Tc Direct
	0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
	0.4	60	0.0050	2.45	0.85	Pipe Channel, CMP_Round 8" 8.0" Round Area= 0.3 sf Perim= 2.1' r= 0.17' n= 0.013 Corrugated PE, smooth interior
	0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
	0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
	0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
	1.0	215	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
	0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
	0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
	6.0	898	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 65

Subcatchment 41S: east Roof to Basin #203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 66

Summary for Subcatchment 42S: EAST TRUCK MVS

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 189% of capacity of segment #2

[47] Hint: Peak is 116% of capacity of segment #3

[47] Hint: Peak is 116% of capacity of segment #4

Runoff = 8.65 cfs @ 12.08 hrs, Volume= 0.591 af, Depth>10.90"
 Routed to Pond 51P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
28,332	98	Paved roads w/curbs & sewers, HSG D
28,332		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
0.8					Direct Entry, Tc Direct
0.3	70	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
0.2	56	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	30.25	213.85	Pipe Channel, RCP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.011 Concrete pipe, straight & clean
2.0	405	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 67

Subcatchment 42S: EAST TRUCK MVS



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 68

Summary for Subcatchment 43S: west Roof to Basin #104

[49] Hint: Tc<2dt may require smaller dt

[47] Hint: Peak is 7879% of capacity of segment #2

[47] Hint: Peak is 2018% of capacity of segment #3

[47] Hint: Peak is 1241% of capacity of segment #4

[47] Hint: Peak is 684% of capacity of segment #5

[47] Hint: Peak is 421% of capacity of segment #6

Runoff = 31.26 cfs @ 12.12 hrs, Volume= 2.458 af, Depth>10.89"
 Routed to Pond 48P : Basin 104

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

	Area (sf)	CN	Description
*	117,968	98	bldg
	117,968		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.9					Direct Entry, Tc Direct
0.7	90	0.0050	2.02	0.40	Pipe Channel, CMP_Round 6" 6.0" Round Area= 0.2 sf Perim= 1.6' r= 0.13' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	2.84	1.55	Pipe Channel, CMP_Round 10" 10.0" Round Area= 0.5 sf Perim= 2.6' r= 0.21' n= 0.013 Corrugated PE, smooth interior
0.5	90	0.0050	3.21	2.52	Pipe Channel, CMP_Round 12" 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
0.4	90	0.0050	3.72	4.57	Pipe Channel, CMP_Round 15" 15.0" Round Area= 1.2 sf Perim= 3.9' r= 0.31' n= 0.013 Corrugated PE, smooth interior
1.1	275	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.6	257	0.0050	6.67	47.16	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
5.7	892	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 69

Subcatchment 43S: west Roof to Basin #104



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 70

Summary for Subcatchment 44S: Grass in basin

[49] Hint: Tc<2dt may require smaller dt

Runoff = 1.47 cfs @ 12.10 hrs, Volume= 0.100 af, Depth> 9.78"
 Routed to Pond 51P : Basin 206

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
5,332	89	<50% Grass cover, Poor, HSG D
5,332		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.1	16	0.0050	4.20	7.43	Pipe Channel, CMP_Round 18" 18.0" Round Area= 1.8 sf Perim= 4.7' r= 0.38' n= 0.013 Corrugated PE, smooth interior
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
4.0	279	Total			

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 71

Subcatchment 44S: Grass in basin



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 72


Summary for Subcatchment 45S: Grass in basin[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 8.10 cfs @ 12.10 hrs, Volume= 0.547 af, Depth> 9.78"
Routed to Pond 49P : Basin 203

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, $dt=0.05$ hrs
NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Area (sf)	CN	Description
29,224	89	<50% Grass cover, Poor, HSG D
29,224		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.3					Direct Entry, Tc Direct
0.5	163	0.0050	5.09	16.00	Pipe Channel, CMP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.013 Corrugated PE, smooth interior
0.1	100	0.0736	25.60	180.95	Pipe Channel, CMP_Round 36" 36.0" Round Area= 7.1 sf Perim= 9.4' r= 0.75' n= 0.013 Corrugated PE, smooth interior
3.9	263	Total			

Subcatchment 45S: Grass in basin

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 73

Summary for Pond 47P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 10.68" for Yr 2100 - 100 Yr event
 Inflow = 18.03 cfs @ 12.09 hrs, Volume= 1.243 af
 Outflow = 13.98 cfs @ 12.13 hrs, Volume= 1.105 af, Atten= 22%, Lag= 2.4 min
 Primary = 13.98 cfs @ 12.13 hrs, Volume= 1.105 af
 Routed to Pond 48P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 48P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.48' @ 12.13 hrs Surf.Area= 4,454 sf Storage= 14,729 cf

Plug-Flow detention time= 141.8 min calculated for 1.105 af (89% of inflow)
 Center-of-Mass det. time= 85.6 min (826.2 - 740.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf
#2	Secondary	48.50'	20.0' long + 0.3 '/' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 74


Primary OutFlow Max=13.74 cfs @ 12.13 hrs HW=48.46' (Free Discharge)

- 1=Culvert (Inlet Controls 13.74 cfs @ 7.78 fps)
- 3=Orifice/Grate (Passes < 18.95 cfs potential flow)
- 4=Orifice/Grate (Passes < 1.27 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.66 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 47P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 75

Summary for Pond 48P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 47P by 0.37' @ 23.95 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 10.31" for Yr 2100 - 100 Yr event
 Inflow = 54.87 cfs @ 12.11 hrs, Volume= 4.244 af
 Outflow = 16.07 cfs @ 12.34 hrs, Volume= 3.146 af, Atten= 71%, Lag= 13.8 min
 Primary = 16.07 cfs @ 12.34 hrs, Volume= 3.146 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.32' @ 12.34 hrs Surf.Area= 22,290 sf Storage= 85,305 cf

Plug-Flow detention time= 189.7 min calculated for 3.140 af (74% of inflow)
 Center-of-Mass det. time= 98.9 min (864.3 - 765.5)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 76

Primary OutFlow Max=16.07 cfs @ 12.34 hrs HW=48.32' (Free Discharge)


- ↑ **1=Culvert** (Inlet Controls 16.07 cfs @ 9.09 fps)
- ↑ **3=Orifice/Grate** (Passes < 99.49 cfs potential flow)
- ↑ **4=Orifice/Grate** (Passes < 2.42 cfs potential flow)
- ↑ **5=Orifice/Grate** (Passes < 0.64 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- ↑ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond 48P: Basin 104

Hydrograph



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 77

Summary for Pond 49P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 51P by 1.20' @ 14.55 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 10.45" for Yr 2100 - 100 Yr event
 Inflow = 44.33 cfs @ 12.11 hrs, Volume= 3.335 af
 Outflow = 30.74 cfs @ 12.19 hrs, Volume= 2.561 af, Atten= 31%, Lag= 4.9 min
 Primary = 30.74 cfs @ 12.19 hrs, Volume= 2.561 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.36' @ 12.19 hrs Surf.Area= 18,231 sf Storage= 63,575 cf

Plug-Flow detention time= 217.5 min calculated for 2.556 af (77% of inflow)
 Center-of-Mass det. time= 133.1 min (888.5 - 755.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 78


Primary OutFlow Max=30.23 cfs @ 12.19 hrs HW=48.35' (Free Discharge)

- 1=Culvert (Passes 30.23 cfs of 33.71 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 27.38 cfs @ 2.64 fps)
- 4=Orifice/Grate (Orifice Controls 2.20 cfs @ 6.31 fps)
- 5=Orifice/Grate (Orifice Controls 0.65 cfs @ 7.40 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 49P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 79

Summary for Pond 51P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 10.72" for Yr 2100 - 100 Yr event
 Inflow = 10.07 cfs @ 12.08 hrs, Volume= 0.690 af
 Outflow = 9.78 cfs @ 12.09 hrs, Volume= 0.624 af, Atten= 3%, Lag= 0.5 min
 Primary = 9.78 cfs @ 12.09 hrs, Volume= 0.624 af
 Routed to Pond 49P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 49P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.48' @ 12.09 hrs Surf.Area= 1,865 sf Storage= 6,973 cf

Plug-Flow detention time= 117.1 min calculated for 0.622 af (90% of inflow)
 Center-of-Mass det. time= 66.7 min (806.0 - 739.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 80


Primary OutFlow Max=9.38 cfs @ 12.09 hrs HW=48.47' (Free Discharge)

- 1=Culvert (Passes 9.38 cfs of 13.78 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 7.41 cfs @ 1.70 fps)
- 4=Orifice/Grate (Orifice Controls 1.31 cfs @ 6.67 fps)
- 5=Orifice/Grate (Orifice Controls 0.66 cfs @ 7.59 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 51P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC


Page 81

Summary for Link 24L: POA 1 (2100)

Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 8.08" for Yr 2100 - 100 Yr event
Inflow = 61.95 cfs @ 12.14 hrs, Volume= 7.545 af
Primary = 61.95 cfs @ 12.14 hrs, Volume= 7.545 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 24L: POA 1 (2100)



**5.1 STORM MANAGEMENT DESIGN
POND ROUTINGS (2, 10 AND 100-YEAR ADJUSTED STORM
EVENTS)**

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 28

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.26' @ 23.90 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 2.63" for Adj - 2 Yr event
 Inflow = 12.10 cfs @ 12.13 hrs, Volume= 1.084 af
 Outflow = 0.21 cfs @ 21.88 hrs, Volume= 0.151 af, Atten= 98%, Lag= 584.9 min
 Primary = 0.21 cfs @ 21.88 hrs, Volume= 0.151 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.24' @ 21.88 hrs Surf.Area= 20,611 sf Storage= 40,754 cf

Plug-Flow detention time= 664.4 min calculated for 0.151 af (14% of inflow)
 Center-of-Mass det. time= 378.7 min (1,174.5 - 795.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 29

Primary OutFlow Max=0.21 cfs @ 21.88 hrs HW=46.24' (Free Discharge)


- 1=Culvert (Passes 0.21 cfs of 9.87 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Controls 0.00 cfs)
- 5=Orifice/Grate (Orifice Controls 0.21 cfs @ 2.43 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 30

Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 31

Hydrograph for Pond 39P: Basin 104

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.00	0	42.83	0.00	0.00	0.00
1.50	0.01	6	42.83	0.00	0.00	0.00
2.00	0.03	41	42.84	0.00	0.00	0.00
2.50	0.04	103	42.84	0.00	0.00	0.00
3.00	0.05	191	42.86	0.00	0.00	0.00
3.50	0.07	301	42.87	0.00	0.00	0.00
4.00	0.08	431	42.89	0.00	0.00	0.00
4.50	0.09	579	42.91	0.00	0.00	0.00
5.00	0.10	745	42.94	0.00	0.00	0.00
5.50	0.11	926	42.96	0.00	0.00	0.00
6.00	0.11	1,124	42.99	0.00	0.00	0.00
6.50	0.13	1,346	43.03	0.00	0.00	0.00
7.00	0.16	1,608	43.06	0.00	0.00	0.00
7.50	0.18	1,910	43.11	0.00	0.00	0.00
8.00	0.20	2,255	43.16	0.00	0.00	0.00
8.50	0.23	2,643	43.21	0.00	0.00	0.00
9.00	0.25	3,077	43.28	0.00	0.00	0.00
9.50	0.33	3,594	43.35	0.00	0.00	0.00
10.00	0.41	4,255	43.45	0.00	0.00	0.00
10.50	0.50	5,067	43.56	0.00	0.00	0.00
11.00	0.79	6,201	43.73	0.00	0.00	0.00
11.50	1.34	8,102	44.00	0.00	0.00	0.00
12.00	6.72	13,368	44.77	0.00	0.00	0.00
12.50	3.34	25,637	45.48	0.00	0.00	0.00
13.00	1.83	29,908	45.71	0.00	0.00	0.00
13.50	1.19	32,574	45.84	0.00	0.00	0.00
14.00	0.90	34,378	45.93	0.03	0.03	0.00
14.50	0.74	35,765	46.00	0.07	0.07	0.00
15.00	0.62	36,834	46.05	0.11	0.11	0.00
15.50	0.56	37,666	46.09	0.13	0.13	0.00
16.00	0.51	38,362	46.13	0.16	0.16	0.00
16.50	0.46	38,943	46.15	0.17	0.17	0.00
17.00	0.42	39,418	46.18	0.18	0.18	0.00
17.50	0.37	39,794	46.20	0.19	0.19	0.00
18.00	0.33	40,076	46.21	0.20	0.20	0.00
18.50	0.30	40,276	46.22	0.20	0.20	0.00
19.00	0.28	40,428	46.23	0.21	0.21	0.00
19.50	0.26	40,544	46.23	0.21	0.21	0.00
20.00	0.25	40,630	46.24	0.21	0.21	0.00
20.50	0.24	40,691	46.24	0.21	0.21	0.00
21.00	0.23	40,730	46.24	0.21	0.21	0.00
21.50	0.22	40,750	46.24	0.21	0.21	0.00
22.00	0.21	40,754	46.24	0.21	0.21	0.00
22.50	0.20	40,742	46.24	0.21	0.21	0.00
23.00	0.19	40,715	46.24	0.21	0.21	0.00
23.50	0.18	40,674	46.24	0.21	0.21	0.00
24.00	0.19	40,622	46.24	0.21	0.21	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 32

Stage-Discharge for Pond 39P: Basin 104

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	15.41	15.41	0.00
42.93	0.00	0.00	0.00	48.13	15.64	15.64	0.00
43.03	0.00	0.00	0.00	48.23	15.87	15.87	0.00
43.13	0.00	0.00	0.00	48.33	16.10	16.10	0.00
43.23	0.00	0.00	0.00				
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.30	0.30	0.00				
46.53	0.54	0.54	0.00				
46.63	0.87	0.87	0.00				
46.73	2.35	2.35	0.00				
46.83	5.37	5.37	0.00				
46.93	9.30	9.30	0.00				
47.03	12.85	12.85	0.00				
47.13	13.13	13.13	0.00				
47.23	13.40	13.40	0.00				
47.33	13.67	13.67	0.00				
47.43	13.93	13.93	0.00				
47.53	14.19	14.19	0.00				
47.63	14.44	14.44	0.00				
47.73	14.69	14.69	0.00				
47.83	14.93	14.93	0.00				
47.93	15.17	15.17	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 33

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 0.38' @ 18.45 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 2.74" for Adj - 2 Yr event
 Inflow = 10.89 cfs @ 12.12 hrs, Volume= 0.875 af
 Outflow = 0.26 cfs @ 17.17 hrs, Volume= 0.216 af, Atten= 98%, Lag= 302.5 min
 Primary = 0.26 cfs @ 17.17 hrs, Volume= 0.216 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.35' @ 17.17 hrs Surf.Area= 15,084 sf Storage= 30,152 cf

Plug-Flow detention time= 529.0 min calculated for 0.216 af (25% of inflow)
 Center-of-Mass det. time= 329.4 min (1,110.1 - 780.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 34

Primary OutFlow Max=0.26 cfs @ 17.17 hrs HW=46.35' (Free Discharge)

- 1=Culvert (Passes 0.26 cfs of 29.46 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.01 cfs @ 0.73 fps)
- 5=Orifice/Grate (Orifice Controls 0.25 cfs @ 2.89 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Culvert ☐

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 35

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 36

Hydrograph for Pond 41P: Basin 203

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.00	0	42.83	0.00	0.00	0.00
1.50	0.01	5	42.83	0.00	0.00	0.00
2.00	0.02	36	42.84	0.00	0.00	0.00
2.50	0.04	91	42.85	0.00	0.00	0.00
3.00	0.05	169	42.87	0.00	0.00	0.00
3.50	0.06	265	42.89	0.00	0.00	0.00
4.00	0.07	380	42.91	0.00	0.00	0.00
4.50	0.08	511	42.94	0.00	0.00	0.00
5.00	0.09	657	42.97	0.00	0.00	0.00
5.50	0.09	817	43.00	0.00	0.00	0.00
6.00	0.10	991	43.04	0.00	0.00	0.00
6.50	0.12	1,187	43.08	0.00	0.00	0.00
7.00	0.14	1,417	43.13	0.00	0.00	0.00
7.50	0.16	1,682	43.18	0.00	0.00	0.00
8.00	0.18	1,985	43.25	0.00	0.00	0.00
8.50	0.20	2,325	43.32	0.00	0.00	0.00
9.00	0.22	2,704	43.40	0.00	0.00	0.00
9.50	0.29	3,156	43.49	0.00	0.00	0.00
10.00	0.36	3,733	43.61	0.00	0.00	0.00
10.50	0.43	4,442	43.76	0.00	0.00	0.00
11.00	0.68	5,430	43.97	0.00	0.00	0.00
11.50	1.17	7,086	44.32	0.00	0.00	0.00
12.00	5.96	11,712	45.01	0.00	0.00	0.00
12.50	2.88	22,678	45.84	0.00	0.00	0.00
13.00	1.32	25,942	46.06	0.11	0.11	0.00
13.50	0.84	27,548	46.17	0.18	0.18	0.00
14.00	0.65	28,497	46.24	0.21	0.21	0.00
14.50	0.54	29,172	46.28	0.23	0.23	0.00
15.00	0.42	29,608	46.31	0.24	0.24	0.00
15.50	0.36	29,855	46.33	0.25	0.25	0.00
16.00	0.32	30,014	46.34	0.25	0.25	0.00
16.50	0.29	30,110	46.34	0.26	0.26	0.00
17.00	0.27	30,150	46.35	0.26	0.26	0.00
17.50	0.24	30,142	46.35	0.26	0.26	0.00
18.00	0.22	30,091	46.34	0.26	0.26	0.00
18.50	0.20	30,008	46.34	0.25	0.25	0.00
19.00	0.20	29,915	46.33	0.25	0.25	0.00
19.50	0.19	29,814	46.32	0.25	0.25	0.00
20.00	0.18	29,708	46.32	0.24	0.24	0.00
20.50	0.18	29,596	46.31	0.24	0.24	0.00
21.00	0.17	29,480	46.30	0.24	0.24	0.00
21.50	0.16	29,360	46.29	0.23	0.23	0.00
22.00	0.16	29,234	46.29	0.23	0.23	0.00
22.50	0.15	29,103	46.28	0.23	0.23	0.00
23.00	0.15	28,967	46.27	0.22	0.22	0.00
23.50	0.14	28,827	46.26	0.22	0.22	0.00
24.00	0.15	28,684	46.25	0.21	0.21	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 37

Stage-Discharge for Pond 41P: Basin 203

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	12.51	12.51	0.00
42.93	0.00	0.00	0.00	48.13	17.42	17.42	0.00
43.03	0.00	0.00	0.00	48.23	22.94	22.94	0.00
43.13	0.00	0.00	0.00	48.33	28.99	28.99	0.00
43.23	0.00	0.00	0.00				
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.34	0.34	0.00				
46.53	0.48	0.48	0.00				
46.63	0.67	0.67	0.00				
46.73	0.89	0.89	0.00				
46.83	1.12	1.12	0.00				
46.93	1.33	1.33	0.00				
47.03	1.49	1.49	0.00				
47.13	1.63	1.63	0.00				
47.23	1.77	1.77	0.00				
47.33	1.89	1.89	0.00				
47.43	2.00	2.00	0.00				
47.53	2.11	2.11	0.00				
47.63	2.22	2.22	0.00				
47.73	2.59	2.59	0.00				
47.83	4.86	4.86	0.00				
47.93	8.27	8.27	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 38

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 2.98" for Adj - 2 Yr event
 Inflow = 2.93 cfs @ 12.08 hrs, Volume= 0.192 af
 Outflow = 1.00 cfs @ 12.22 hrs, Volume= 0.129 af, Atten= 66%, Lag= 8.2 min
 Primary = 1.00 cfs @ 12.22 hrs, Volume= 0.129 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.93' @ 12.22 hrs Surf.Area= 1,603 sf Storage= 4,298 cf

Plug-Flow detention time= 211.0 min calculated for 0.129 af (67% of inflow)
 Center-of-Mass det. time= 111.4 min (871.0 - 759.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 ' / Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025


Page 39

Primary OutFlow Max=0.99 cfs @ 12.22 hrs HW=46.93' (Free Discharge)


- 1=Culvert (Passes 0.99 cfs of 7.45 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.58 cfs @ 2.97 fps)
- 5=Orifice/Grate (Orifice Controls 0.41 cfs @ 4.68 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 43P: Basin 206



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 40

Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 41

Hydrograph for Pond 43P: Basin 206

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.00	0	42.83	0.00	0.00	0.00
1.50	0.00	2	42.83	0.00	0.00	0.00
2.00	0.01	11	42.85	0.00	0.00	0.00
2.50	0.01	27	42.88	0.00	0.00	0.00
3.00	0.01	49	42.92	0.00	0.00	0.00
3.50	0.02	76	42.96	0.00	0.00	0.00
4.00	0.02	108	43.02	0.00	0.00	0.00
4.50	0.02	144	43.08	0.00	0.00	0.00
5.00	0.02	184	43.15	0.00	0.00	0.00
5.50	0.03	229	43.23	0.00	0.00	0.00
6.00	0.03	276	43.31	0.00	0.00	0.00
6.50	0.03	330	43.41	0.00	0.00	0.00
7.00	0.04	394	43.52	0.00	0.00	0.00
7.50	0.04	466	43.64	0.00	0.00	0.00
8.00	0.05	548	43.78	0.00	0.00	0.00
8.50	0.05	640	43.94	0.00	0.00	0.00
9.00	0.06	741	44.12	0.00	0.00	0.00
9.50	0.08	864	44.34	0.00	0.00	0.00
10.00	0.10	1,020	44.61	0.00	0.00	0.00
10.50	0.12	1,210	44.87	0.00	0.00	0.00
11.00	0.18	1,481	45.06	0.00	0.00	0.00
11.50	0.32	1,936	45.38	0.00	0.00	0.00
12.00	1.77	3,292	46.29	0.23	0.23	0.00
12.50	0.51	4,021	46.76	0.80	0.80	0.00
13.00	0.23	3,572	46.47	0.38	0.38	0.00
13.50	0.14	3,351	46.33	0.25	0.25	0.00
14.00	0.11	3,173	46.21	0.20	0.20	0.00
14.50	0.10	3,041	46.12	0.16	0.16	0.00
15.00	0.08	2,950	46.06	0.12	0.12	0.00
15.50	0.07	2,896	46.03	0.09	0.09	0.00
16.00	0.06	2,866	46.01	0.08	0.08	0.00
16.50	0.06	2,847	46.00	0.07	0.07	0.00
17.00	0.05	2,832	45.99	0.06	0.06	0.00
17.50	0.05	2,818	45.98	0.05	0.05	0.00
18.00	0.04	2,805	45.97	0.05	0.05	0.00
18.50	0.04	2,795	45.96	0.04	0.04	0.00
19.00	0.04	2,788	45.96	0.04	0.04	0.00
19.50	0.04	2,783	45.95	0.04	0.04	0.00
20.00	0.04	2,779	45.95	0.04	0.04	0.00
20.50	0.04	2,775	45.95	0.04	0.04	0.00
21.00	0.03	2,772	45.94	0.04	0.04	0.00
21.50	0.03	2,768	45.94	0.03	0.03	0.00
22.00	0.03	2,764	45.94	0.03	0.03	0.00
22.50	0.03	2,759	45.94	0.03	0.03	0.00
23.00	0.03	2,755	45.93	0.03	0.03	0.00
23.50	0.03	2,751	45.93	0.03	0.03	0.00
24.00	0.03	2,748	45.93	0.03	0.03	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 42

Stage-Discharge for Pond 43P: Basin 206

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	1.75	1.75	0.00
42.93	0.00	0.00	0.00	48.13	1.80	1.80	0.00
43.03	0.00	0.00	0.00	48.23	2.13	2.13	0.00
43.13	0.00	0.00	0.00	48.33	4.36	4.36	0.00
43.23	0.00	0.00	0.00	48.43	7.72	7.72	0.00
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.33	0.33	0.00				
46.53	0.45	0.45	0.00				
46.63	0.61	0.61	0.00				
46.73	0.76	0.76	0.00				
46.83	0.89	0.89	0.00				
46.93	0.99	0.99	0.00				
47.03	1.08	1.08	0.00				
47.13	1.17	1.17	0.00				
47.23	1.25	1.25	0.00				
47.33	1.32	1.32	0.00				
47.43	1.39	1.39	0.00				
47.53	1.46	1.46	0.00				
47.63	1.52	1.52	0.00				
47.73	1.58	1.58	0.00				
47.83	1.64	1.64	0.00				
47.93	1.70	1.70	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 43

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 2.96" for Adj - 2 Yr event
 Inflow = 5.20 cfs @ 12.09 hrs, Volume= 0.344 af
 Outflow = 0.92 cfs @ 12.48 hrs, Volume= 0.224 af, Atten= 82%, Lag= 23.5 min
 Primary = 0.92 cfs @ 12.48 hrs, Volume= 0.224 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.95' @ 12.48 hrs Surf.Area= 3,654 sf Storage= 8,596 cf

Plug-Flow detention time= 252.2 min calculated for 0.224 af (65% of inflow)
 Center-of-Mass det. time= 149.7 min (911.0 - 761.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025


Page 44

Primary OutFlow Max=0.92 cfs @ 12.48 hrs HW=46.94' (Free Discharge)

- 1=Culvert (Passes 0.92 cfs of 7.52 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.51 cfs @ 2.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.41 cfs @ 4.71 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 44P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 45

Pond 44P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 46

Hydrograph for Pond 44P: Basin 112

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.00	0	42.83	0.00	0.00	0.00
1.50	0.01	3	42.83	0.00	0.00	0.00
2.00	0.01	19	42.85	0.00	0.00	0.00
2.50	0.02	47	42.88	0.00	0.00	0.00
3.00	0.02	85	42.92	0.00	0.00	0.00
3.50	0.03	132	42.96	0.00	0.00	0.00
4.00	0.03	187	43.02	0.00	0.00	0.00
4.50	0.04	250	43.08	0.00	0.00	0.00
5.00	0.04	320	43.16	0.00	0.00	0.00
5.50	0.04	397	43.23	0.00	0.00	0.00
6.00	0.05	480	43.32	0.00	0.00	0.00
6.50	0.06	574	43.41	0.00	0.00	0.00
7.00	0.07	684	43.52	0.00	0.00	0.00
7.50	0.08	811	43.65	0.00	0.00	0.00
8.00	0.08	955	43.80	0.00	0.00	0.00
8.50	0.09	1,116	43.96	0.00	0.00	0.00
9.00	0.10	1,295	44.15	0.00	0.00	0.00
9.50	0.14	1,511	44.37	0.00	0.00	0.00
10.00	0.17	1,786	44.64	0.00	0.00	0.00
10.50	0.20	2,122	44.89	0.00	0.00	0.00
11.00	0.33	2,601	45.08	0.00	0.00	0.00
11.50	0.56	3,406	45.37	0.00	0.00	0.00
12.00	3.11	5,837	46.16	0.17	0.17	0.00
12.50	0.92	8,594	46.94	0.92	0.92	0.00
13.00	0.41	8,069	46.80	0.74	0.74	0.00
13.50	0.26	7,539	46.65	0.51	0.51	0.00
14.00	0.21	7,159	46.54	0.38	0.38	0.00
14.50	0.17	6,891	46.47	0.31	0.31	0.00
15.00	0.14	6,652	46.40	0.27	0.27	0.00
15.50	0.12	6,417	46.33	0.25	0.25	0.00
16.00	0.11	6,208	46.27	0.22	0.22	0.00
16.50	0.10	6,023	46.21	0.20	0.20	0.00
17.00	0.09	5,863	46.16	0.18	0.18	0.00
17.50	0.09	5,726	46.12	0.16	0.16	0.00
18.00	0.08	5,612	46.09	0.13	0.13	0.00
18.50	0.07	5,523	46.06	0.11	0.11	0.00
19.00	0.07	5,460	46.04	0.10	0.10	0.00
19.50	0.07	5,413	46.03	0.09	0.09	0.00
20.00	0.07	5,378	46.02	0.08	0.08	0.00
20.50	0.06	5,351	46.01	0.08	0.08	0.00
21.00	0.06	5,330	46.00	0.07	0.07	0.00
21.50	0.06	5,311	46.00	0.07	0.07	0.00
22.00	0.06	5,295	45.99	0.07	0.07	0.00
22.50	0.05	5,279	45.99	0.06	0.06	0.00
23.00	0.05	5,265	45.98	0.06	0.06	0.00
23.50	0.05	5,251	45.98	0.06	0.06	0.00
24.00	0.06	5,240	45.98	0.06	0.06	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 47

Stage-Discharge for Pond 44P: Basin 112

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	2.90	2.90	0.00
42.93	0.00	0.00	0.00	48.13	5.76	5.76	0.00
43.03	0.00	0.00	0.00	48.23	9.57	9.57	0.00
43.13	0.00	0.00	0.00	48.33	13.40	13.40	0.00
43.23	0.00	0.00	0.00	48.43	13.67	13.67	0.00
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.28	0.28	0.00				
46.53	0.36	0.36	0.00				
46.63	0.48	0.48	0.00				
46.73	0.63	0.63	0.00				
46.83	0.79	0.79	0.00				
46.93	0.91	0.91	0.00				
47.03	1.01	1.01	0.00				
47.13	1.10	1.10	0.00				
47.23	1.19	1.19	0.00				
47.33	1.27	1.27	0.00				
47.43	1.34	1.34	0.00				
47.53	1.41	1.41	0.00				
47.63	1.47	1.47	0.00				
47.73	1.54	1.54	0.00				
47.83	1.60	1.60	0.00				
47.93	1.66	1.66	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 77

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.44' @ 21.65 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 4.34" for Adj - 10 Yr event
 Inflow = 19.36 cfs @ 12.12 hrs, Volume= 1.786 af
 Outflow = 2.12 cfs @ 13.57 hrs, Volume= 0.749 af, Atten= 89%, Lag= 86.7 min
 Primary = 2.12 cfs @ 13.57 hrs, Volume= 0.749 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.72' @ 13.57 hrs Surf.Area= 20,991 sf Storage= 50,681 cf

Plug-Flow detention time= 367.4 min calculated for 0.749 af (42% of inflow)
 Center-of-Mass det. time= 218.3 min (1,005.2 - 786.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 78

Primary OutFlow Max=2.08 cfs @ 13.57 hrs HW=46.72' (Free Discharge)


- 1=Culvert (Passes 2.08 cfs of 11.94 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 0.94 cfs @ 0.86 fps)
- 4=Orifice/Grate (Orifice Controls 0.78 cfs @ 2.08 fps)
- 5=Orifice/Grate (Orifice Controls 0.36 cfs @ 4.12 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 79

Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 80

Hydrograph for Pond 39P: Basin 104

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.01	4	42.83	0.00	0.00	0.00
1.50	0.05	60	42.84	0.00	0.00	0.00
2.00	0.07	169	42.85	0.00	0.00	0.00
2.50	0.10	322	42.88	0.00	0.00	0.00
3.00	0.11	513	42.90	0.00	0.00	0.00
3.50	0.13	735	42.94	0.00	0.00	0.00
4.00	0.15	986	42.97	0.00	0.00	0.00
4.50	0.16	1,264	43.01	0.00	0.00	0.00
5.00	0.18	1,572	43.06	0.00	0.00	0.00
5.50	0.19	1,907	43.11	0.00	0.00	0.00
6.00	0.21	2,269	43.16	0.00	0.00	0.00
6.50	0.24	2,671	43.22	0.00	0.00	0.00
7.00	0.28	3,135	43.28	0.00	0.00	0.00
7.50	0.31	3,664	43.36	0.00	0.00	0.00
8.00	0.35	4,259	43.45	0.00	0.00	0.00
8.50	0.39	4,922	43.54	0.00	0.00	0.00
9.00	0.43	5,654	43.65	0.00	0.00	0.00
9.50	0.54	6,521	43.78	0.00	0.00	0.00
10.00	0.67	7,617	43.93	0.00	0.00	0.00
10.50	0.81	8,951	44.13	0.00	0.00	0.00
11.00	1.27	10,797	44.40	0.00	0.00	0.00
11.50	2.30	13,935	44.84	0.00	0.00	0.00
12.00	11.32	22,941	45.34	0.00	0.00	0.00
12.50	5.38	42,589	46.33	0.25	0.25	0.00
13.00	3.15	48,751	46.63	0.86	0.86	0.00
13.50	2.23	50,667	46.72	2.11	2.11	0.00
14.00	1.67	50,442	46.71	1.89	1.89	0.00
14.50	1.23	50,006	46.69	1.47	1.47	0.00
15.00	0.94	49,622	46.67	1.15	1.15	0.00
15.50	0.80	49,267	46.65	0.96	0.96	0.00
16.00	0.72	48,967	46.64	0.90	0.90	0.00
16.50	0.67	48,654	46.62	0.84	0.84	0.00
17.00	0.61	48,342	46.61	0.79	0.79	0.00
17.50	0.56	48,025	46.59	0.74	0.74	0.00
18.00	0.50	47,704	46.58	0.68	0.68	0.00
18.50	0.47	47,389	46.56	0.63	0.63	0.00
19.00	0.44	47,105	46.55	0.59	0.59	0.00
19.50	0.42	46,844	46.54	0.56	0.56	0.00
20.00	0.39	46,603	46.52	0.52	0.52	0.00
20.50	0.37	46,380	46.51	0.49	0.49	0.00
21.00	0.35	46,177	46.50	0.46	0.46	0.00
21.50	0.34	45,985	46.49	0.44	0.44	0.00
22.00	0.32	45,802	46.49	0.42	0.42	0.00
22.50	0.31	45,628	46.48	0.40	0.40	0.00
23.00	0.30	45,463	46.47	0.38	0.38	0.00
23.50	0.28	45,306	46.46	0.37	0.37	0.00
24.00	0.30	45,160	46.45	0.35	0.35	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 81

Stage-Discharge for Pond 39P: Basin 104

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	15.41	15.41	0.00
42.93	0.00	0.00	0.00	48.13	15.64	15.64	0.00
43.03	0.00	0.00	0.00	48.23	15.87	15.87	0.00
43.13	0.00	0.00	0.00	48.33	16.10	16.10	0.00
43.23	0.00	0.00	0.00				
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.30	0.30	0.00				
46.53	0.54	0.54	0.00				
46.63	0.87	0.87	0.00				
46.73	2.35	2.35	0.00				
46.83	5.37	5.37	0.00				
46.93	9.30	9.30	0.00				
47.03	12.85	12.85	0.00				
47.13	13.13	13.13	0.00				
47.23	13.40	13.40	0.00				
47.33	13.67	13.67	0.00				
47.43	13.93	13.93	0.00				
47.53	14.19	14.19	0.00				
47.63	14.44	14.44	0.00				
47.73	14.69	14.69	0.00				
47.83	14.93	14.93	0.00				
47.93	15.17	15.17	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 82

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 0.70' @ 15.30 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 4.45" for Adj - 10 Yr event
 Inflow = 17.12 cfs @ 12.12 hrs, Volume= 1.421 af
 Outflow = 1.48 cfs @ 13.35 hrs, Volume= 0.713 af, Atten= 91%, Lag= 73.8 min
 Primary = 1.48 cfs @ 13.35 hrs, Volume= 0.713 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.02' @ 13.35 hrs Surf.Area= 16,110 sf Storage= 40,717 cf

Plug-Flow detention time= 340.5 min calculated for 0.713 af (50% of inflow)
 Center-of-Mass det. time= 214.3 min (985.6 - 771.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 83

Primary OutFlow Max=1.48 cfs @ 13.35 hrs HW=47.02' (Free Discharge)

- 1=Culvert (Passes 1.48 cfs of 30.96 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.05 cfs @ 3.01 fps)
- 5=Orifice/Grate (Orifice Controls 0.43 cfs @ 4.90 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Culvert ☐

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 84

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 85

Hydrograph for Pond 41P: Basin 203

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.01	4	42.83	0.00	0.00	0.00
1.50	0.04	53	42.84	0.00	0.00	0.00
2.00	0.07	150	42.86	0.00	0.00	0.00
2.50	0.08	285	42.89	0.00	0.00	0.00
3.00	0.10	453	42.92	0.00	0.00	0.00
3.50	0.12	649	42.97	0.00	0.00	0.00
4.00	0.13	870	43.01	0.00	0.00	0.00
4.50	0.14	1,115	43.06	0.00	0.00	0.00
5.00	0.16	1,385	43.12	0.00	0.00	0.00
5.50	0.17	1,680	43.18	0.00	0.00	0.00
6.00	0.18	1,997	43.25	0.00	0.00	0.00
6.50	0.21	2,349	43.32	0.00	0.00	0.00
7.00	0.24	2,755	43.41	0.00	0.00	0.00
7.50	0.27	3,217	43.50	0.00	0.00	0.00
8.00	0.31	3,736	43.61	0.00	0.00	0.00
8.50	0.34	4,314	43.73	0.00	0.00	0.00
9.00	0.37	4,952	43.87	0.00	0.00	0.00
9.50	0.47	5,707	44.03	0.00	0.00	0.00
10.00	0.59	6,660	44.23	0.00	0.00	0.00
10.50	0.70	7,820	44.47	0.00	0.00	0.00
11.00	1.11	9,424	44.81	0.00	0.00	0.00
11.50	2.05	12,215	45.05	0.00	0.00	0.00
12.00	10.09	20,319	45.67	0.00	0.00	0.00
12.50	4.64	36,936	46.79	1.02	1.02	0.00
13.00	2.26	40,279	47.00	1.44	1.44	0.00
13.50	1.27	40,662	47.02	1.47	1.47	0.00
14.00	0.95	39,988	46.98	1.41	1.41	0.00
14.50	0.80	39,106	46.92	1.31	1.31	0.00
15.00	0.65	38,143	46.86	1.19	1.19	0.00
15.50	0.56	37,183	46.80	1.06	1.06	0.00
16.00	0.50	36,340	46.75	0.94	0.94	0.00
16.50	0.45	35,612	46.70	0.83	0.83	0.00
17.00	0.41	34,980	46.66	0.74	0.74	0.00
17.50	0.37	34,422	46.63	0.66	0.66	0.00
18.00	0.33	33,920	46.59	0.60	0.60	0.00
18.50	0.31	33,468	46.56	0.54	0.54	0.00
19.00	0.30	33,082	46.54	0.50	0.50	0.00
19.50	0.29	32,748	46.52	0.46	0.46	0.00
20.00	0.28	32,458	46.50	0.43	0.43	0.00
20.50	0.27	32,197	46.48	0.41	0.41	0.00
21.00	0.26	31,962	46.47	0.39	0.39	0.00
21.50	0.25	31,747	46.45	0.37	0.37	0.00
22.00	0.24	31,547	46.44	0.35	0.35	0.00
22.50	0.23	31,356	46.43	0.34	0.34	0.00
23.00	0.22	31,173	46.41	0.32	0.32	0.00
23.50	0.21	30,997	46.40	0.31	0.31	0.00
24.00	0.23	30,831	46.39	0.30	0.30	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 86

Stage-Discharge for Pond 41P: Basin 203

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	12.51	12.51	0.00
42.93	0.00	0.00	0.00	48.13	17.42	17.42	0.00
43.03	0.00	0.00	0.00	48.23	22.94	22.94	0.00
43.13	0.00	0.00	0.00	48.33	28.99	28.99	0.00
43.23	0.00	0.00	0.00				
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.34	0.34	0.00				
46.53	0.48	0.48	0.00				
46.63	0.67	0.67	0.00				
46.73	0.89	0.89	0.00				
46.83	1.12	1.12	0.00				
46.93	1.33	1.33	0.00				
47.03	1.49	1.49	0.00				
47.13	1.63	1.63	0.00				
47.23	1.77	1.77	0.00				
47.33	1.89	1.89	0.00				
47.43	2.00	2.00	0.00				
47.53	2.11	2.11	0.00				
47.63	2.22	2.22	0.00				
47.73	2.59	2.59	0.00				
47.83	4.86	4.86	0.00				
47.93	8.27	8.27	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 87

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 4.70" for Adj - 10 Yr event
 Inflow = 4.53 cfs @ 12.08 hrs, Volume= 0.303 af
 Outflow = 1.63 cfs @ 12.21 hrs, Volume= 0.239 af, Atten= 64%, Lag= 7.6 min
 Primary = 1.63 cfs @ 12.21 hrs, Volume= 0.239 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.81' @ 12.21 hrs Surf.Area= 1,745 sf Storage= 5,763 cf

Plug-Flow detention time= 174.2 min calculated for 0.238 af (79% of inflow)
 Center-of-Mass det. time= 93.4 min (844.6 - 751.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025


Page 88

Primary OutFlow Max=1.63 cfs @ 12.21 hrs HW=47.81' (Free Discharge)


- 1=Culvert (Passes 1.63 cfs of 11.90 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.06 cfs @ 5.40 fps)
- 5=Orifice/Grate (Orifice Controls 0.57 cfs @ 6.50 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 43P: Basin 206



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 89

Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 90

Hydrograph for Pond 43P: Basin 206

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.00	2	42.83	0.00	0.00	0.00
1.50	0.01	17	42.86	0.00	0.00	0.00
2.00	0.02	45	42.91	0.00	0.00	0.00
2.50	0.02	83	42.97	0.00	0.00	0.00
3.00	0.03	130	43.06	0.00	0.00	0.00
3.50	0.03	184	43.15	0.00	0.00	0.00
4.00	0.04	245	43.26	0.00	0.00	0.00
4.50	0.04	313	43.37	0.00	0.00	0.00
5.00	0.04	386	43.50	0.00	0.00	0.00
5.50	0.05	466	43.64	0.00	0.00	0.00
6.00	0.05	551	43.79	0.00	0.00	0.00
6.50	0.06	647	43.96	0.00	0.00	0.00
7.00	0.06	756	44.15	0.00	0.00	0.00
7.50	0.07	880	44.36	0.00	0.00	0.00
8.00	0.08	1,018	44.60	0.00	0.00	0.00
8.50	0.09	1,171	44.85	0.00	0.00	0.00
9.00	0.10	1,340	44.96	0.00	0.00	0.00
9.50	0.13	1,542	45.10	0.00	0.00	0.00
10.00	0.15	1,795	45.28	0.00	0.00	0.00
10.50	0.19	2,101	45.49	0.00	0.00	0.00
11.00	0.29	2,536	45.79	0.00	0.00	0.00
11.50	0.50	3,126	46.18	0.19	0.19	0.00
12.00	2.75	4,466	47.04	1.09	1.09	0.00
12.50	0.78	5,200	47.48	1.43	1.43	0.00
13.00	0.35	4,021	46.76	0.80	0.80	0.00
13.50	0.22	3,554	46.46	0.36	0.36	0.00
14.00	0.17	3,361	46.34	0.25	0.25	0.00
14.50	0.15	3,229	46.25	0.22	0.22	0.00
15.00	0.12	3,108	46.17	0.18	0.18	0.00
15.50	0.10	3,012	46.11	0.14	0.14	0.00
16.00	0.10	2,957	46.07	0.12	0.12	0.00
16.50	0.09	2,924	46.05	0.10	0.10	0.00
17.00	0.08	2,901	46.03	0.09	0.09	0.00
17.50	0.07	2,882	46.02	0.08	0.08	0.00
18.00	0.06	2,864	46.01	0.07	0.07	0.00
18.50	0.06	2,850	46.00	0.07	0.07	0.00
19.00	0.06	2,841	45.99	0.06	0.06	0.00
19.50	0.06	2,834	45.99	0.06	0.06	0.00
20.00	0.06	2,828	45.98	0.06	0.06	0.00
20.50	0.05	2,823	45.98	0.06	0.06	0.00
21.00	0.05	2,818	45.98	0.05	0.05	0.00
21.50	0.05	2,813	45.97	0.05	0.05	0.00
22.00	0.05	2,809	45.97	0.05	0.05	0.00
22.50	0.05	2,804	45.97	0.05	0.05	0.00
23.00	0.04	2,799	45.96	0.05	0.05	0.00
23.50	0.04	2,794	45.96	0.04	0.04	0.00
24.00	0.05	2,792	45.96	0.04	0.04	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 91

Stage-Discharge for Pond 43P: Basin 206

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	1.75	1.75	0.00
42.93	0.00	0.00	0.00	48.13	1.80	1.80	0.00
43.03	0.00	0.00	0.00	48.23	2.13	2.13	0.00
43.13	0.00	0.00	0.00	48.33	4.36	4.36	0.00
43.23	0.00	0.00	0.00	48.43	7.72	7.72	0.00
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.33	0.33	0.00				
46.53	0.45	0.45	0.00				
46.63	0.61	0.61	0.00				
46.73	0.76	0.76	0.00				
46.83	0.89	0.89	0.00				
46.93	0.99	0.99	0.00				
47.03	1.08	1.08	0.00				
47.13	1.17	1.17	0.00				
47.23	1.25	1.25	0.00				
47.33	1.32	1.32	0.00				
47.43	1.39	1.39	0.00				
47.53	1.46	1.46	0.00				
47.63	1.52	1.52	0.00				
47.73	1.58	1.58	0.00				
47.83	1.64	1.64	0.00				
47.93	1.70	1.70	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 92

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 4.67" for Adj - 10 Yr event
 Inflow = 8.06 cfs @ 12.09 hrs, Volume= 0.544 af
 Outflow = 1.67 cfs @ 12.37 hrs, Volume= 0.420 af, Atten= 79%, Lag= 16.8 min
 Primary = 1.67 cfs @ 12.37 hrs, Volume= 0.420 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.95' @ 12.37 hrs Surf.Area= 4,060 sf Storage= 12,458 cf

Plug-Flow detention time= 213.9 min calculated for 0.419 af (77% of inflow)
 Center-of-Mass det. time= 130.2 min (883.1 - 752.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 '/' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025


Page 93

Primary OutFlow Max=1.66 cfs @ 12.37 hrs HW=47.95' (Free Discharge)


- 1=Culvert (Passes 1.66 cfs of 12.32 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.08 cfs @ 5.48 fps)
- 5=Orifice/Grate (Orifice Controls 0.59 cfs @ 6.74 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 44P: Basin 112



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 94

Pond 44P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 95

Hydrograph for Pond 44P: Basin 112

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.01	3	42.83	0.00	0.00	0.00
1.50	0.02	29	42.86	0.00	0.00	0.00
2.00	0.03	77	42.91	0.00	0.00	0.00
2.50	0.04	143	42.98	0.00	0.00	0.00
3.00	0.05	225	43.06	0.00	0.00	0.00
3.50	0.06	319	43.15	0.00	0.00	0.00
4.00	0.06	425	43.26	0.00	0.00	0.00
4.50	0.07	542	43.38	0.00	0.00	0.00
5.00	0.07	671	43.51	0.00	0.00	0.00
5.50	0.08	811	43.65	0.00	0.00	0.00
6.00	0.09	960	43.81	0.00	0.00	0.00
6.50	0.10	1,128	43.98	0.00	0.00	0.00
7.00	0.11	1,320	44.17	0.00	0.00	0.00
7.50	0.13	1,539	44.39	0.00	0.00	0.00
8.00	0.14	1,783	44.64	0.00	0.00	0.00
8.50	0.16	2,055	44.86	0.00	0.00	0.00
9.00	0.17	2,354	44.98	0.00	0.00	0.00
9.50	0.22	2,712	45.12	0.00	0.00	0.00
10.00	0.28	3,162	45.29	0.00	0.00	0.00
10.50	0.33	3,707	45.48	0.00	0.00	0.00
11.00	0.53	4,479	45.74	0.00	0.00	0.00
11.50	0.89	5,686	46.11	0.15	0.15	0.00
12.00	4.84	8,856	47.02	1.00	1.00	0.00
12.50	1.42	12,376	47.93	1.65	1.65	0.00
13.00	0.64	11,097	47.61	1.46	1.46	0.00
13.50	0.40	9,616	47.22	1.18	1.18	0.00
14.00	0.32	8,395	46.89	0.86	0.86	0.00
14.50	0.26	7,651	46.68	0.56	0.56	0.00
15.00	0.21	7,231	46.56	0.40	0.40	0.00
15.50	0.19	6,947	46.48	0.32	0.32	0.00
16.00	0.17	6,737	46.42	0.28	0.28	0.00
16.50	0.16	6,553	46.37	0.26	0.26	0.00
17.00	0.15	6,376	46.32	0.24	0.24	0.00
17.50	0.13	6,208	46.27	0.22	0.22	0.00
18.00	0.12	6,048	46.22	0.20	0.20	0.00
18.50	0.11	5,906	46.18	0.18	0.18	0.00
19.00	0.11	5,789	46.14	0.17	0.17	0.00
19.50	0.10	5,696	46.11	0.15	0.15	0.00
20.00	0.10	5,624	46.09	0.14	0.14	0.00
20.50	0.10	5,569	46.08	0.12	0.12	0.00
21.00	0.09	5,527	46.06	0.12	0.12	0.00
21.50	0.09	5,493	46.05	0.11	0.11	0.00
22.00	0.09	5,464	46.04	0.10	0.10	0.00
22.50	0.08	5,440	46.04	0.10	0.10	0.00
23.00	0.08	5,418	46.03	0.09	0.09	0.00
23.50	0.08	5,398	46.02	0.09	0.09	0.00
24.00	0.09	5,382	46.02	0.08	0.08	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 96

Stage-Discharge for Pond 44P: Basin 112

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	2.90	2.90	0.00
42.93	0.00	0.00	0.00	48.13	5.76	5.76	0.00
43.03	0.00	0.00	0.00	48.23	9.57	9.57	0.00
43.13	0.00	0.00	0.00	48.33	13.40	13.40	0.00
43.23	0.00	0.00	0.00	48.43	13.67	13.67	0.00
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.28	0.28	0.00				
46.53	0.36	0.36	0.00				
46.63	0.48	0.48	0.00				
46.73	0.63	0.63	0.00				
46.83	0.79	0.79	0.00				
46.93	0.91	0.91	0.00				
47.03	1.01	1.01	0.00				
47.13	1.10	1.10	0.00				
47.23	1.19	1.19	0.00				
47.33	1.27	1.27	0.00				
47.43	1.34	1.34	0.00				
47.53	1.41	1.41	0.00				
47.63	1.47	1.47	0.00				
47.73	1.54	1.54	0.00				
47.83	1.60	1.60	0.00				
47.93	1.66	1.66	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 126

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.42' @ 23.95 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 7.71" for Adj - 100 Yr event
 Inflow = 42.71 cfs @ 12.12 hrs, Volume= 3.173 af
 Outflow = 13.93 cfs @ 12.32 hrs, Volume= 2.098 af, Atten= 67%, Lag= 12.1 min
 Primary = 13.93 cfs @ 12.32 hrs, Volume= 2.098 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.43' @ 12.32 hrs Surf.Area= 21,564 sf Storage= 65,808 cf

Plug-Flow detention time= 216.8 min calculated for 2.094 af (66% of inflow)
 Center-of-Mass det. time= 112.3 min (885.1 - 772.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 127

Primary OutFlow Max=13.92 cfs @ 12.32 hrs HW=47.43' (Free Discharge)


- 1=Culvert (Inlet Controls 13.92 cfs @ 7.88 fps)
- 3=Orifice/Grate (Passes < 35.81 cfs potential flow)
- 4=Orifice/Grate (Passes < 1.71 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.50 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 128

Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 129

Hydrograph for Pond 39P: Basin 104

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.08	74	42.84	0.00	0.00	0.00
1.50	0.14	277	42.87	0.00	0.00	0.00
2.00	0.18	569	42.91	0.00	0.00	0.00
2.50	0.22	929	42.96	0.00	0.00	0.00
3.00	0.25	1,346	43.03	0.00	0.00	0.00
3.50	0.28	1,821	43.09	0.00	0.00	0.00
4.00	0.31	2,348	43.17	0.00	0.00	0.00
4.50	0.33	2,924	43.25	0.00	0.00	0.00
5.00	0.36	3,543	43.34	0.00	0.00	0.00
5.50	0.38	4,205	43.44	0.00	0.00	0.00
6.00	0.40	4,907	43.54	0.00	0.00	0.00
6.50	0.46	5,678	43.65	0.00	0.00	0.00
7.00	0.52	6,555	43.78	0.00	0.00	0.00
7.50	0.58	7,545	43.92	0.00	0.00	0.00
8.00	0.64	8,646	44.08	0.00	0.00	0.00
8.50	0.71	9,861	44.26	0.00	0.00	0.00
9.00	0.77	11,191	44.45	0.00	0.00	0.00
9.50	1.03	12,780	44.68	0.00	0.00	0.00
10.00	1.37	14,942	44.90	0.00	0.00	0.00
10.50	1.67	17,684	45.05	0.00	0.00	0.00
11.00	2.62	21,466	45.26	0.00	0.00	0.00
11.50	4.58	27,898	45.60	0.00	0.00	0.00
12.00	20.15	44,318	46.41	0.29	0.29	0.00
12.50	8.80	63,684	47.33	13.67	13.67	0.00
13.00	4.45	53,641	46.86	6.48	6.48	0.00
13.50	3.18	51,930	46.78	3.70	3.70	0.00
14.00	2.53	51,242	46.75	2.79	2.79	0.00
14.50	2.05	50,840	46.73	2.27	2.27	0.00
15.00	1.56	50,381	46.70	1.83	1.83	0.00
15.50	1.28	49,975	46.69	1.45	1.45	0.00
16.00	1.14	49,754	46.67	1.23	1.23	0.00
16.50	1.03	49,584	46.67	1.13	1.13	0.00
17.00	0.94	49,407	46.66	1.04	1.04	0.00
17.50	0.85	49,238	46.65	0.94	0.94	0.00
18.00	0.78	49,037	46.64	0.91	0.91	0.00
18.50	0.73	48,792	46.63	0.86	0.86	0.00
19.00	0.71	48,570	46.62	0.82	0.82	0.00
19.50	0.68	48,365	46.61	0.79	0.79	0.00
20.00	0.65	48,171	46.60	0.76	0.76	0.00
20.50	0.63	47,985	46.59	0.73	0.73	0.00
21.00	0.60	47,807	46.58	0.70	0.70	0.00
21.50	0.58	47,634	46.57	0.67	0.67	0.00
22.00	0.55	47,468	46.57	0.64	0.64	0.00
22.50	0.53	47,304	46.56	0.62	0.62	0.00
23.00	0.51	47,140	46.55	0.60	0.60	0.00
23.50	0.48	46,975	46.54	0.57	0.57	0.00
24.00	0.51	46,817	46.53	0.55	0.55	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 130

Stage-Discharge for Pond 39P: Basin 104

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	15.41	15.41	0.00
42.93	0.00	0.00	0.00	48.13	15.64	15.64	0.00
43.03	0.00	0.00	0.00	48.23	15.87	15.87	0.00
43.13	0.00	0.00	0.00	48.33	16.10	16.10	0.00
43.23	0.00	0.00	0.00				
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.30	0.30	0.00				
46.53	0.54	0.54	0.00				
46.63	0.87	0.87	0.00				
46.73	2.35	2.35	0.00				
46.83	5.37	5.37	0.00				
46.93	9.30	9.30	0.00				
47.03	12.85	12.85	0.00				
47.13	13.13	13.13	0.00				
47.23	13.40	13.40	0.00				
47.33	13.67	13.67	0.00				
47.43	13.93	13.93	0.00				
47.53	14.19	14.19	0.00				
47.63	14.44	14.44	0.00				
47.73	14.69	14.69	0.00				
47.83	14.93	14.93	0.00				
47.93	15.17	15.17	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 131

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 1.20' @ 14.20 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 7.83" for Adj - 100 Yr event
 Inflow = 34.27 cfs @ 12.11 hrs, Volume= 2.500 af
 Outflow = 11.00 cfs @ 12.32 hrs, Volume= 1.750 af, Atten= 68%, Lag= 12.1 min
 Primary = 11.00 cfs @ 12.32 hrs, Volume= 1.750 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.00' @ 12.32 hrs Surf.Area= 17,601 sf Storage= 57,107 cf

Plug-Flow detention time= 257.5 min calculated for 1.746 af (70% of inflow)
 Center-of-Mass det. time= 162.2 min (923.0 - 760.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices	
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf	
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78	
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 132

Primary OutFlow Max=10.86 cfs @ 12.32 hrs HW=47.99' (Free Discharge)

- 1=Culvert (Passes 10.86 cfs of 33.00 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 8.30 cfs @ 1.77 fps)
- 4=Orifice/Grate (Orifice Controls 1.96 cfs @ 5.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.60 cfs @ 6.82 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)


- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Culvert

Pond 41P: Basin 203

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 133

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 134

Hydrograph for Pond 41P: Basin 203

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.07	66	42.84	0.00	0.00	0.00
1.50	0.12	245	42.88	0.00	0.00	0.00
2.00	0.16	503	42.94	0.00	0.00	0.00
2.50	0.19	820	43.00	0.00	0.00	0.00
3.00	0.22	1,188	43.08	0.00	0.00	0.00
3.50	0.25	1,605	43.17	0.00	0.00	0.00
4.00	0.27	2,067	43.26	0.00	0.00	0.00
4.50	0.29	2,571	43.37	0.00	0.00	0.00
5.00	0.31	3,112	43.48	0.00	0.00	0.00
5.50	0.33	3,690	43.60	0.00	0.00	0.00
6.00	0.35	4,302	43.73	0.00	0.00	0.00
6.50	0.40	4,973	43.87	0.00	0.00	0.00
7.00	0.45	5,737	44.03	0.00	0.00	0.00
7.50	0.51	6,597	44.21	0.00	0.00	0.00
8.00	0.56	7,554	44.41	0.00	0.00	0.00
8.50	0.61	8,609	44.63	0.00	0.00	0.00
9.00	0.67	9,763	44.85	0.00	0.00	0.00
9.50	0.94	11,184	44.97	0.00	0.00	0.00
10.00	1.22	13,130	45.12	0.00	0.00	0.00
10.50	1.47	15,543	45.31	0.00	0.00	0.00
11.00	2.28	18,850	45.56	0.00	0.00	0.00
11.50	3.90	24,366	45.95	0.04	0.04	0.00
12.00	17.01	38,077	46.86	1.19	1.19	0.00
12.50	7.19	56,098	47.94	8.63	8.63	0.00
13.00	3.74	53,958	47.82	4.50	4.50	0.00
13.50	2.22	52,734	47.74	2.88	2.88	0.00
14.00	1.56	51,568	47.68	2.26	2.26	0.00
14.50	1.28	50,115	47.59	2.18	2.18	0.00
15.00	1.04	48,373	47.49	2.07	2.07	0.00
15.50	0.92	46,491	47.38	1.94	1.94	0.00
16.00	0.84	44,692	47.27	1.81	1.81	0.00
16.50	0.77	43,000	47.16	1.68	1.68	0.00
17.00	0.70	41,423	47.07	1.54	1.54	0.00
17.50	0.63	39,970	46.98	1.41	1.41	0.00
18.00	0.56	38,640	46.89	1.26	1.26	0.00
18.50	0.53	37,486	46.82	1.10	1.10	0.00
19.00	0.51	36,555	46.76	0.97	0.97	0.00
19.50	0.49	35,808	46.71	0.86	0.86	0.00
20.00	0.47	35,206	46.68	0.77	0.77	0.00
20.50	0.45	34,711	46.64	0.70	0.70	0.00
21.00	0.44	34,298	46.62	0.65	0.65	0.00
21.50	0.42	33,945	46.59	0.60	0.60	0.00
22.00	0.40	33,637	46.57	0.56	0.56	0.00
22.50	0.39	33,365	46.56	0.53	0.53	0.00
23.00	0.37	33,118	46.54	0.50	0.50	0.00
23.50	0.36	32,889	46.53	0.48	0.48	0.00
24.00	0.38	32,682	46.51	0.46	0.46	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 135

Stage-Discharge for Pond 41P: Basin 203

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	12.51	12.51	0.00
42.93	0.00	0.00	0.00	48.13	17.42	17.42	0.00
43.03	0.00	0.00	0.00	48.23	22.94	22.94	0.00
43.13	0.00	0.00	0.00	48.33	28.99	28.99	0.00
43.23	0.00	0.00	0.00				
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.34	0.34	0.00				
46.53	0.48	0.48	0.00				
46.63	0.67	0.67	0.00				
46.73	0.89	0.89	0.00				
46.83	1.12	1.12	0.00				
46.93	1.33	1.33	0.00				
47.03	1.49	1.49	0.00				
47.13	1.63	1.63	0.00				
47.23	1.77	1.77	0.00				
47.33	1.89	1.89	0.00				
47.43	2.00	2.00	0.00				
47.53	2.11	2.11	0.00				
47.63	2.22	2.22	0.00				
47.73	2.59	2.59	0.00				
47.83	4.86	4.86	0.00				
47.93	8.27	8.27	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 136

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 8.10" for Adj - 100 Yr event
 Inflow = 7.65 cfs @ 12.08 hrs, Volume= 0.521 af
 Outflow = 7.94 cfs @ 12.11 hrs, Volume= 0.456 af, Atten= 0%, Lag= 1.7 min
 Primary = 7.94 cfs @ 12.11 hrs, Volume= 0.456 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.44' @ 12.11 hrs Surf.Area= 1,858 sf Storage= 6,896 cf

Plug-Flow detention time= 137.2 min calculated for 0.456 af (87% of inflow)
 Center-of-Mass det. time= 76.2 min (819.1 - 742.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025


Page 137

Primary OutFlow Max=7.22 cfs @ 12.11 hrs HW=48.42' (Free Discharge)


- 1=Culvert (Passes 7.22 cfs of 13.63 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 5.28 cfs @ 1.52 fps)
- 4=Orifice/Grate (Orifice Controls 1.29 cfs @ 6.58 fps)
- 5=Orifice/Grate (Orifice Controls 0.66 cfs @ 7.51 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 43P: Basin 206



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 138

Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 139

Hydrograph for Pond 43P: Basin 206

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.02	23	42.87	0.00	0.00	0.00
1.50	0.04	75	42.96	0.00	0.00	0.00
2.00	0.04	147	43.09	0.00	0.00	0.00
2.50	0.05	235	43.24	0.00	0.00	0.00
3.00	0.06	337	43.42	0.00	0.00	0.00
3.50	0.07	450	43.61	0.00	0.00	0.00
4.00	0.07	575	43.83	0.00	0.00	0.00
4.50	0.08	710	44.07	0.00	0.00	0.00
5.00	0.08	854	44.32	0.00	0.00	0.00
5.50	0.09	1,007	44.58	0.00	0.00	0.00
6.00	0.09	1,169	44.84	0.00	0.00	0.00
6.50	0.11	1,347	44.97	0.00	0.00	0.00
7.00	0.12	1,548	45.11	0.00	0.00	0.00
7.50	0.13	1,775	45.27	0.00	0.00	0.00
8.00	0.15	2,025	45.44	0.00	0.00	0.00
8.50	0.16	2,301	45.63	0.00	0.00	0.00
9.00	0.17	2,601	45.83	0.00	0.00	0.00
9.50	0.22	2,894	46.03	0.09	0.09	0.00
10.00	0.27	3,093	46.16	0.17	0.17	0.00
10.50	0.32	3,267	46.27	0.23	0.23	0.00
11.00	0.51	3,531	46.45	0.35	0.35	0.00
11.50	0.86	3,878	46.67	0.67	0.67	0.00
12.00	4.65	5,754	47.81	1.63	1.63	0.00
12.50	1.32	6,234	48.08	1.78	1.78	0.00
13.00	0.59	4,867	47.28	1.29	1.29	0.00
13.50	0.37	3,909	46.69	0.70	0.70	0.00
14.00	0.29	3,579	46.48	0.39	0.39	0.00
14.50	0.24	3,456	46.40	0.30	0.30	0.00
15.00	0.19	3,356	46.33	0.25	0.25	0.00
15.50	0.17	3,258	46.27	0.22	0.22	0.00
16.00	0.16	3,179	46.22	0.20	0.20	0.00
16.50	0.15	3,113	46.17	0.18	0.18	0.00
17.00	0.14	3,059	46.14	0.16	0.16	0.00
17.50	0.12	3,013	46.11	0.14	0.14	0.00
18.00	0.11	2,976	46.08	0.13	0.13	0.00
18.50	0.10	2,949	46.06	0.11	0.11	0.00
19.00	0.10	2,933	46.05	0.11	0.11	0.00
19.50	0.10	2,922	46.05	0.10	0.10	0.00
20.00	0.09	2,914	46.04	0.10	0.10	0.00
20.50	0.09	2,907	46.04	0.09	0.09	0.00
21.00	0.09	2,900	46.03	0.09	0.09	0.00
21.50	0.08	2,893	46.03	0.09	0.09	0.00
22.00	0.08	2,886	46.02	0.08	0.08	0.00
22.50	0.08	2,879	46.02	0.08	0.08	0.00
23.00	0.07	2,872	46.01	0.08	0.08	0.00
23.50	0.07	2,865	46.01	0.07	0.07	0.00
24.00	0.08	2,862	46.01	0.07	0.07	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 140

Stage-Discharge for Pond 43P: Basin 206

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	1.75	1.75	0.00
42.93	0.00	0.00	0.00	48.13	1.80	1.80	0.00
43.03	0.00	0.00	0.00	48.23	2.13	2.13	0.00
43.13	0.00	0.00	0.00	48.33	4.36	4.36	0.00
43.23	0.00	0.00	0.00	48.43	7.72	7.72	0.00
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.33	0.33	0.00				
46.53	0.45	0.45	0.00				
46.63	0.61	0.61	0.00				
46.73	0.76	0.76	0.00				
46.83	0.89	0.89	0.00				
46.93	0.99	0.99	0.00				
47.03	1.08	1.08	0.00				
47.13	1.17	1.17	0.00				
47.23	1.25	1.25	0.00				
47.33	1.32	1.32	0.00				
47.43	1.39	1.39	0.00				
47.53	1.46	1.46	0.00				
47.63	1.52	1.52	0.00				
47.73	1.58	1.58	0.00				
47.83	1.64	1.64	0.00				
47.93	1.70	1.70	0.00				

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 141

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 8.06" for Adj - 100 Yr event
 Inflow = 13.64 cfs @ 12.09 hrs, Volume= 0.938 af
 Outflow = 12.39 cfs @ 12.11 hrs, Volume= 0.808 af, Atten= 9%, Lag= 1.5 min
 Primary = 12.39 cfs @ 12.11 hrs, Volume= 0.808 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.30' @ 12.11 hrs Surf.Area= 4,311 sf Storage= 13,929 cf

Plug-Flow detention time= 164.0 min calculated for 0.806 af (86% of inflow)
 Center-of-Mass det. time= 99.8 min (844.2 - 744.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 '/' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025


Page 142

Primary OutFlow Max=12.12 cfs @ 12.11 hrs HW=48.29' (Free Discharge)

- 1=Culvert (Passes 12.12 cfs of 13.29 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 10.27 cfs @ 1.90 fps)
- 4=Orifice/Grate (Orifice Controls 1.21 cfs @ 6.16 fps)
- 5=Orifice/Grate (Orifice Controls 0.64 cfs @ 7.30 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 44P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const


HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 143

Pond 44P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 144

Hydrograph for Pond 44P: Basin 112

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Outflow (cfs)	Primary (cfs)	Secondary (cfs)
0.00	0.00	0	42.83	0.00	0.00	0.00
0.50	0.00	0	42.83	0.00	0.00	0.00
1.00	0.04	38	42.87	0.00	0.00	0.00
1.50	0.06	128	42.96	0.00	0.00	0.00
2.00	0.08	254	43.09	0.00	0.00	0.00
2.50	0.09	407	43.24	0.00	0.00	0.00
3.00	0.10	584	43.42	0.00	0.00	0.00
3.50	0.12	782	43.62	0.00	0.00	0.00
4.00	0.13	1,001	43.85	0.00	0.00	0.00
4.50	0.14	1,239	44.09	0.00	0.00	0.00
5.00	0.15	1,493	44.35	0.00	0.00	0.00
5.50	0.15	1,764	44.62	0.00	0.00	0.00
6.00	0.16	2,050	44.86	0.00	0.00	0.00
6.50	0.19	2,365	44.99	0.00	0.00	0.00
7.00	0.21	2,724	45.13	0.00	0.00	0.00
7.50	0.24	3,126	45.27	0.00	0.00	0.00
8.00	0.26	3,573	45.43	0.00	0.00	0.00
8.50	0.29	4,064	45.60	0.00	0.00	0.00
9.00	0.31	4,601	45.78	0.00	0.00	0.00
9.50	0.40	5,214	45.97	0.05	0.05	0.00
10.00	0.49	5,809	46.15	0.17	0.17	0.00
10.50	0.58	6,393	46.32	0.24	0.24	0.00
11.00	0.91	7,208	46.56	0.39	0.39	0.00
11.50	1.53	8,338	46.87	0.85	0.85	0.00
12.00	8.23	12,713	48.01	2.49	2.49	0.00
12.50	2.39	12,716	48.01	2.51	2.51	0.00
13.00	1.07	12,060	47.85	1.61	1.61	0.00
13.50	0.67	10,844	47.54	1.42	1.42	0.00
14.00	0.53	9,559	47.21	1.17	1.17	0.00
14.50	0.44	8,558	46.94	0.91	0.91	0.00
15.00	0.35	7,862	46.74	0.65	0.65	0.00
15.50	0.32	7,455	46.63	0.48	0.48	0.00
16.00	0.29	7,223	46.56	0.39	0.39	0.00
16.50	0.27	7,062	46.52	0.35	0.35	0.00
17.00	0.24	6,929	46.48	0.31	0.31	0.00
17.50	0.22	6,804	46.44	0.29	0.29	0.00
18.00	0.20	6,674	46.40	0.27	0.27	0.00
18.50	0.19	6,540	46.36	0.26	0.26	0.00
19.00	0.18	6,418	46.33	0.25	0.25	0.00
19.50	0.18	6,308	46.30	0.23	0.23	0.00
20.00	0.17	6,208	46.27	0.22	0.22	0.00
20.50	0.16	6,117	46.24	0.21	0.21	0.00
21.00	0.16	6,035	46.22	0.20	0.20	0.00
21.50	0.15	5,961	46.19	0.19	0.19	0.00
22.00	0.15	5,894	46.17	0.18	0.18	0.00
22.50	0.14	5,832	46.16	0.17	0.17	0.00
23.00	0.13	5,776	46.14	0.16	0.16	0.00
23.50	0.13	5,724	46.12	0.16	0.16	0.00
24.00	0.15	5,682	46.11	0.15	0.15	0.00

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 145

Stage-Discharge for Pond 44P: Basin 112

Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)	Elevation (feet)	Discharge (cfs)	Primary (cfs)	Secondary (cfs)
42.83	0.00	0.00	0.00	48.03	2.90	2.90	0.00
42.93	0.00	0.00	0.00	48.13	5.76	5.76	0.00
43.03	0.00	0.00	0.00	48.23	9.57	9.57	0.00
43.13	0.00	0.00	0.00	48.33	13.40	13.40	0.00
43.23	0.00	0.00	0.00	48.43	13.67	13.67	0.00
43.33	0.00	0.00	0.00				
43.43	0.00	0.00	0.00				
43.53	0.00	0.00	0.00				
43.63	0.00	0.00	0.00				
43.73	0.00	0.00	0.00				
43.83	0.00	0.00	0.00				
43.93	0.00	0.00	0.00				
44.03	0.00	0.00	0.00				
44.13	0.00	0.00	0.00				
44.23	0.00	0.00	0.00				
44.33	0.00	0.00	0.00				
44.43	0.00	0.00	0.00				
44.53	0.00	0.00	0.00				
44.63	0.00	0.00	0.00				
44.73	0.00	0.00	0.00				
44.83	0.00	0.00	0.00				
44.93	0.00	0.00	0.00				
45.03	0.00	0.00	0.00				
45.13	0.00	0.00	0.00				
45.23	0.00	0.00	0.00				
45.33	0.00	0.00	0.00				
45.43	0.00	0.00	0.00				
45.53	0.00	0.00	0.00				
45.63	0.00	0.00	0.00				
45.73	0.00	0.00	0.00				
45.83	0.00	0.00	0.00				
45.93	0.03	0.03	0.00				
46.03	0.09	0.09	0.00				
46.13	0.16	0.16	0.00				
46.23	0.21	0.21	0.00				
46.33	0.25	0.25	0.00				
46.43	0.28	0.28	0.00				
46.53	0.36	0.36	0.00				
46.63	0.48	0.48	0.00				
46.73	0.63	0.63	0.00				
46.83	0.79	0.79	0.00				
46.93	0.91	0.91	0.00				
47.03	1.01	1.01	0.00				
47.13	1.10	1.10	0.00				
47.23	1.19	1.19	0.00				
47.33	1.27	1.27	0.00				
47.43	1.34	1.34	0.00				
47.53	1.41	1.41	0.00				
47.63	1.47	1.47	0.00				
47.73	1.54	1.54	0.00				
47.83	1.60	1.60	0.00				
47.93	1.66	1.66	0.00				

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 146


Summary for Link 2A: POA 1 (Adj)

Inflow Area = 11.212 ac, 65.35% Impervious, Inflow Depth > 5.53" for Adj - 100 Yr event

Inflow = 30.55 cfs @ 12.28 hrs, Volume= 5.171 af

Primary = 30.55 cfs @ 12.28 hrs, Volume= 5.171 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 147

Hydrograph for Link 2A: POA 1 (Adj)

Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)	Time (hours)	Inflow (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	0.00	0.00	13.00	12.73	0.00	12.73
0.25	0.00	0.00	0.00	13.25	9.46	0.00	9.46
0.50	0.00	0.00	0.00	13.50	7.67	0.00	7.67
0.75	0.01	0.00	0.01	13.75	6.49	0.00	6.49
1.00	0.02	0.00	0.02	14.00	5.92	0.00	5.92
1.25	0.02	0.00	0.02	14.25	5.53	0.00	5.53
1.50	0.02	0.00	0.02	14.50	5.18	0.00	5.18
1.75	0.03	0.00	0.03	14.75	4.85	0.00	4.85
2.00	0.03	0.00	0.03	15.00	4.48	0.00	4.48
2.25	0.03	0.00	0.03	15.25	4.16	0.00	4.16
2.50	0.04	0.00	0.04	15.50	3.91	0.00	3.91
2.75	0.04	0.00	0.04	15.75	3.70	0.00	3.70
3.00	0.04	0.00	0.04	16.00	3.53	0.00	3.53
3.25	0.04	0.00	0.04	16.25	3.39	0.00	3.39
3.50	0.04	0.00	0.04	16.50	3.25	0.00	3.25
3.75	0.05	0.00	0.05	16.75	3.12	0.00	3.12
4.00	0.05	0.00	0.05	17.00	2.99	0.00	2.99
4.25	0.05	0.00	0.05	17.25	2.85	0.00	2.85
4.50	0.05	0.00	0.05	17.50	2.72	0.00	2.72
4.75	0.05	0.00	0.05	17.75	2.61	0.00	2.61
5.00	0.06	0.00	0.06	18.00	2.50	0.00	2.50
5.25	0.07	0.00	0.07	18.25	2.38	0.00	2.38
5.50	0.08	0.00	0.08	18.50	2.28	0.00	2.28
5.75	0.08	0.00	0.08	18.75	2.18	0.00	2.18
6.00	0.09	0.00	0.09	19.00	2.09	0.00	2.09
6.25	0.11	0.00	0.11	19.25	2.01	0.00	2.01
6.50	0.12	0.00	0.12	19.50	1.94	0.00	1.94
6.75	0.13	0.00	0.13	19.75	1.88	0.00	1.88
7.00	0.15	0.00	0.15	20.00	1.81	0.00	1.81
7.25	0.16	0.00	0.16	20.25	1.76	0.00	1.76
7.50	0.18	0.00	0.18	20.50	1.71	0.00	1.71
7.75	0.20	0.00	0.20	20.75	1.66	0.00	1.66
8.00	0.22	0.00	0.22	21.00	1.61	0.00	1.61
8.25	0.24	0.00	0.24	21.25	1.57	0.00	1.57
8.50	0.26	0.00	0.26	21.50	1.53	0.00	1.53
8.75	0.28	0.00	0.28	21.75	1.49	0.00	1.49
9.00	0.30	0.00	0.30	22.00	1.45	0.00	1.45
9.25	0.35	0.00	0.35	22.25	1.42	0.00	1.42
9.50	0.41	0.00	0.41	22.50	1.38	0.00	1.38
9.75	0.47	0.00	0.47	22.75	1.35	0.00	1.35
10.00	0.53	0.00	0.53	23.00	1.33	0.00	1.33
10.25	0.60	0.00	0.60	23.25	1.29	0.00	1.29
10.50	0.67	0.00	0.67	23.50	1.27	0.00	1.27
10.75	0.90	0.00	0.90	23.75	1.24	0.00	1.24
11.00	1.14	0.00	1.14	24.00	1.25	0.00	1.25
11.25	1.60	0.00	1.60				
11.50	2.14	0.00	2.14				
11.75	4.52	0.00	4.52				
12.00	14.04	0.00	14.04				
12.25	30.30	0.00	30.30				
12.50	26.13	0.00	26.13				
12.75	21.03	0.00	21.03				

5.2 STORM MANAGEMENT DESIGN STORM STORAGE DESIGN

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.26' @ 23.90 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 2.63" for Adj - 2 Yr event
 Inflow = 12.10 cfs @ 12.13 hrs, Volume= 1.084 af
 Outflow = 0.21 cfs @ 21.88 hrs, Volume= 0.151 af, Atten= 98%, Lag= 584.9 min
 Primary = 0.21 cfs @ 21.88 hrs, Volume= 0.151 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.24' @ 21.88 hrs Surf.Area= 20,611 sf Storage= 40,754 cf

Plug-Flow detention time= 664.4 min calculated for 0.151 af (14% of inflow)
 Center-of-Mass det. time= 378.7 min (1,174.5 - 795.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 2

Primary OutFlow Max=0.21 cfs @ 21.88 hrs HW=46.24' (Free Discharge)


- 1=Culvert (Passes 0.21 cfs of 9.87 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Controls 0.00 cfs)
- 5=Orifice/Grate (Orifice Controls 0.21 cfs @ 2.43 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 39P: Basin 104

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	17,239	0	48.03	22,054	78,896
42.93	17,239	690	48.13	22,135	81,105
43.03	17,239	1,379	48.23	22,217	83,323
43.13	17,239	2,069	48.33	22,299	85,549
43.23	17,239	2,758			
43.33	17,239	3,448			
43.43	17,239	4,137			
43.53	17,239	4,827			
43.63	17,239	5,516			
43.73	17,239	6,206			
43.83	17,239	6,896			
43.93	17,239	7,585			
44.03	17,239	8,275			
44.13	17,239	8,964			
44.23	17,239	9,654			
44.33	17,239	10,343			
44.43	17,239	11,033			
44.53	17,239	11,723			
44.63	17,239	12,412			
44.73	17,239	13,102			
44.83	17,239	13,791			
44.93	17,492	15,526			
45.03	17,769	17,290			
45.13	18,034	19,080			
45.23	18,301	20,897			
45.33	18,569	22,740			
45.43	18,840	24,610			
45.53	19,113	26,508			
45.63	19,387	28,433			
45.73	19,664	30,386			
45.83	19,942	32,366			
45.93	20,223	34,374			
46.03	20,444	36,409			
46.13	20,523	38,458			
46.23	20,602	40,514			
46.33	20,681	42,578			
46.43	20,760	44,650			
46.53	20,840	46,730			
46.63	20,920	48,818			
46.73	21,000	50,914			
46.83	21,080	53,018			
46.93	21,160	55,130			
47.03	21,240	57,250			
47.13	21,321	59,378			
47.23	21,402	61,514			
47.33	21,483	63,658			
47.43	21,564	65,811			
47.53	21,645	67,971			
47.63	21,726	70,140			
47.73	21,808	72,317			
47.83	21,890	74,501			
47.93	21,972	76,694			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.44' @ 21.65 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 4.34" for Adj - 10 Yr event
 Inflow = 19.36 cfs @ 12.12 hrs, Volume= 1.786 af
 Outflow = 2.12 cfs @ 13.57 hrs, Volume= 0.749 af, Atten= 89%, Lag= 86.7 min
 Primary = 2.12 cfs @ 13.57 hrs, Volume= 0.749 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.72' @ 13.57 hrs Surf.Area= 20,991 sf Storage= 50,681 cf

Plug-Flow detention time= 367.4 min calculated for 0.749 af (42% of inflow)
 Center-of-Mass det. time= 218.3 min (1,005.2 - 786.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 5

Primary OutFlow Max=2.08 cfs @ 13.57 hrs HW=46.72' (Free Discharge)


- 1=Culvert (Passes 2.08 cfs of 11.94 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 0.94 cfs @ 0.86 fps)
- 4=Orifice/Grate (Orifice Controls 0.78 cfs @ 2.08 fps)
- 5=Orifice/Grate (Orifice Controls 0.36 cfs @ 4.12 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 39P: Basin 104

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	17,239	0	48.03	22,054	78,896
42.93	17,239	690	48.13	22,135	81,105
43.03	17,239	1,379	48.23	22,217	83,323
43.13	17,239	2,069	48.33	22,299	85,549
43.23	17,239	2,758			
43.33	17,239	3,448			
43.43	17,239	4,137			
43.53	17,239	4,827			
43.63	17,239	5,516			
43.73	17,239	6,206			
43.83	17,239	6,896			
43.93	17,239	7,585			
44.03	17,239	8,275			
44.13	17,239	8,964			
44.23	17,239	9,654			
44.33	17,239	10,343			
44.43	17,239	11,033			
44.53	17,239	11,723			
44.63	17,239	12,412			
44.73	17,239	13,102			
44.83	17,239	13,791			
44.93	17,492	15,526			
45.03	17,769	17,290			
45.13	18,034	19,080			
45.23	18,301	20,897			
45.33	18,569	22,740			
45.43	18,840	24,610			
45.53	19,113	26,508			
45.63	19,387	28,433			
45.73	19,664	30,386			
45.83	19,942	32,366			
45.93	20,223	34,374			
46.03	20,444	36,409			
46.13	20,523	38,458			
46.23	20,602	40,514			
46.33	20,681	42,578			
46.43	20,760	44,650			
46.53	20,840	46,730			
46.63	20,920	48,818			
46.73	21,000	50,914			
46.83	21,080	53,018			
46.93	21,160	55,130			
47.03	21,240	57,250			
47.13	21,321	59,378			
47.23	21,402	61,514			
47.33	21,483	63,658			
47.43	21,564	65,811			
47.53	21,645	67,971			
47.63	21,726	70,140			
47.73	21,808	72,317			
47.83	21,890	74,501			
47.93	21,972	76,694			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 44P by 0.42' @ 23.95 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 7.71" for Adj - 100 Yr event
 Inflow = 42.71 cfs @ 12.12 hrs, Volume= 3.173 af
 Outflow = 13.93 cfs @ 12.32 hrs, Volume= 2.098 af, Atten= 67%, Lag= 12.1 min
 Primary = 13.93 cfs @ 12.32 hrs, Volume= 2.098 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.43' @ 12.32 hrs Surf.Area= 21,564 sf Storage= 65,808 cf

Plug-Flow detention time= 216.8 min calculated for 2.094 af (66% of inflow)
 Center-of-Mass det. time= 112.3 min (885.1 - 772.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 8

Primary OutFlow Max=13.92 cfs @ 12.32 hrs HW=47.43' (Free Discharge)


- 1=Culvert (Inlet Controls 13.92 cfs @ 7.88 fps)
- 3=Orifice/Grate (Passes < 35.81 cfs potential flow)
- 4=Orifice/Grate (Passes < 1.71 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.50 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 39P: Basin 104

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	17,239	0	48.03	22,054	78,896
42.93	17,239	690	48.13	22,135	81,105
43.03	17,239	1,379	48.23	22,217	83,323
43.13	17,239	2,069	48.33	22,299	85,549
43.23	17,239	2,758			
43.33	17,239	3,448			
43.43	17,239	4,137			
43.53	17,239	4,827			
43.63	17,239	5,516			
43.73	17,239	6,206			
43.83	17,239	6,896			
43.93	17,239	7,585			
44.03	17,239	8,275			
44.13	17,239	8,964			
44.23	17,239	9,654			
44.33	17,239	10,343			
44.43	17,239	11,033			
44.53	17,239	11,723			
44.63	17,239	12,412			
44.73	17,239	13,102			
44.83	17,239	13,791			
44.93	17,492	15,526			
45.03	17,769	17,290			
45.13	18,034	19,080			
45.23	18,301	20,897			
45.33	18,569	22,740			
45.43	18,840	24,610			
45.53	19,113	26,508			
45.63	19,387	28,433			
45.73	19,664	30,386			
45.83	19,942	32,366			
45.93	20,223	34,374			
46.03	20,444	36,409			
46.13	20,523	38,458			
46.23	20,602	40,514			
46.33	20,681	42,578			
46.43	20,760	44,650			
46.53	20,840	46,730			
46.63	20,920	48,818			
46.73	21,000	50,914			
46.83	21,080	53,018			
46.93	21,160	55,130			
47.03	21,240	57,250			
47.13	21,321	59,378			
47.23	21,402	61,514			
47.33	21,483	63,658			
47.43	21,564	65,811			
47.53	21,645	67,971			
47.63	21,726	70,140			
47.73	21,808	72,317			
47.83	21,890	74,501			
47.93	21,972	76,694			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 2.96" for Adj - 2 Yr event
 Inflow = 5.20 cfs @ 12.09 hrs, Volume= 0.344 af
 Outflow = 0.92 cfs @ 12.48 hrs, Volume= 0.224 af, Atten= 82%, Lag= 23.5 min
 Primary = 0.92 cfs @ 12.48 hrs, Volume= 0.224 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.95' @ 12.48 hrs Surf.Area= 3,654 sf Storage= 8,596 cf

Plug-Flow detention time= 252.2 min calculated for 0.224 af (65% of inflow)
 Center-of-Mass det. time= 149.7 min (911.0 - 761.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025


Page 2

Primary OutFlow Max=0.92 cfs @ 12.48 hrs HW=46.94' (Free Discharge)


- 1=Culvert (Passes 0.92 cfs of 7.52 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.51 cfs @ 2.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.41 cfs @ 4.71 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 44P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 44P: Basin 112

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	2,461	0	48.03	4,105	12,796
42.93	2,461	98	48.13	4,181	13,210
43.03	2,461	197	48.23	4,257	13,632
43.13	2,461	295	48.33	4,335	14,061
43.23	2,461	394	48.43	4,413	14,499
43.33	2,461	492			
43.43	2,461	591			
43.53	2,461	689			
43.63	2,461	788			
43.73	2,461	886			
43.83	2,461	984			
43.93	2,461	1,083			
44.03	2,461	1,181			
44.13	2,461	1,280			
44.23	2,461	1,378			
44.33	2,461	1,477			
44.43	2,461	1,575			
44.53	2,461	1,673			
44.63	2,461	1,772			
44.73	2,461	1,870			
44.83	2,461	1,969			
44.93	2,521	2,218			
45.03	2,588	2,473			
45.13	2,656	2,735			
45.23	2,726	3,004			
45.33	2,795	3,280			
45.43	2,866	3,563			
45.53	2,938	3,854			
45.63	3,011	4,151			
45.73	3,084	4,456			
45.83	3,159	4,768			
45.93	3,234	5,088			
46.03	3,298	5,415			
46.13	3,336	5,746			
46.23	3,375	6,082			
46.33	3,413	6,421			
46.43	3,452	6,764			
46.53	3,490	7,112			
46.63	3,530	7,463			
46.73	3,569	7,817			
46.83	3,608	8,176			
46.93	3,648	8,539			
47.03	3,688	8,906			
47.13	3,728	9,277			
47.23	3,767	9,651			
47.33	3,808	10,030			
47.43	3,848	10,413			
47.53	3,889	10,800			
47.63	3,929	11,191			
47.73	3,970	11,586			
47.83	4,011	11,985			
47.93	4,053	12,388			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 4.67" for Adj - 10 Yr event
 Inflow = 8.06 cfs @ 12.09 hrs, Volume= 0.544 af
 Outflow = 1.67 cfs @ 12.37 hrs, Volume= 0.420 af, Atten= 79%, Lag= 16.8 min
 Primary = 1.67 cfs @ 12.37 hrs, Volume= 0.420 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.95' @ 12.37 hrs Surf.Area= 4,060 sf Storage= 12,458 cf

Plug-Flow detention time= 213.9 min calculated for 0.419 af (77% of inflow)
 Center-of-Mass det. time= 130.2 min (883.1 - 752.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025


Page 5

Primary OutFlow Max=1.66 cfs @ 12.37 hrs HW=47.95' (Free Discharge)


- 1=Culvert (Passes 1.66 cfs of 12.32 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.08 cfs @ 5.48 fps)
- 5=Orifice/Grate (Orifice Controls 0.59 cfs @ 6.74 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 44P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 44P: Basin 112

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	2,461	0	48.03	4,105	12,796
42.93	2,461	98	48.13	4,181	13,210
43.03	2,461	197	48.23	4,257	13,632
43.13	2,461	295	48.33	4,335	14,061
43.23	2,461	394	48.43	4,413	14,499
43.33	2,461	492			
43.43	2,461	591			
43.53	2,461	689			
43.63	2,461	788			
43.73	2,461	886			
43.83	2,461	984			
43.93	2,461	1,083			
44.03	2,461	1,181			
44.13	2,461	1,280			
44.23	2,461	1,378			
44.33	2,461	1,477			
44.43	2,461	1,575			
44.53	2,461	1,673			
44.63	2,461	1,772			
44.73	2,461	1,870			
44.83	2,461	1,969			
44.93	2,521	2,218			
45.03	2,588	2,473			
45.13	2,656	2,735			
45.23	2,726	3,004			
45.33	2,795	3,280			
45.43	2,866	3,563			
45.53	2,938	3,854			
45.63	3,011	4,151			
45.73	3,084	4,456			
45.83	3,159	4,768			
45.93	3,234	5,088			
46.03	3,298	5,415			
46.13	3,336	5,746			
46.23	3,375	6,082			
46.33	3,413	6,421			
46.43	3,452	6,764			
46.53	3,490	7,112			
46.63	3,530	7,463			
46.73	3,569	7,817			
46.83	3,608	8,176			
46.93	3,648	8,539			
47.03	3,688	8,906			
47.13	3,728	9,277			
47.23	3,767	9,651			
47.33	3,808	10,030			
47.43	3,848	10,413			
47.53	3,889	10,800			
47.63	3,929	11,191			
47.73	3,970	11,586			
47.83	4,011	11,985			
47.93	4,053	12,388			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 8.06" for Adj - 100 Yr event
 Inflow = 13.64 cfs @ 12.09 hrs, Volume= 0.938 af
 Outflow = 12.39 cfs @ 12.11 hrs, Volume= 0.808 af, Atten= 9%, Lag= 1.5 min
 Primary = 12.39 cfs @ 12.11 hrs, Volume= 0.808 af
 Routed to Pond 39P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.30' @ 12.11 hrs Surf.Area= 4,311 sf Storage= 13,929 cf

Plug-Flow detention time= 164.0 min calculated for 0.806 af (86% of inflow)
 Center-of-Mass det. time= 99.8 min (844.2 - 744.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025


Page 8

Primary OutFlow Max=12.12 cfs @ 12.11 hrs HW=48.29' (Free Discharge)


- 1=Culvert (Passes 12.12 cfs of 13.29 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 10.27 cfs @ 1.90 fps)
- 4=Orifice/Grate (Orifice Controls 1.21 cfs @ 6.16 fps)
- 5=Orifice/Grate (Orifice Controls 0.64 cfs @ 7.30 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 44P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 44P: Basin 112

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	2,461	0	48.03	4,105	12,796
42.93	2,461	98	48.13	4,181	13,210
43.03	2,461	197	48.23	4,257	13,632
43.13	2,461	295	48.33	4,335	14,061
43.23	2,461	394	48.43	4,413	14,499
43.33	2,461	492			
43.43	2,461	591			
43.53	2,461	689			
43.63	2,461	788			
43.73	2,461	886			
43.83	2,461	984			
43.93	2,461	1,083			
44.03	2,461	1,181			
44.13	2,461	1,280			
44.23	2,461	1,378			
44.33	2,461	1,477			
44.43	2,461	1,575			
44.53	2,461	1,673			
44.63	2,461	1,772			
44.73	2,461	1,870			
44.83	2,461	1,969			
44.93	2,521	2,218			
45.03	2,588	2,473			
45.13	2,656	2,735			
45.23	2,726	3,004			
45.33	2,795	3,280			
45.43	2,866	3,563			
45.53	2,938	3,854			
45.63	3,011	4,151			
45.73	3,084	4,456			
45.83	3,159	4,768			
45.93	3,234	5,088			
46.03	3,298	5,415			
46.13	3,336	5,746			
46.23	3,375	6,082			
46.33	3,413	6,421			
46.43	3,452	6,764			
46.53	3,490	7,112			
46.63	3,530	7,463			
46.73	3,569	7,817			
46.83	3,608	8,176			
46.93	3,648	8,539			
47.03	3,688	8,906			
47.13	3,728	9,277			
47.23	3,767	9,651			
47.33	3,808	10,030			
47.43	3,848	10,413			
47.53	3,889	10,800			
47.63	3,929	11,191			
47.73	3,970	11,586			
47.83	4,011	11,985			
47.93	4,053	12,388			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 0.38' @ 18.45 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 2.74" for Adj - 2 Yr event
 Inflow = 10.89 cfs @ 12.12 hrs, Volume= 0.875 af
 Outflow = 0.26 cfs @ 17.17 hrs, Volume= 0.216 af, Atten= 98%, Lag= 302.5 min
 Primary = 0.26 cfs @ 17.17 hrs, Volume= 0.216 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.35' @ 17.17 hrs Surf.Area= 15,084 sf Storage= 30,152 cf

Plug-Flow detention time= 529.0 min calculated for 0.216 af (25% of inflow)
 Center-of-Mass det. time= 329.4 min (1,110.1 - 780.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025

Page 2

Primary OutFlow Max=0.26 cfs @ 17.17 hrs HW=46.35' (Free Discharge)

- 1=Culvert (Passes 0.26 cfs of 29.46 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.01 cfs @ 0.73 fps)
- 5=Orifice/Grate (Orifice Controls 0.25 cfs @ 2.89 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Culvert

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 41P: Basin 203

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	11,929	0	48.03	17,659	57,703
42.93	11,929	477	48.13	17,833	59,477
43.03	11,929	954	48.23	18,007	61,269
43.13	11,929	1,431	48.33	18,183	63,079
43.23	11,929	1,909			
43.33	11,929	2,386			
43.43	11,929	2,863			
43.53	11,929	3,340			
43.63	11,929	3,817			
43.73	11,929	4,294			
43.83	11,929	4,772			
43.93	11,929	5,249			
44.03	11,929	5,726			
44.13	11,929	6,203			
44.23	11,929	6,680			
44.33	11,929	7,157			
44.43	11,929	7,635			
44.53	11,929	8,112			
44.63	11,929	8,589			
44.73	11,929	9,066			
44.83	11,929	9,543			
44.93	12,138	10,745			
45.03	12,366	11,971			
45.13	12,585	13,218			
45.23	12,806	14,488			
45.33	13,029	15,780			
45.43	13,254	17,094			
45.53	13,481	18,431			
45.63	13,709	19,790			
45.73	13,940	21,173			
45.83	14,172	22,578			
45.93	14,407	24,007			
46.03	14,616	25,459			
46.13	14,763	26,928			
46.23	14,911	28,412			
46.33	15,060	29,910			
46.43	15,209	31,424			
46.53	15,359	32,952			
46.63	15,510	34,496			
46.73	15,662	36,054			
46.83	15,814	37,628			
46.93	15,967	39,217			
47.03	16,120	40,822			
47.13	16,270	42,441			
47.23	16,421	44,076			
47.33	16,573	45,725			
47.43	16,725	47,390			
47.53	16,878	49,070			
47.63	17,032	50,766			
47.73	17,186	52,477			
47.83	17,342	54,203			
47.93	17,497	55,945			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 0.70' @ 15.30 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 4.45" for Adj - 10 Yr event
 Inflow = 17.12 cfs @ 12.12 hrs, Volume= 1.421 af
 Outflow = 1.48 cfs @ 13.35 hrs, Volume= 0.713 af, Atten= 91%, Lag= 73.8 min
 Primary = 1.48 cfs @ 13.35 hrs, Volume= 0.713 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.02' @ 13.35 hrs Surf.Area= 16,110 sf Storage= 40,717 cf

Plug-Flow detention time= 340.5 min calculated for 0.713 af (50% of inflow)
 Center-of-Mass det. time= 214.3 min (985.6 - 771.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices	
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf	
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78	
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025

Page 5

Primary OutFlow Max=1.48 cfs @ 13.35 hrs HW=47.02' (Free Discharge)

- 1=Culvert (Passes 1.48 cfs of 30.96 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.05 cfs @ 3.01 fps)
- 5=Orifice/Grate (Orifice Controls 0.43 cfs @ 4.90 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Culvert ☐

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 41P: Basin 203

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	11,929	0	48.03	17,659	57,703
42.93	11,929	477	48.13	17,833	59,477
43.03	11,929	954	48.23	18,007	61,269
43.13	11,929	1,431	48.33	18,183	63,079
43.23	11,929	1,909			
43.33	11,929	2,386			
43.43	11,929	2,863			
43.53	11,929	3,340			
43.63	11,929	3,817			
43.73	11,929	4,294			
43.83	11,929	4,772			
43.93	11,929	5,249			
44.03	11,929	5,726			
44.13	11,929	6,203			
44.23	11,929	6,680			
44.33	11,929	7,157			
44.43	11,929	7,635			
44.53	11,929	8,112			
44.63	11,929	8,589			
44.73	11,929	9,066			
44.83	11,929	9,543			
44.93	12,138	10,745			
45.03	12,366	11,971			
45.13	12,585	13,218			
45.23	12,806	14,488			
45.33	13,029	15,780			
45.43	13,254	17,094			
45.53	13,481	18,431			
45.63	13,709	19,790			
45.73	13,940	21,173			
45.83	14,172	22,578			
45.93	14,407	24,007			
46.03	14,616	25,459			
46.13	14,763	26,928			
46.23	14,911	28,412			
46.33	15,060	29,910			
46.43	15,209	31,424			
46.53	15,359	32,952			
46.63	15,510	34,496			
46.73	15,662	36,054			
46.83	15,814	37,628			
46.93	15,967	39,217			
47.03	16,120	40,822			
47.13	16,270	42,441			
47.23	16,421	44,076			
47.33	16,573	45,725			
47.43	16,725	47,390			
47.53	16,878	49,070			
47.63	17,032	50,766			
47.73	17,186	52,477			
47.83	17,342	54,203			
47.93	17,497	55,945			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 43P by 1.20' @ 14.20 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 7.83" for Adj - 100 Yr event
 Inflow = 34.27 cfs @ 12.11 hrs, Volume= 2.500 af
 Outflow = 11.00 cfs @ 12.32 hrs, Volume= 1.750 af, Atten= 68%, Lag= 12.1 min
 Primary = 11.00 cfs @ 12.32 hrs, Volume= 1.750 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.00' @ 12.32 hrs Surf.Area= 17,601 sf Storage= 57,107 cf

Plug-Flow detention time= 257.5 min calculated for 1.746 af (70% of inflow)
 Center-of-Mass det. time= 162.2 min (923.0 - 760.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices	
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf	
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78	
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025

Page 8

Primary OutFlow Max=10.86 cfs @ 12.32 hrs HW=47.99' (Free Discharge)

- 1=Culvert (Passes 10.86 cfs of 33.00 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 8.30 cfs @ 1.77 fps)
- 4=Orifice/Grate (Orifice Controls 1.96 cfs @ 5.61 fps)
- 5=Orifice/Grate (Orifice Controls 0.60 cfs @ 6.82 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)


- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond 41P: Basin 203

Broad-Crested Rectangular Weir
Orifice/Grate
Orifice/Grate

Culvert

Pond 41P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 41P: Basin 203

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	11,929	0	48.03	17,659	57,703
42.93	11,929	477	48.13	17,833	59,477
43.03	11,929	954	48.23	18,007	61,269
43.13	11,929	1,431	48.33	18,183	63,079
43.23	11,929	1,909			
43.33	11,929	2,386			
43.43	11,929	2,863			
43.53	11,929	3,340			
43.63	11,929	3,817			
43.73	11,929	4,294			
43.83	11,929	4,772			
43.93	11,929	5,249			
44.03	11,929	5,726			
44.13	11,929	6,203			
44.23	11,929	6,680			
44.33	11,929	7,157			
44.43	11,929	7,635			
44.53	11,929	8,112			
44.63	11,929	8,589			
44.73	11,929	9,066			
44.83	11,929	9,543			
44.93	12,138	10,745			
45.03	12,366	11,971			
45.13	12,585	13,218			
45.23	12,806	14,488			
45.33	13,029	15,780			
45.43	13,254	17,094			
45.53	13,481	18,431			
45.63	13,709	19,790			
45.73	13,940	21,173			
45.83	14,172	22,578			
45.93	14,407	24,007			
46.03	14,616	25,459			
46.13	14,763	26,928			
46.23	14,911	28,412			
46.33	15,060	29,910			
46.43	15,209	31,424			
46.53	15,359	32,952			
46.63	15,510	34,496			
46.73	15,662	36,054			
46.83	15,814	37,628			
46.93	15,967	39,217			
47.03	16,120	40,822			
47.13	16,270	42,441			
47.23	16,421	44,076			
47.33	16,573	45,725			
47.43	16,725	47,390			
47.53	16,878	49,070			
47.63	17,032	50,766			
47.73	17,186	52,477			
47.83	17,342	54,203			
47.93	17,497	55,945			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 2.98" for Adj - 2 Yr event
 Inflow = 2.93 cfs @ 12.08 hrs, Volume= 0.192 af
 Outflow = 1.00 cfs @ 12.22 hrs, Volume= 0.129 af, Atten= 66%, Lag= 8.2 min
 Primary = 1.00 cfs @ 12.22 hrs, Volume= 0.129 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.93' @ 12.22 hrs Surf.Area= 1,603 sf Storage= 4,298 cf

Plug-Flow detention time= 211.0 min calculated for 0.129 af (67% of inflow)
 Center-of-Mass det. time= 111.4 min (871.0 - 759.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Printed 12/12/2025


Page 2

Primary OutFlow Max=0.99 cfs @ 12.22 hrs HW=46.93' (Free Discharge)


- 1=Culvert (Passes 0.99 cfs of 7.45 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.58 cfs @ 2.97 fps)
- 5=Orifice/Grate (Orifice Controls 0.41 cfs @ 4.68 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 2 Yr Rainfall=3.36"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 43P: Basin 206

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	1,435	0	48.03	1,782	6,150
42.93	1,435	57	48.13	1,801	6,329
43.03	1,435	115	48.23	1,819	6,510
43.13	1,435	172	48.33	1,837	6,693
43.23	1,435	230	48.43	1,856	6,878
43.33	1,435	287			
43.43	1,435	344			
43.53	1,435	402			
43.63	1,435	459			
43.73	1,435	517			
43.83	1,435	574			
43.93	1,435	631			
44.03	1,435	689			
44.13	1,435	746			
44.23	1,435	804			
44.33	1,435	861			
44.43	1,435	918			
44.53	1,435	976			
44.63	1,435	1,033			
44.73	1,435	1,091			
44.83	1,435	1,148			
44.93	1,435	1,292			
45.03	1,437	1,435			
45.13	1,442	1,579			
45.23	1,447	1,723			
45.33	1,453	1,868			
45.43	1,458	2,014			
45.53	1,463	2,160			
45.63	1,469	2,307			
45.73	1,474	2,454			
45.83	1,480	2,602			
45.93	1,485	2,750			
46.03	1,493	2,899			
46.13	1,505	3,048			
46.23	1,517	3,200			
46.33	1,529	3,352			
46.43	1,541	3,505			
46.53	1,553	3,660			
46.63	1,565	3,816			
46.73	1,578	3,973			
46.83	1,590	4,131			
46.93	1,602	4,291			
47.03	1,616	4,452			
47.13	1,632	4,614			
47.23	1,648	4,778			
47.33	1,665	4,944			
47.43	1,681	5,111			
47.53	1,698	5,280			
47.63	1,715	5,451			
47.73	1,731	5,623			
47.83	1,748	5,797			
47.93	1,765	5,973			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 4.70" for Adj - 10 Yr event
 Inflow = 4.53 cfs @ 12.08 hrs, Volume= 0.303 af
 Outflow = 1.63 cfs @ 12.21 hrs, Volume= 0.239 af, Atten= 64%, Lag= 7.6 min
 Primary = 1.63 cfs @ 12.21 hrs, Volume= 0.239 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.81' @ 12.21 hrs Surf.Area= 1,745 sf Storage= 5,763 cf

Plug-Flow detention time= 174.2 min calculated for 0.238 af (79% of inflow)
 Center-of-Mass det. time= 93.4 min (844.6 - 751.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Printed 12/12/2025


Page 5

Primary OutFlow Max=1.63 cfs @ 12.21 hrs HW=47.81' (Free Discharge)


- 1=Culvert (Passes 1.63 cfs of 11.90 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.06 cfs @ 5.40 fps)
- 5=Orifice/Grate (Orifice Controls 0.57 cfs @ 6.50 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 10 Yr Rainfall=5.10"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 43P: Basin 206

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	1,435	0	48.03	1,782	6,150
42.93	1,435	57	48.13	1,801	6,329
43.03	1,435	115	48.23	1,819	6,510
43.13	1,435	172	48.33	1,837	6,693
43.23	1,435	230	48.43	1,856	6,878
43.33	1,435	287			
43.43	1,435	344			
43.53	1,435	402			
43.63	1,435	459			
43.73	1,435	517			
43.83	1,435	574			
43.93	1,435	631			
44.03	1,435	689			
44.13	1,435	746			
44.23	1,435	804			
44.33	1,435	861			
44.43	1,435	918			
44.53	1,435	976			
44.63	1,435	1,033			
44.73	1,435	1,091			
44.83	1,435	1,148			
44.93	1,435	1,292			
45.03	1,437	1,435			
45.13	1,442	1,579			
45.23	1,447	1,723			
45.33	1,453	1,868			
45.43	1,458	2,014			
45.53	1,463	2,160			
45.63	1,469	2,307			
45.73	1,474	2,454			
45.83	1,480	2,602			
45.93	1,485	2,750			
46.03	1,493	2,899			
46.13	1,505	3,048			
46.23	1,517	3,200			
46.33	1,529	3,352			
46.43	1,541	3,505			
46.53	1,553	3,660			
46.63	1,565	3,816			
46.73	1,578	3,973			
46.83	1,590	4,131			
46.93	1,602	4,291			
47.03	1,616	4,452			
47.13	1,632	4,614			
47.23	1,648	4,778			
47.33	1,665	4,944			
47.43	1,681	5,111			
47.53	1,698	5,280			
47.63	1,715	5,451			
47.73	1,731	5,623			
47.83	1,748	5,797			
47.93	1,765	5,973			

2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 8.10" for Adj - 100 Yr event
 Inflow = 7.65 cfs @ 12.08 hrs, Volume= 0.521 af
 Outflow = 7.94 cfs @ 12.11 hrs, Volume= 0.456 af, Atten= 0%, Lag= 1.7 min
 Primary = 7.94 cfs @ 12.11 hrs, Volume= 0.456 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.44' @ 12.11 hrs Surf.Area= 1,858 sf Storage= 6,896 cf

Plug-Flow detention time= 137.2 min calculated for 0.456 af (87% of inflow)
 Center-of-Mass det. time= 76.2 min (819.1 - 742.9)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Printed 12/12/2025


Page 8

Primary OutFlow Max=7.22 cfs @ 12.11 hrs HW=48.42' (Free Discharge)


- 1=Culvert (Passes 7.22 cfs of 13.63 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 5.28 cfs @ 1.52 fps)
- 4=Orifice/Grate (Orifice Controls 1.29 cfs @ 6.58 fps)
- 5=Orifice/Grate (Orifice Controls 0.66 cfs @ 7.51 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 43P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Adj - 100 Yr Rainfall=8.51"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 43P: Basin 206

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	1,435	0	48.03	1,782	6,150
42.93	1,435	57	48.13	1,801	6,329
43.03	1,435	115	48.23	1,819	6,510
43.13	1,435	172	48.33	1,837	6,693
43.23	1,435	230	48.43	1,856	6,878
43.33	1,435	287			
43.43	1,435	344			
43.53	1,435	402			
43.63	1,435	459			
43.73	1,435	517			
43.83	1,435	574			
43.93	1,435	631			
44.03	1,435	689			
44.13	1,435	746			
44.23	1,435	804			
44.33	1,435	861			
44.43	1,435	918			
44.53	1,435	976			
44.63	1,435	1,033			
44.73	1,435	1,091			
44.83	1,435	1,148			
44.93	1,435	1,292			
45.03	1,437	1,435			
45.13	1,442	1,579			
45.23	1,447	1,723			
45.33	1,453	1,868			
45.43	1,458	2,014			
45.53	1,463	2,160			
45.63	1,469	2,307			
45.73	1,474	2,454			
45.83	1,480	2,602			
45.93	1,485	2,750			
46.03	1,493	2,899			
46.13	1,505	3,048			
46.23	1,517	3,200			
46.33	1,529	3,352			
46.43	1,541	3,505			
46.53	1,553	3,660			
46.63	1,565	3,816			
46.73	1,578	3,973			
46.83	1,590	4,131			
46.93	1,602	4,291			
47.03	1,616	4,452			
47.13	1,632	4,614			
47.23	1,648	4,778			
47.33	1,665	4,944			
47.43	1,681	5,111			
47.53	1,698	5,280			
47.63	1,715	5,451			
47.73	1,731	5,623			
47.83	1,748	5,797			
47.93	1,765	5,973			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 48P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 47P by 0.42' @ 21.65 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 3.12" for Yr 2100 - 2 Yr event
 Inflow = 14.63 cfs @ 12.12 hrs, Volume= 1.285 af
 Outflow = 0.36 cfs @ 18.21 hrs, Volume= 0.272 af, Atten= 98%, Lag= 365.8 min
 Primary = 0.36 cfs @ 18.21 hrs, Volume= 0.272 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.46' @ 18.21 hrs Surf.Area= 20,785 sf Storage= 45,291 cf

Plug-Flow detention time= 563.8 min calculated for 0.272 af (21% of inflow)
 Center-of-Mass det. time= 338.1 min (1,130.1 - 792.0)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 2

Primary OutFlow Max=0.36 cfs @ 18.21 hrs HW=46.46' (Free Discharge)


- 1=Culvert (Passes 0.36 cfs of 11.13 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.07 cfs @ 0.79 fps)
- 5=Orifice/Grate (Orifice Controls 0.29 cfs @ 3.32 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 48P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 48P: Basin 104

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	17,239	0	48.03	22,054	78,896
42.93	17,239	690	48.13	22,135	81,105
43.03	17,239	1,379	48.23	22,217	83,323
43.13	17,239	2,069	48.33	22,299	85,549
43.23	17,239	2,758			
43.33	17,239	3,448			
43.43	17,239	4,137			
43.53	17,239	4,827			
43.63	17,239	5,516			
43.73	17,239	6,206			
43.83	17,239	6,896			
43.93	17,239	7,585			
44.03	17,239	8,275			
44.13	17,239	8,964			
44.23	17,239	9,654			
44.33	17,239	10,343			
44.43	17,239	11,033			
44.53	17,239	11,723			
44.63	17,239	12,412			
44.73	17,239	13,102			
44.83	17,239	13,791			
44.93	17,492	15,526			
45.03	17,769	17,290			
45.13	18,034	19,080			
45.23	18,301	20,897			
45.33	18,569	22,740			
45.43	18,840	24,610			
45.53	19,113	26,508			
45.63	19,387	28,433			
45.73	19,664	30,386			
45.83	19,942	32,366			
45.93	20,223	34,374			
46.03	20,444	36,409			
46.13	20,523	38,458			
46.23	20,602	40,514			
46.33	20,681	42,578			
46.43	20,760	44,650			
46.53	20,840	46,730			
46.63	20,920	48,818			
46.73	21,000	50,914			
46.83	21,080	53,018			
46.93	21,160	55,130			
47.03	21,240	57,250			
47.13	21,321	59,378			
47.23	21,402	61,514			
47.33	21,483	63,658			
47.43	21,564	65,811			
47.53	21,645	67,971			
47.63	21,726	70,140			
47.73	21,808	72,317			
47.83	21,890	74,501			
47.93	21,972	76,694			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 48P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 47P by 0.44' @ 22.85 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 5.08" for Yr 2100 - 10 Yr event
 Inflow = 24.00 cfs @ 12.13 hrs, Volume= 2.090 af
 Outflow = 3.94 cfs @ 12.81 hrs, Volume= 1.044 af, Atten= 84%, Lag= 40.7 min
 Primary = 3.94 cfs @ 12.81 hrs, Volume= 1.044 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.79' @ 12.81 hrs Surf.Area= 21,045 sf Storage= 52,109 cf

Plug-Flow detention time= 306.7 min calculated for 1.044 af (50% of inflow)
 Center-of-Mass det. time= 174.1 min (956.7 - 782.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 ' / Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025

Page 5

Primary OutFlow Max=3.94 cfs @ 12.81 hrs HW=46.79' (Free Discharge)


- 1=Culvert (Passes 3.94 cfs of 12.14 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 2.65 cfs @ 1.21 fps)
- 4=Orifice/Grate (Orifice Controls 0.91 cfs @ 2.44 fps)
- 5=Orifice/Grate (Orifice Controls 0.38 cfs @ 4.31 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 48P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 48P: Basin 104

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	17,239	0	48.03	22,054	78,896
42.93	17,239	690	48.13	22,135	81,105
43.03	17,239	1,379	48.23	22,217	83,323
43.13	17,239	2,069	48.33	22,299	85,549
43.23	17,239	2,758			
43.33	17,239	3,448			
43.43	17,239	4,137			
43.53	17,239	4,827			
43.63	17,239	5,516			
43.73	17,239	6,206			
43.83	17,239	6,896			
43.93	17,239	7,585			
44.03	17,239	8,275			
44.13	17,239	8,964			
44.23	17,239	9,654			
44.33	17,239	10,343			
44.43	17,239	11,033			
44.53	17,239	11,723			
44.63	17,239	12,412			
44.73	17,239	13,102			
44.83	17,239	13,791			
44.93	17,492	15,526			
45.03	17,769	17,290			
45.13	18,034	19,080			
45.23	18,301	20,897			
45.33	18,569	22,740			
45.43	18,840	24,610			
45.53	19,113	26,508			
45.63	19,387	28,433			
45.73	19,664	30,386			
45.83	19,942	32,366			
45.93	20,223	34,374			
46.03	20,444	36,409			
46.13	20,523	38,458			
46.23	20,602	40,514			
46.33	20,681	42,578			
46.43	20,760	44,650			
46.53	20,840	46,730			
46.63	20,920	48,818			
46.73	21,000	50,914			
46.83	21,080	53,018			
46.93	21,160	55,130			
47.03	21,240	57,250			
47.13	21,321	59,378			
47.23	21,402	61,514			
47.33	21,483	63,658			
47.43	21,564	65,811			
47.53	21,645	67,971			
47.63	21,726	70,140			
47.73	21,808	72,317			
47.83	21,890	74,501			
47.93	21,972	76,694			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 48P: Basin 104

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 47P by 0.37' @ 23.95 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 10.31" for Yr 2100 - 100 Yr event
 Inflow = 54.87 cfs @ 12.11 hrs, Volume= 4.244 af
 Outflow = 16.07 cfs @ 12.34 hrs, Volume= 3.146 af, Atten= 71%, Lag= 13.8 min
 Primary = 16.07 cfs @ 12.34 hrs, Volume= 3.146 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.32' @ 12.34 hrs Surf.Area= 22,290 sf Storage= 85,305 cf

Plug-Flow detention time= 189.7 min calculated for 3.140 af (74% of inflow)
 Center-of-Mass det. time= 98.9 min (864.3 - 765.5)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 8

Primary OutFlow Max=16.07 cfs @ 12.34 hrs HW=48.32' (Free Discharge)


- 1=Culvert (Inlet Controls 16.07 cfs @ 9.09 fps)
- 3=Orifice/Grate (Passes < 99.49 cfs potential flow)
- 4=Orifice/Grate (Passes < 2.42 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.64 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 48P: Basin 104



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 48P: Basin 104

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	17,239	0	48.03	22,054	78,896
42.93	17,239	690	48.13	22,135	81,105
43.03	17,239	1,379	48.23	22,217	83,323
43.13	17,239	2,069	48.33	22,299	85,549
43.23	17,239	2,758			
43.33	17,239	3,448			
43.43	17,239	4,137			
43.53	17,239	4,827			
43.63	17,239	5,516			
43.73	17,239	6,206			
43.83	17,239	6,896			
43.93	17,239	7,585			
44.03	17,239	8,275			
44.13	17,239	8,964			
44.23	17,239	9,654			
44.33	17,239	10,343			
44.43	17,239	11,033			
44.53	17,239	11,723			
44.63	17,239	12,412			
44.73	17,239	13,102			
44.83	17,239	13,791			
44.93	17,492	15,526			
45.03	17,769	17,290			
45.13	18,034	19,080			
45.23	18,301	20,897			
45.33	18,569	22,740			
45.43	18,840	24,610			
45.53	19,113	26,508			
45.63	19,387	28,433			
45.73	19,664	30,386			
45.83	19,942	32,366			
45.93	20,223	34,374			
46.03	20,444	36,409			
46.13	20,523	38,458			
46.23	20,602	40,514			
46.33	20,681	42,578			
46.43	20,760	44,650			
46.53	20,840	46,730			
46.63	20,920	48,818			
46.73	21,000	50,914			
46.83	21,080	53,018			
46.93	21,160	55,130			
47.03	21,240	57,250			
47.13	21,321	59,378			
47.23	21,402	61,514			
47.33	21,483	63,658			
47.43	21,564	65,811			
47.53	21,645	67,971			
47.63	21,726	70,140			
47.73	21,808	72,317			
47.83	21,890	74,501			
47.93	21,972	76,694			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 47P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 3.45" for Yr 2100 - 2 Yr event
 Inflow = 6.05 cfs @ 12.09 hrs, Volume= 0.401 af
 Outflow = 1.20 cfs @ 12.38 hrs, Volume= 0.280 af, Atten= 80%, Lag= 17.5 min
 Primary = 1.20 cfs @ 12.38 hrs, Volume= 0.280 af
 Routed to Pond 48P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 48P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.24' @ 12.38 hrs Surf.Area= 3,773 sf Storage= 9,699 cf

Plug-Flow detention time= 235.4 min calculated for 0.279 af (70% of inflow)
 Center-of-Mass det. time= 140.1 min (898.3 - 758.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025


Page 2

Primary OutFlow Max=1.20 cfs @ 12.38 hrs HW=47.24' (Free Discharge)


- 1=Culvert (Passes 1.20 cfs of 9.18 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.73 cfs @ 3.71 fps)
- 5=Orifice/Grate (Orifice Controls 0.47 cfs @ 5.40 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 47P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 47P: Basin 112

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	2,461	0	48.03	4,105	12,796
42.93	2,461	98	48.13	4,181	13,210
43.03	2,461	197	48.23	4,257	13,632
43.13	2,461	295	48.33	4,335	14,061
43.23	2,461	394	48.43	4,413	14,499
43.33	2,461	492			
43.43	2,461	591			
43.53	2,461	689			
43.63	2,461	788			
43.73	2,461	886			
43.83	2,461	984			
43.93	2,461	1,083			
44.03	2,461	1,181			
44.13	2,461	1,280			
44.23	2,461	1,378			
44.33	2,461	1,477			
44.43	2,461	1,575			
44.53	2,461	1,673			
44.63	2,461	1,772			
44.73	2,461	1,870			
44.83	2,461	1,969			
44.93	2,521	2,218			
45.03	2,588	2,473			
45.13	2,656	2,735			
45.23	2,726	3,004			
45.33	2,795	3,280			
45.43	2,866	3,563			
45.53	2,938	3,854			
45.63	3,011	4,151			
45.73	3,084	4,456			
45.83	3,159	4,768			
45.93	3,234	5,088			
46.03	3,298	5,415			
46.13	3,336	5,746			
46.23	3,375	6,082			
46.33	3,413	6,421			
46.43	3,452	6,764			
46.53	3,490	7,112			
46.63	3,530	7,463			
46.73	3,569	7,817			
46.83	3,608	8,176			
46.93	3,648	8,539			
47.03	3,688	8,906			
47.13	3,728	9,277			
47.23	3,767	9,651			
47.33	3,808	10,030			
47.43	3,848	10,413			
47.53	3,889	10,800			
47.63	3,929	11,191			
47.73	3,970	11,586			
47.83	4,011	11,985			
47.93	4,053	12,388			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 47P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 5.42" for Yr 2100 - 10 Yr event
 Inflow = 9.34 cfs @ 12.09 hrs, Volume= 0.630 af
 Outflow = 4.34 cfs @ 12.19 hrs, Volume= 0.506 af, Atten= 54%, Lag= 6.2 min
 Primary = 4.34 cfs @ 12.19 hrs, Volume= 0.506 af
 Routed to Pond 48P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 48P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.08' @ 12.19 hrs Surf.Area= 4,145 sf Storage= 13,017 cf

Plug-Flow detention time= 200.2 min calculated for 0.506 af (80% of inflow)
 Center-of-Mass det. time= 121.1 min (871.4 - 750.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025


Page 5

Primary OutFlow Max=4.18 cfs @ 12.19 hrs HW=48.08' (Free Discharge)


- 1=Culvert (Passes 4.18 cfs of 12.71 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 2.44 cfs @ 1.18 fps)
- 4=Orifice/Grate (Orifice Controls 1.13 cfs @ 5.76 fps)
- 5=Orifice/Grate (Orifice Controls 0.61 cfs @ 6.97 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 47P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 47P: Basin 112

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	2,461	0	48.03	4,105	12,796
42.93	2,461	98	48.13	4,181	13,210
43.03	2,461	197	48.23	4,257	13,632
43.13	2,461	295	48.33	4,335	14,061
43.23	2,461	394	48.43	4,413	14,499
43.33	2,461	492			
43.43	2,461	591			
43.53	2,461	689			
43.63	2,461	788			
43.73	2,461	886			
43.83	2,461	984			
43.93	2,461	1,083			
44.03	2,461	1,181			
44.13	2,461	1,280			
44.23	2,461	1,378			
44.33	2,461	1,477			
44.43	2,461	1,575			
44.53	2,461	1,673			
44.63	2,461	1,772			
44.73	2,461	1,870			
44.83	2,461	1,969			
44.93	2,521	2,218			
45.03	2,588	2,473			
45.13	2,656	2,735			
45.23	2,726	3,004			
45.33	2,795	3,280			
45.43	2,866	3,563			
45.53	2,938	3,854			
45.63	3,011	4,151			
45.73	3,084	4,456			
45.83	3,159	4,768			
45.93	3,234	5,088			
46.03	3,298	5,415			
46.13	3,336	5,746			
46.23	3,375	6,082			
46.33	3,413	6,421			
46.43	3,452	6,764			
46.53	3,490	7,112			
46.63	3,530	7,463			
46.73	3,569	7,817			
46.83	3,608	8,176			
46.93	3,648	8,539			
47.03	3,688	8,906			
47.13	3,728	9,277			
47.23	3,767	9,651			
47.33	3,808	10,030			
47.43	3,848	10,413			
47.53	3,889	10,800			
47.63	3,929	11,191			
47.73	3,970	11,586			
47.83	4,011	11,985			
47.93	4,053	12,388			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 47P: Basin 112

[92] Warning: Device #2 is above defined storage

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 10.68" for Yr 2100 - 100 Yr event
 Inflow = 18.03 cfs @ 12.09 hrs, Volume= 1.243 af
 Outflow = 13.98 cfs @ 12.13 hrs, Volume= 1.105 af, Atten= 22%, Lag= 2.4 min
 Primary = 13.98 cfs @ 12.13 hrs, Volume= 1.105 af
 Routed to Pond 48P : Basin 104
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 48P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.48' @ 12.13 hrs Surf.Area= 4,454 sf Storage= 14,729 cf

Plug-Flow detention time= 141.8 min calculated for 1.105 af (89% of inflow)
 Center-of-Mass det. time= 85.6 min (826.2 - 740.6)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf	
#2	Secondary	48.50'	20.0' long + 0.3 ' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74	
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600	Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025


Page 8

Primary OutFlow Max=13.74 cfs @ 12.13 hrs HW=48.46' (Free Discharge)


- 1=Culvert (Inlet Controls 13.74 cfs @ 7.78 fps)
- 3=Orifice/Grate (Passes < 18.95 cfs potential flow)
- 4=Orifice/Grate (Passes < 1.27 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.66 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 47P: Basin 112



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 47P: Basin 112

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	2,461	0	48.03	4,105	12,796
42.93	2,461	98	48.13	4,181	13,210
43.03	2,461	197	48.23	4,257	13,632
43.13	2,461	295	48.33	4,335	14,061
43.23	2,461	394	48.43	4,413	14,499
43.33	2,461	492			
43.43	2,461	591			
43.53	2,461	689			
43.63	2,461	788			
43.73	2,461	886			
43.83	2,461	984			
43.93	2,461	1,083			
44.03	2,461	1,181			
44.13	2,461	1,280			
44.23	2,461	1,378			
44.33	2,461	1,477			
44.43	2,461	1,575			
44.53	2,461	1,673			
44.63	2,461	1,772			
44.73	2,461	1,870			
44.83	2,461	1,969			
44.93	2,521	2,218			
45.03	2,588	2,473			
45.13	2,656	2,735			
45.23	2,726	3,004			
45.33	2,795	3,280			
45.43	2,866	3,563			
45.53	2,938	3,854			
45.63	3,011	4,151			
45.73	3,084	4,456			
45.83	3,159	4,768			
45.93	3,234	5,088			
46.03	3,298	5,415			
46.13	3,336	5,746			
46.23	3,375	6,082			
46.33	3,413	6,421			
46.43	3,452	6,764			
46.53	3,490	7,112			
46.63	3,530	7,463			
46.73	3,569	7,817			
46.83	3,608	8,176			
46.93	3,648	8,539			
47.03	3,688	8,906			
47.13	3,728	9,277			
47.23	3,767	9,651			
47.33	3,808	10,030			
47.43	3,848	10,413			
47.53	3,889	10,800			
47.63	3,929	11,191			
47.73	3,970	11,586			
47.83	4,011	11,985			
47.93	4,053	12,388			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 49P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 51P by 0.50' @ 16.35 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 3.23" for Yr 2100 - 2 Yr event
 Inflow = 12.85 cfs @ 12.12 hrs, Volume= 1.031 af
 Outflow = 0.51 cfs @ 14.89 hrs, Volume= 0.348 af, Atten= 96%, Lag= 166.1 min
 Primary = 0.51 cfs @ 14.89 hrs, Volume= 0.348 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 46.55' @ 14.89 hrs Surf.Area= 15,385 sf Storage= 33,213 cf

Plug-Flow detention time= 447.3 min calculated for 0.347 af (34% of inflow)
 Center-of-Mass det. time= 284.1 min (1,061.3 - 777.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025

Page 2

Primary OutFlow Max=0.51 cfs @ 14.89 hrs HW=46.55' (Free Discharge)

- 1=Culvert (Passes 0.51 cfs of 29.91 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.20 cfs @ 1.69 fps)
- 5=Orifice/Grate (Orifice Controls 0.31 cfs @ 3.60 fps)


Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Culvert

Pond 49P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 49P: Basin 203

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	11,929	0	48.03	17,659	57,703
42.93	11,929	477	48.13	17,833	59,477
43.03	11,929	954	48.23	18,007	61,269
43.13	11,929	1,431	48.33	18,183	63,079
43.23	11,929	1,909			
43.33	11,929	2,386			
43.43	11,929	2,863			
43.53	11,929	3,340			
43.63	11,929	3,817			
43.73	11,929	4,294			
43.83	11,929	4,772			
43.93	11,929	5,249			
44.03	11,929	5,726			
44.13	11,929	6,203			
44.23	11,929	6,680			
44.33	11,929	7,157			
44.43	11,929	7,635			
44.53	11,929	8,112			
44.63	11,929	8,589			
44.73	11,929	9,066			
44.83	11,929	9,543			
44.93	12,138	10,745			
45.03	12,366	11,971			
45.13	12,585	13,218			
45.23	12,806	14,488			
45.33	13,029	15,780			
45.43	13,254	17,094			
45.53	13,481	18,431			
45.63	13,709	19,790			
45.73	13,940	21,173			
45.83	14,172	22,578			
45.93	14,407	24,007			
46.03	14,616	25,459			
46.13	14,763	26,928			
46.23	14,911	28,412			
46.33	15,060	29,910			
46.43	15,209	31,424			
46.53	15,359	32,952			
46.63	15,510	34,496			
46.73	15,662	36,054			
46.83	15,814	37,628			
46.93	15,967	39,217			
47.03	16,120	40,822			
47.13	16,270	42,441			
47.23	16,421	44,076			
47.33	16,573	45,725			
47.43	16,725	47,390			
47.53	16,878	49,070			
47.63	17,032	50,766			
47.73	17,186	52,477			
47.83	17,342	54,203			
47.93	17,497	55,945			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 49P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 51P by 0.90' @ 14.15 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 5.19" for Yr 2100 - 10 Yr event
 Inflow = 19.80 cfs @ 12.12 hrs, Volume= 1.658 af
 Outflow = 1.92 cfs @ 13.27 hrs, Volume= 0.939 af, Atten= 90%, Lag= 68.9 min
 Primary = 1.92 cfs @ 13.27 hrs, Volume= 0.939 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.36' @ 13.27 hrs Surf.Area= 16,619 sf Storage= 46,223 cf

Plug-Flow detention time= 318.9 min calculated for 0.937 af (56% of inflow)
 Center-of-Mass det. time= 203.7 min (972.1 - 768.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025


Page 5

Primary OutFlow Max=1.93 cfs @ 13.27 hrs HW=47.36' (Free Discharge)

- 1=Culvert (Passes 1.93 cfs of 31.68 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.43 cfs @ 4.10 fps)
- 5=Orifice/Grate (Orifice Controls 0.49 cfs @ 5.64 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 49P: Basin 203

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	11,929	0	48.03	17,659	57,703
42.93	11,929	477	48.13	17,833	59,477
43.03	11,929	954	48.23	18,007	61,269
43.13	11,929	1,431	48.33	18,183	63,079
43.23	11,929	1,909			
43.33	11,929	2,386			
43.43	11,929	2,863			
43.53	11,929	3,340			
43.63	11,929	3,817			
43.73	11,929	4,294			
43.83	11,929	4,772			
43.93	11,929	5,249			
44.03	11,929	5,726			
44.13	11,929	6,203			
44.23	11,929	6,680			
44.33	11,929	7,157			
44.43	11,929	7,635			
44.53	11,929	8,112			
44.63	11,929	8,589			
44.73	11,929	9,066			
44.83	11,929	9,543			
44.93	12,138	10,745			
45.03	12,366	11,971			
45.13	12,585	13,218			
45.23	12,806	14,488			
45.33	13,029	15,780			
45.43	13,254	17,094			
45.53	13,481	18,431			
45.63	13,709	19,790			
45.73	13,940	21,173			
45.83	14,172	22,578			
45.93	14,407	24,007			
46.03	14,616	25,459			
46.13	14,763	26,928			
46.23	14,911	28,412			
46.33	15,060	29,910			
46.43	15,209	31,424			
46.53	15,359	32,952			
46.63	15,510	34,496			
46.73	15,662	36,054			
46.83	15,814	37,628			
46.93	15,967	39,217			
47.03	16,120	40,822			
47.13	16,270	42,441			
47.23	16,421	44,076			
47.33	16,573	45,725			
47.43	16,725	47,390			
47.53	16,878	49,070			
47.63	17,032	50,766			
47.73	17,186	52,477			
47.83	17,342	54,203			
47.93	17,497	55,945			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 49P: Basin 203

[92] Warning: Device #2 is above defined storage

[81] Warning: Exceeded Pond 51P by 1.20' @ 14.55 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 10.45" for Yr 2100 - 100 Yr event
 Inflow = 44.33 cfs @ 12.11 hrs, Volume= 3.335 af
 Outflow = 30.74 cfs @ 12.19 hrs, Volume= 2.561 af, Atten= 31%, Lag= 4.9 min
 Primary = 30.74 cfs @ 12.19 hrs, Volume= 2.561 af
 Routed to Link 24L : POA 1 (2100)
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Link 24L : POA 1 (2100)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.36' @ 12.19 hrs Surf.Area= 18,231 sf Storage= 63,575 cf

Plug-Flow detention time= 217.5 min calculated for 2.556 af (77% of inflow)
 Center-of-Mass det. time= 133.1 min (888.5 - 755.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 ' / Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025

Page 8

Primary OutFlow Max=30.23 cfs @ 12.19 hrs HW=48.35' (Free Discharge)

- 1=Culvert (Passes 30.23 cfs of 33.71 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 27.38 cfs @ 2.64 fps)
- 4=Orifice/Grate (Orifice Controls 2.20 cfs @ 6.31 fps)
- 5=Orifice/Grate (Orifice Controls 0.65 cfs @ 7.40 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)




Pond 49P: Basin 203

Broad-Crested Rectangular Weir
Orifice/Grate
Orifice/Grate

Culvert

Pond 49P: Basin 203



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 49P: Basin 203

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	11,929	0	48.03	17,659	57,703
42.93	11,929	477	48.13	17,833	59,477
43.03	11,929	954	48.23	18,007	61,269
43.13	11,929	1,431	48.33	18,183	63,079
43.23	11,929	1,909			
43.33	11,929	2,386			
43.43	11,929	2,863			
43.53	11,929	3,340			
43.63	11,929	3,817			
43.73	11,929	4,294			
43.83	11,929	4,772			
43.93	11,929	5,249			
44.03	11,929	5,726			
44.13	11,929	6,203			
44.23	11,929	6,680			
44.33	11,929	7,157			
44.43	11,929	7,635			
44.53	11,929	8,112			
44.63	11,929	8,589			
44.73	11,929	9,066			
44.83	11,929	9,543			
44.93	12,138	10,745			
45.03	12,366	11,971			
45.13	12,585	13,218			
45.23	12,806	14,488			
45.33	13,029	15,780			
45.43	13,254	17,094			
45.53	13,481	18,431			
45.63	13,709	19,790			
45.73	13,940	21,173			
45.83	14,172	22,578			
45.93	14,407	24,007			
46.03	14,616	25,459			
46.13	14,763	26,928			
46.23	14,911	28,412			
46.33	15,060	29,910			
46.43	15,209	31,424			
46.53	15,359	32,952			
46.63	15,510	34,496			
46.73	15,662	36,054			
46.83	15,814	37,628			
46.93	15,967	39,217			
47.03	16,120	40,822			
47.13	16,270	42,441			
47.23	16,421	44,076			
47.33	16,573	45,725			
47.43	16,725	47,390			
47.53	16,878	49,070			
47.63	17,032	50,766			
47.73	17,186	52,477			
47.83	17,342	54,203			
47.93	17,497	55,945			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Summary for Pond 51P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 3.48" for Yr 2100 - 2 Yr event
 Inflow = 3.40 cfs @ 12.08 hrs, Volume= 0.224 af
 Outflow = 1.24 cfs @ 12.20 hrs, Volume= 0.160 af, Atten= 63%, Lag= 7.4 min
 Primary = 1.24 cfs @ 12.20 hrs, Volume= 0.160 af
 Routed to Pond 49P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 49P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 47.22' @ 12.20 hrs Surf.Area= 1,647 sf Storage= 4,761 cf

Plug-Flow detention time= 197.0 min calculated for 0.160 af (72% of inflow)
 Center-of-Mass det. time= 103.5 min (860.1 - 756.5)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Printed 12/12/2025


Page 2

Primary OutFlow Max=1.24 cfs @ 12.20 hrs HW=47.22' (Free Discharge)


- 1=Culvert (Passes 1.24 cfs of 9.00 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 0.77 cfs @ 3.93 fps)
- 5=Orifice/Grate (Orifice Controls 0.47 cfs @ 5.34 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 51P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 2 Yr Rainfall=3.86"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 3

Stage-Area-Storage for Pond 51P: Basin 206

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	1,435	0	48.03	1,782	6,150
42.93	1,435	57	48.13	1,801	6,329
43.03	1,435	115	48.23	1,819	6,510
43.13	1,435	172	48.33	1,837	6,693
43.23	1,435	230	48.43	1,856	6,878
43.33	1,435	287			
43.43	1,435	344			
43.53	1,435	402			
43.63	1,435	459			
43.73	1,435	517			
43.83	1,435	574			
43.93	1,435	631			
44.03	1,435	689			
44.13	1,435	746			
44.23	1,435	804			
44.33	1,435	861			
44.43	1,435	918			
44.53	1,435	976			
44.63	1,435	1,033			
44.73	1,435	1,091			
44.83	1,435	1,148			
44.93	1,435	1,292			
45.03	1,437	1,435			
45.13	1,442	1,579			
45.23	1,447	1,723			
45.33	1,453	1,868			
45.43	1,458	2,014			
45.53	1,463	2,160			
45.63	1,469	2,307			
45.73	1,474	2,454			
45.83	1,480	2,602			
45.93	1,485	2,750			
46.03	1,493	2,899			
46.13	1,505	3,048			
46.23	1,517	3,200			
46.33	1,529	3,352			
46.43	1,541	3,505			
46.53	1,553	3,660			
46.63	1,565	3,816			
46.73	1,578	3,973			
46.83	1,590	4,131			
46.93	1,602	4,291			
47.03	1,616	4,452			
47.13	1,632	4,614			
47.23	1,648	4,778			
47.33	1,665	4,944			
47.43	1,681	5,111			
47.53	1,698	5,280			
47.63	1,715	5,451			
47.73	1,731	5,623			
47.83	1,748	5,797			
47.93	1,765	5,973			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Pond 51P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 5.45" for Yr 2100 - 10 Yr event
 Inflow = 5.23 cfs @ 12.08 hrs, Volume= 0.351 af
 Outflow = 1.80 cfs @ 12.21 hrs, Volume= 0.286 af, Atten= 66%, Lag= 8.0 min
 Primary = 1.80 cfs @ 12.21 hrs, Volume= 0.286 af
 Routed to Pond 49P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 49P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.12' @ 12.21 hrs Surf.Area= 1,799 sf Storage= 6,316 cf

Plug-Flow detention time= 165.8 min calculated for 0.286 af (82% of inflow)
 Center-of-Mass det. time= 89.7 min (838.4 - 748.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Printed 12/12/2025


Page 5

Primary OutFlow Max=1.80 cfs @ 12.21 hrs HW=48.12' (Free Discharge)


- 1=Culvert (Passes 1.80 cfs of 12.81 cfs potential flow)
- 3=Orifice/Grate (Controls 0.00 cfs)
- 4=Orifice/Grate (Orifice Controls 1.18 cfs @ 6.03 fps)
- 5=Orifice/Grate (Orifice Controls 0.61 cfs @ 7.03 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 51P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 10 Yr Rainfall=5.85"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 6

Stage-Area-Storage for Pond 51P: Basin 206

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	1,435	0	48.03	1,782	6,150
42.93	1,435	57	48.13	1,801	6,329
43.03	1,435	115	48.23	1,819	6,510
43.13	1,435	172	48.33	1,837	6,693
43.23	1,435	230	48.43	1,856	6,878
43.33	1,435	287			
43.43	1,435	344			
43.53	1,435	402			
43.63	1,435	459			
43.73	1,435	517			
43.83	1,435	574			
43.93	1,435	631			
44.03	1,435	689			
44.13	1,435	746			
44.23	1,435	804			
44.33	1,435	861			
44.43	1,435	918			
44.53	1,435	976			
44.63	1,435	1,033			
44.73	1,435	1,091			
44.83	1,435	1,148			
44.93	1,435	1,292			
45.03	1,437	1,435			
45.13	1,442	1,579			
45.23	1,447	1,723			
45.33	1,453	1,868			
45.43	1,458	2,014			
45.53	1,463	2,160			
45.63	1,469	2,307			
45.73	1,474	2,454			
45.83	1,480	2,602			
45.93	1,485	2,750			
46.03	1,493	2,899			
46.13	1,505	3,048			
46.23	1,517	3,200			
46.33	1,529	3,352			
46.43	1,541	3,505			
46.53	1,553	3,660			
46.63	1,565	3,816			
46.73	1,578	3,973			
46.83	1,590	4,131			
46.93	1,602	4,291			
47.03	1,616	4,452			
47.13	1,632	4,614			
47.23	1,648	4,778			
47.33	1,665	4,944			
47.43	1,681	5,111			
47.53	1,698	5,280			
47.63	1,715	5,451			
47.73	1,731	5,623			
47.83	1,748	5,797			
47.93	1,765	5,973			

2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Pond 51P: Basin 206

[92] Warning: Device #2 is above defined storage

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 10.72" for Yr 2100 - 100 Yr event
 Inflow = 10.07 cfs @ 12.08 hrs, Volume= 0.690 af
 Outflow = 9.78 cfs @ 12.09 hrs, Volume= 0.624 af, Atten= 3%, Lag= 0.5 min
 Primary = 9.78 cfs @ 12.09 hrs, Volume= 0.624 af
 Routed to Pond 49P : Basin 203
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Pond 49P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.48' @ 12.09 hrs Surf.Area= 1,865 sf Storage= 6,973 cf

Plug-Flow detention time= 117.1 min calculated for 0.622 af (90% of inflow)
 Center-of-Mass det. time= 66.7 min (806.0 - 739.2)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Printed 12/12/2025


Page 8

Primary OutFlow Max=9.38 cfs @ 12.09 hrs HW=48.47' (Free Discharge)


- 1=Culvert (Passes 9.38 cfs of 13.78 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 7.41 cfs @ 1.70 fps)
- 4=Orifice/Grate (Orifice Controls 1.31 cfs @ 6.67 fps)
- 5=Orifice/Grate (Orifice Controls 0.66 cfs @ 7.59 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=42.83' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)



Pond 51P: Basin 206



2025.12.02 Proposed Conditions

NOAA 24-hr C Yr 2100 - 100 Yr Rainfall=11.14"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 9

Stage-Area-Storage for Pond 51P: Basin 206

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
42.83	1,435	0	48.03	1,782	6,150
42.93	1,435	57	48.13	1,801	6,329
43.03	1,435	115	48.23	1,819	6,510
43.13	1,435	172	48.33	1,837	6,693
43.23	1,435	230	48.43	1,856	6,878
43.33	1,435	287			
43.43	1,435	344			
43.53	1,435	402			
43.63	1,435	459			
43.73	1,435	517			
43.83	1,435	574			
43.93	1,435	631			
44.03	1,435	689			
44.13	1,435	746			
44.23	1,435	804			
44.33	1,435	861			
44.43	1,435	918			
44.53	1,435	976			
44.63	1,435	1,033			
44.73	1,435	1,091			
44.83	1,435	1,148			
44.93	1,435	1,292			
45.03	1,437	1,435			
45.13	1,442	1,579			
45.23	1,447	1,723			
45.33	1,453	1,868			
45.43	1,458	2,014			
45.53	1,463	2,160			
45.63	1,469	2,307			
45.73	1,474	2,454			
45.83	1,480	2,602			
45.93	1,485	2,750			
46.03	1,493	2,899			
46.13	1,505	3,048			
46.23	1,517	3,200			
46.33	1,529	3,352			
46.43	1,541	3,505			
46.53	1,553	3,660			
46.63	1,565	3,816			
46.73	1,578	3,973			
46.83	1,590	4,131			
46.93	1,602	4,291			
47.03	1,616	4,452			
47.13	1,632	4,614			
47.23	1,648	4,778			
47.33	1,665	4,944			
47.43	1,681	5,111			
47.53	1,698	5,280			
47.63	1,715	5,451			
47.73	1,731	5,623			
47.83	1,748	5,797			
47.93	1,765	5,973			

5.4 STORM MANAGEMENT DESIGN

T_c CALCULATIONS EXISTING AND PROPOSED

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY



TR55 TIME OF CONCENTRATION CALCULATION EXISTING AREA POA-1 (Adj Onsite Pervious)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.36			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	100	0.21%	0.150	E	-----	0.393	23.6
Sheet	0	21.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	365	1.90%	-----	U	2.22	0.046	2.7
Shallow Concentrated	70	4.30%	-----	U	3.35	0.006	0.3
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA POA-1Op (Adj)			Time of concentration, Tc =		0.44	26.6	

Sheet Flow, $T_t = \frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION EXISTING AREA POA-1 (Adj Onsite Impervious)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.36			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	100	1.10%	0.011	A	-----	0.025	1.5
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	189.06	1.10%	-----	P	2.13	0.025	1.5
Shallow Concentrated	143.3	8.30%	-----	U	4.65	0.009	0.5
Shallow Concentrated			-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA POA-10i (Adj)			Time of concentration, Tc =			0.06	3.5

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION EXISTING AREA POA-1 (2100 Onsite Pervious)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.85			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	100	0.21%	0.150	E	-----	0.367	22.0
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	365	1.90%	-----	U	2.22	0.046	2.7
Shallow Concentrated	70	4.30%	-----	U	3.35	0.006	0.3
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA POA-1Op (2100)			Time of concentration, Tc =		0.42	25.1	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION EXISTING AREA POA-1 (2100 Onsite Impervious)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.86			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	100	1.10%	0.011	A	-----	0.023	1.4
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	189.06	1.10%	-----	P	2.13	0.025	1.5
Shallow Concentrated	143.3	8.30%	-----	U	4.65	0.009	0.5
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA POA-10i (2100)			Time of concentration, Tc =		0.06	3.4	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION PROPOSED AREA - Onsite Impervious (Adjusted)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.36			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	93	3.80%	0.011	A	-----	0.014	0.9
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	0	0.00%	-----	P	0.00	0.000	0.0
Shallow Concentrated				U	0.00	0.000	0.0
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA Onsite - Impervious			Time of concentration, Tc =		0.01	0.9	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION PROPOSED AREA - Onsite Pervious (Adjusted)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.36			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	19	2.04%	0.150	E	-----	0.042	2.5
Sheet	77	1.94%	0.011	A	-----	0.016	1.0
Shallow Concentrated	0	1.94%	-----	P	2.83	0.000	0.0
Shallow Concentrated		0.00%	-----	U	0.00	0.000	0.0
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA Onsite - Pervious			Time of concentration, Tc =		0.06	3.5	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION **PROPOSED AREA - Onsite Impervious Roof (Adjusted)**

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.36			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	100	0.50%	0.011	A	-----	0.034	2.1
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	0	0.50%	-----	P	1.44	0.000	0.0
Shallow Concentrated		0.00%		P	0.00	0.000	0.0
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA Onsite roof			Time of concentration, Tc =		0.03	2.1	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION PROPOSED AREA - Onsite Impervious (2100 yr)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.86			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	93	3.80%	0.011	A	-----	0.013	0.8
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	0	1.22%	-----	P	2.25	0.000	0.0
Shallow Concentrated				U	0.00	0.000	0.0
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA Onsite - Impervious			Time of concentration, Tc =		0.01	0.8	

Sheet Flow, Tt =	$\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$	Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION PROPOSED AREA - Onsite Pervious (2100 yr)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.86			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	19	2.04%	0.150	E	-----	0.039	2.3
Sheet	77	1.94%	0.011	A	-----	0.015	0.9
Shallow Concentrated		1.49%	-----	P	2.48	0.000	0.0
Shallow Concentrated				U	0.00	0.000	0.0
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA Onsite - Pervious			Time of concentration, Tc =		0.05	3.3	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		



TR55 TIME OF CONCENTRATION CALCULATION PROPOSED AREA - Onsite Impervious Roof (2100 yr)

2 YR RAINFALL, INCHES	Surface Code	Mannings N-Value	Cover Description
3.86			
Maximum Sheet Flow Length to be less than or equal to 100 feet.	A	0.011	Smooth Surfaces (Concrete, Asphalt, Gravel, Bare Soil)
	B	0.050	Fallow (No Residue)
	C	0.060	Cultivated Soils, (Residue Cover less than or equal to 20%)
	D	0.170	Cultivated Soils, (Residue Cover Greater than or equal to 20%)
	E	0.150	Grass, Short
	F	0.240	Grass, Dense
	G	0.410	Grass, Bermuda
	H	0.400	Woods, Light Underbrush
	I	0.800	Woods, Dense Underbrush
	J	0.130	Range(Natural)
Shallow Concentrated Flow Length < 1000 Feet Recommended.	U	-----	Unpaved Shallow Concentrated Flow
	P	-----	Paved Shallow Concentrated Flow

Tt Flow Type	Flow Length, ft	Slope % grade	Manning's N - Value	Surface Code	Velocity feet / second	Travel Time hours	Travel Time minutes
Sheet	100	0.50%	0.011	A	-----	0.032	1.9
Sheet	0	0.00%	0.011	A	-----	0.000	0.0
Shallow Concentrated	0	0.50%	-----	P	1.44	0.000	0.0
Shallow Concentrated				P	0.00	0.000	0.0
Shallow Concentrated	0	0.00%	-----	U	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
Open Channel	0	-----	-----	-----	0.00	0.000	0.0
AREA Onsite roof			Time of concentration, Tc =		0.03	1.9	

Sheet Flow, Tt = $\frac{0.007(nL)^{0.8}}{P^{0.5} S^{0.4}}$		Unpaved Shallow Concentrated Flow Velocity, fps = $16.1345(S)^{0.5}$
		Paved Shallow Concentrated Flow Velocity, fps = $20.3282(S)^{0.5}$
Tt = Travel Time in hours, L = Flow Length in feet, n = Manning's N, P = 2 year rainfall in inches, S = Slope in (ft/ft)		


6. STORM PIPE CAPACITY CALCULATIONS

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

Pipe Capacity- Line 2 East




Structure Report

Struct No.	Structure ID	Junction Type	Rim Elev (ft)	Structure			Line Out			Line In		
				Shape	Length (ft)	Width (ft)	Size (in)	Shape	Invert (ft)	Size (in)	Shape	Invert (ft)
2		Grate	0.00	Cir	4.00	4.00	15	Cir	45.70			
1		Grate	0.00	Cir	4.00	4.00	18	Cir	45.35	15	Cir	45.35
Pipe Capacity- Line 2 East							Number of Structures: 2			Run Date: 10/20/2025		

Storm Sewer Tabulation

Station		Len	Drng Area		Rnoff coeff	Area x C		Tc		Rain (l)	Total flow	Cap full	Vel	Pipe		Invert Elev		HGL Elev		Grnd / Rim Elev		Line ID
Line	To Line		Incr	Total		Incr	Total	Inlet	Syst					Size	Slope	Dn	Up	Dn	Up	Dn	Up	
		(ft)	(ac)	(ac)	(C)			(min)	(min)	(in/hr)	(cfs)	(cfs)	(ft/s)	(in)	(%)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	
2 1	1 End	70.000 56.000	0.27 0.39	0.27 0.66	0.00 0.00	0.00 0.00	0.00 0.00	0.0 0.0	0.0 0.4	0.0 0.0	1.96 4.79	4.57 8.30	2.83 4.70	15 18	0.50 0.62	45.35 45.00	45.70 45.35	46.19 45.84	46.29 46.19	0.00 0.00	0.00 0.00	
Pipe Capacity- Line 2 East																Number of lines: 2				Run Date: 10/20/2025		
NOTES:Known Qs only ; c = cir e = ellip b = box																						

Hydraflow Storm Sewers Extension for Autodesk® Civil 3D® Plan



Project File: Pipe Capacity- Line 1 West.stm	Number of lines: 3	Date: 10/20/2025
--	--------------------	------------------

Structure Report

Struct No.	Structure ID	Junction Type	Rim Elev (ft)	Structure			Line Out			Line In		
				Shape	Length (ft)	Width (ft)	Size (in)	Shape	Invert (ft)	Size (in)	Shape	Invert (ft)
3		Grate	0.00	Cir	4.00	4.00	15	Cir	46.00			
2		Grate	0.00	Cir	4.00	4.00	18	Cir	45.55	15	Cir	45.55
1		Curb-Horiz	0.00	Cir	4.00	4.00	18	Cir	45.05	18	Cir	45.05
Project File: Pipe Capacity- Line 1 West.stm							Number of Structures: 3			Run Date: 10/20/2025		

Storm Sewer Tabulation

Station		Len	Drng Area		Rnoff coeff	Area x C		Tc		Rain (l)	Total flow	Cap full	Vel	Pipe		Invert Elev		HGL Elev		Grnd / Rim Elev		Line ID
Line	To Line		Incr	Total		Incr	Total	Inlet	Syst					Size	Slope	Dn	Up	Dn	Up	Dn	Up	
		(ft)	(ac)	(ac)	(C)			(min)	(min)	(in/hr)	(cfs)	(cfs)	(ft/s)	(in)	(%)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	
3	2	89.000	0.28	0.28	0.00	0.00	0.00	0.0	0.0	0.0	2.06	4.59	1.68	15	0.51	45.55	46.00	47.15	47.23	0.00	0.00	114
2	1	131.000	0.61	0.89	0.00	0.00	0.00	0.0	0.9	0.0	6.40	6.49	4.18	18	0.38	45.05	45.55	46.26	46.76	0.00	0.00	
1	End	6.000	0.29	1.18	0.00	0.00	0.00	0.0	1.4	0.0	8.47	9.59	5.94	18	0.83	45.00	45.05	46.13	46.18	0.00	0.00	
Project File: Pipe Capacity- Line 1 West.stm																Number of lines: 3				Run Date: 10/20/2025		
NOTES:Known Qs only ; c = cir e = ellip b = box																						

7. EMERGENCY SPILLWAY CALCULATIONS

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	ES Storm	NOAA 24-hr	C	Default	24.00	1	12.77	2

2025.12.02 Proposed Conditions

NOAA 24-hr C ES Storm Rainfall=12.77"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 2

Summary for Pond 39P: Basin 104

[92] Warning: Device #2 is above defined storage

[93] Warning: Storage range exceeded by 0.41'

[81] Warning: Exceeded Pond 44P by 0.47' @ 12.30 hrs

[81] Warning: Exceeded Pond 44P by 0.47' @ 12.30 hrs

Inflow Area = 4.940 ac, 77.74% Impervious, Inflow Depth > 11.92" for ES Storm event
 Inflow = 64.03 cfs @ 12.11 hrs, Volume= 4.907 af
 Outflow = 48.86 cfs @ 12.20 hrs, Volume= 3.797 af, Atten= 24%, Lag= 5.5 min
 Primary = 17.15 cfs @ 12.21 hrs, Volume= 3.594 af
 Routed to Link 2A : POA 1 (Adj)
 Secondary = 31.73 cfs @ 12.20 hrs, Volume= 0.204 af
 Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.81' @ 12.21 hrs Surf.Area= 22,357 sf Storage= 87,112 cf

Plug-Flow detention time= 176.8 min calculated for 3.797 af (77% of inflow)
 Center-of-Mass det. time= 91.4 min (853.8 - 762.4)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	87,112 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	17,239	897.0	0.0	0	0	17,239
42.84	17,239	897.0	40.0	69	69	17,248
43.00	17,239	897.0	40.0	1,103	1,172	17,391
44.00	17,239	897.0	40.0	6,896	8,068	18,288
44.83	17,239	897.0	40.0	5,723	13,791	19,033
44.84	17,239	897.0	100.0	172	13,964	19,042
45.00	17,690	902.0	100.0	2,794	16,758	19,772
46.00	20,420	926.0	100.0	19,039	35,797	23,381
47.00	21,216	939.0	100.0	20,817	56,613	25,524
48.00	22,029	952.0	100.0	21,621	78,234	27,697
48.40	22,357	957.0	100.0	8,877	87,112	28,547

Device	Routing	Invert	Outlet Devices
#1	Primary	44.00'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 44.00' / 44.00' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	46.65'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	18.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C ES Storm Rainfall=12.77"

Printed 12/12/2025

Page 3

#5 Device 1 45.82' **4.0" Vert. Orifice/Grate** C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=17.02 cfs @ 12.21 hrs HW=48.75' (Free Discharge)


- 1=Culvert (Inlet Controls 17.02 cfs @ 9.63 fps)
- 3=Orifice/Grate (Passes < 111.64 cfs potential flow)
- 4=Orifice/Grate (Passes < 2.69 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.70 cfs potential flow)

Secondary OutFlow Max=29.65 cfs @ 12.20 hrs HW=48.78' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Weir Controls 29.65 cfs @ 1.55 fps)



Pond 39P: Basin 104



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	ES Storm	NOAA 24-hr	C	Default	24.00	1	12.77	2

2025.12.02 Proposed Conditions

NOAA 24-hr C ES Storm Rainfall=12.77"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 2

Summary for Pond 44P: Basin 112

[92] Warning: Device #2 is above defined storage

[93] Warning: Storage range exceeded by 0.20'

Inflow Area = 1.397 ac, 81.07% Impervious, Inflow Depth > 12.31" for ES Storm event
 Inflow = 20.59 cfs @ 12.09 hrs, Volume= 1.433 af
 Outflow = 18.55 cfs @ 12.10 hrs, Volume= 1.289 af, Atten= 10%, Lag= 0.8 min
 Primary = 14.36 cfs @ 12.11 hrs, Volume= 1.272 af
 Routed to Pond 39P : Basin 104
 Secondary = 4.20 cfs @ 12.10 hrs, Volume= 0.018 af
 Routed to Pond 39P : Basin 104

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.70' @ 12.11 hrs Surf.Area= 4,468 sf Storage= 14,810 cf

Plug-Flow detention time= 130.9 min calculated for 1.289 af (90% of inflow)
 Center-of-Mass det. time= 78.5 min (817.5 - 739.0)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	14,810 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	2,461	213.0	0.0	0	0	2,461
42.84	2,461	213.0	40.0	10	10	2,463
43.00	2,461	213.0	40.0	158	167	2,497
44.00	2,461	213.0	40.0	984	1,152	2,710
44.83	2,461	213.0	40.0	817	1,969	2,887
44.84	2,461	213.0	100.0	25	1,993	2,889
45.00	2,568	216.0	100.0	402	2,396	2,997
46.00	3,287	251.0	100.0	2,920	5,316	4,319
47.00	3,676	265.7	100.0	3,480	8,796	4,976
48.00	4,082	276.0	100.0	3,877	12,673	5,496
48.50	4,468	290.0	100.0	2,137	14,810	6,142

Device	Routing	Invert	Outlet Devices
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010, Flow Area= 1.77 sf
#2	Secondary	48.50'	20.0' long + 0.3 '/' SideZ x 8.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.43 2.54 2.70 2.69 2.68 2.68 2.66 2.64 2.64 2.64 2.65 2.65 2.66 2.66 2.68 2.70 2.74
#3	Device 1	47.95'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.40'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C ES Storm Rainfall=12.77"

Printed 12/12/2025


Page 3

Primary OutFlow Max=14.29 cfs @ 12.11 hrs HW=48.67' (Free Discharge)

- 1=Culvert (Inlet Controls 14.29 cfs @ 8.08 fps)
- 3=Orifice/Grate (Passes < 31.93 cfs potential flow)
- 4=Orifice/Grate (Passes < 1.34 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.69 cfs potential flow)


Secondary OutFlow Max=4.12 cfs @ 12.10 hrs HW=48.69' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Weir Controls 4.12 cfs @ 1.07 fps)



Pond 44P: Basin 112

Hydrograph



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	ES Storm	NOAA 24-hr	C	Default	24.00	1	12.77	2

2025.12.02 Proposed Conditions

NOAA 24-hr C ES Storm Rainfall=12.77"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 2

Summary for Pond 41P: Basin 203

[92] Warning: Device #2 is above defined storage

[93] Warning: Storage range exceeded by 0.32'

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

[81] Warning: Exceeded Pond 43P by 1.20' @ 14.85 hrs

[81] Warning: Exceeded Pond 43P by 0.31' @ 12.15 hrs

Inflow Area = 3.830 ac, 79.29% Impervious, Inflow Depth > 12.07" for ES Storm event

Inflow = 51.00 cfs @ 12.11 hrs, Volume= 3.853 af

Outflow = 57.13 cfs @ 12.15 hrs, Volume= 3.065 af, Atten= 0%, Lag= 2.4 min

Primary = 34.48 cfs @ 12.15 hrs, Volume= 2.971 af

Routed to Link 2A : POA 1 (Adj)

Secondary = 22.67 cfs @ 12.15 hrs, Volume= 0.094 af

Routed to Link 2A : POA 1 (Adj)

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 48.72' @ 12.15 hrs Surf.Area= 18,306 sf Storage= 64,356 cf

Plug-Flow detention time= 202.3 min calculated for 3.065 af (80% of inflow)

Center-of-Mass det. time= 122.1 min (875.2 - 753.0)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	64,356 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	11,929	737.0	0.0	0	0	11,929
42.84	11,929	737.0	40.0	48	48	11,936
43.00	11,929	737.0	40.0	763	811	12,054
44.00	11,929	737.0	40.0	4,772	5,583	12,791
44.83	11,929	737.0	40.0	3,960	9,543	13,403
44.84	11,929	737.0	100.0	119	9,662	13,410
45.00	12,301	741.0	100.0	1,938	11,601	13,895
46.00	14,572	762.0	100.0	13,420	25,021	16,517
47.00	16,075	784.0	100.0	15,317	40,339	19,332
48.00	17,607	806.0	100.0	16,835	57,174	22,227
48.40	18,306	815.0	100.0	7,182	64,356	23,432

Device	Routing	Invert	Outlet Devices
#1	Primary	39.00'	21.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 39.00' / 39.00' S= 0.0000 ' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 2.41 sf
#2	Secondary	48.40'	50.0' long x 7.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.40 2.52 2.70 2.68 2.68 2.67 2.66 2.65 2.65 2.65 2.66 2.65 2.66 2.68 2.70 2.73 2.78
#3	Device 1	47.70'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	46.30'	8.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C ES Storm Rainfall=12.77"

Printed 12/12/2025

Page 3


#5 Device 1 45.82' 4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=34.39 cfs @ 12.15 hrs HW=48.69' (Free Discharge)

- 1=Culvert (Inlet Controls 34.39 cfs @ 14.30 fps)
- 3=Orifice/Grate (Passes < 51.75 cfs potential flow)
- 4=Orifice/Grate (Passes < 2.41 cfs potential flow)
- 5=Orifice/Grate (Passes < 0.69 cfs potential flow)

Secondary OutFlow Max=22.62 cfs @ 12.15 hrs HW=48.72' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Weir Controls 22.62 cfs @ 1.40 fps)



2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 1

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	ES Storm	NOAA 24-hr	C	Default	24.00	1	12.77	2

2025.12.02 Proposed Conditions

NOAA 24-hr C ES Storm Rainfall=12.77"

Prepared by REDCOM Engineering & Const

Printed 12/12/2025

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

Page 2

Summary for Pond 43P: Basin 206

[92] Warning: Device #2 is above defined storage

[93] Warning: Storage range exceeded by 0.02'

[88] Warning: Qout>Qin may require smaller dt or Finer Routing

Inflow Area = 0.773 ac, 84.16% Impervious, Inflow Depth > 12.35" for ES Storm event
 Inflow = 11.53 cfs @ 12.08 hrs, Volume= 0.795 af
 Outflow = 11.67 cfs @ 12.09 hrs, Volume= 0.728 af, Atten= 0%, Lag= 0.7 min
 Primary = 11.51 cfs @ 12.09 hrs, Volume= 0.727 af
 Routed to Pond 41P : Basin 203
 Secondary = 0.17 cfs @ 12.10 hrs, Volume= 0.001 af
 Routed to Pond 41P : Basin 203

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs
 Peak Elev= 48.52' @ 12.09 hrs Surf.Area= 1,869 sf Storage= 7,008 cf

Plug-Flow detention time= 107.9 min calculated for 0.726 af (91% of inflow)
 Center-of-Mass det. time= 62.0 min (799.8 - 737.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	42.83'	7,008 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
42.83	1,435	180.0	0.0	0	0	1,435
42.84	1,435	180.0	40.0	6	6	1,437
43.00	1,435	180.0	40.0	92	98	1,466
44.00	1,435	180.0	40.0	574	672	1,646
44.83	1,435	180.0	40.0	476	1,148	1,795
44.84	1,435	180.0	100.0	14	1,162	1,797
45.00	1,435	180.0	100.0	230	1,392	1,826
46.00	1,489	190.0	100.0	1,462	2,854	2,173
47.00	1,611	213.0	100.0	1,550	4,403	2,938
48.00	1,777	233.0	100.0	1,693	6,097	3,682
48.50	1,869	240.0	100.0	911	7,008	3,971

Device	Routing	Invert	Outlet Devices	
#1	Primary	45.10'	18.0" Round Culvert L= 3.0' Ke= 0.500 Inlet / Outlet Invert= 45.10' / 45.10' S= 0.0000 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 1.77 sf	
#2	Secondary	48.50'	16.0' long x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83	
#3	Device 1	48.20'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#4	Device 1	46.30'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	
#5	Device 1	45.82'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads	

2025.12.02 Proposed Conditions

Prepared by REDCOM Engineering & Const

HydroCAD® 10.20-7a s/n 02701 © 2025 HydroCAD Software Solutions LLC

NOAA 24-hr C ES Storm Rainfall=12.77"

Printed 12/12/2025


Page 3

Primary OutFlow Max=11.07 cfs @ 12.09 hrs HW=48.51' (Free Discharge)


- 1=Culvert (Passes 11.07 cfs of 13.88 cfs potential flow)
- 3=Orifice/Grate (Weir Controls 9.07 cfs @ 1.82 fps)
- 4=Orifice/Grate (Orifice Controls 1.32 cfs @ 6.74 fps)
- 5=Orifice/Grate (Orifice Controls 0.67 cfs @ 7.65 fps)

Secondary OutFlow Max=0.10 cfs @ 12.10 hrs HW=48.52' (Free Discharge)

- 2=Broad-Crested Rectangular Weir (Weir Controls 0.10 cfs @ 0.33 fps)



Pond 43P: Basin 206



8. MAPS & DIAGRAMS

PREPARED: September 19, 2025

REVISED: December 15, 2025


300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

REVISIONS		
DATE	NAME	N.O.
JAN. 01, 2012	DANIEL A. NAGY	24GS02751300

SHEET NO. 5

SHEET NO. 12

6



THIS SHEET HAS BEEN DRAWN USING COMPUTER AIDED DRAFTING/DESIGN (CADD/D) AND IS A DIGITAL COPY OF THE TAX MAP (ORIGINALLY PREPARED BY JOHN M. DURA, P.L.S., SSM/T.T. MOORE ASSOCIATES, INC. DATED OCT. 1990. THE ORIGINAL APPROVED MAP IS ON FILE IN THE OFFICE OF THE MUNICIPAL CLERK.

TAX MAP

TOWNSHIP OF LAWRENCE
MERCER COUNTY, NEW JERSEY
SCALE: 1"=100' OCT. 1990
JOHN M. DURA, P.L.S.
TO SHOW CONDITIONS AS OF JAN. 01, 2012

SSMT. T. MOORE
ASSOCIATES, INC.
AD.R.

ASSOCIATES, INC.
23301 LAWRENCE HIGHWAY
WEST TRENTON, N.J. 08628 883-2313 PENNSAUKEN NJ 08110 865-7200

SHEET NO. 5

6


REVISIONS		
DATE	NAME	LIC. NO.

LAWRENCE TOWNSHIP
MERCER COUNTY

LAWRENCE TOWNSHIP
ASSESSORS LINE

TOWNSHIP OF HAMILTON
MERCER COUNTY

THE CITY OF TRENTON'S TAX ASSESSORS
LINE DATED 1928




This sheet has been drawn using
Computer Aided Drafting/Design
(CAD/D), and Coordinate Geometry
(COCO).

THIS MAP HAS BEEN GIVEN A FORMAL
CERTIFICATION BY THE DIVISION OF TAXATION
ON JANUARY 9, 2003. SIGNED BY
SANTO C. DICONATO, CTA AND ASSIGNED
SERIAL NUMBER 811


TAX MAP
CITY OF TRENTON
MERCER COUNTY, NEW JERSEY
SCALE 1"=50'
MARCH 2000
HARRY J. SYPNIEWSKI
NEW JERSEY LICENSED LAND SURVEYOR No. 20808
van note-harvey associates, p.c.
777 Alexander Road, Princeton, N.J. 08540

Land Resource Protection Web Map




3/6/2025, 1:16:29 PM

- Parcel (Block and Lot)
- County
- Flood Hazard Zones
- Regulatory Floodway
- 0.2% Annual Chance Flood Hazard
- Flood Hazard Boundaries
- Cross-Sections
- FIRM Panels





Map Scale: 1:3,440 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 18N WGS84



**Natural Resources
Conservation Service**

**Web Soil Survey
National Cooperative Soil Survey**

5/9/2025
Page 1 of 4

MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils

Soil Rating Polygons

A

A/D

B

B/D

C

C/D

D

Not rated or not available

Soil Rating Lines

A

A/D

B

B/D

C

C/D

D

Not rated or not available

Soil Rating Points

A

A/D

B

B/D

Water Features

Streams and Canals

Transportation

Rails

Interstate Highways

US Routes

Major Roads

Local Roads

Background

Aerial Photography

C

C/D

D

Not rated or not available

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Mercer County, New Jersey
Survey Area Data: Version 20, Sep 3, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 4, 2022—Jul 22, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
UdgB	Udorthents, gravelly substratum, 0 to 8 percent slopes	D	18.6	80.8%
UdstB	Udorthents, stratified substratum, 0 to 8 percent slopes	D	0.1	0.4%
WATER	Water		4.3	18.8%
Totals for Area of Interest			23.0	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



9/30/2025, 8:31:55 AM

State Planning Area Boundaries



Parks and Natural Areas (PA 6,7,8)



Metropolitan Planning Area (PA 1)

County Boundaries

1:18,056

0 0.1 0.2 0.35 0.4 mi

0 0.17 0.35 0.7 km

Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community

9. CHARTS & TABLES

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

Table 2-2a Runoff curve numbers for urban areas ^{1/}

Cover description		Curve numbers for hydrologic soil group			
Cover type and hydrologic condition	Average percent impervious area ^{2/}	A	B	C	D
<i>Fully developed urban areas (vegetation established)</i>					
Open space (lawns, parks, golf courses, cemeteries, etc.) ^{3/} :					
Poor condition (grass cover < 50%)		68	79	86	89
Fair condition (grass cover 50% to 75%)		49	69	79	84
Good condition (grass cover > 75%)		39	61	74	80
Impervious areas:					
Paved parking lots, roofs, driveways, etc. (excluding right-of-way)		98	98	98	98
Streets and roads:					
Paved; curbs and storm sewers (excluding right-of-way)		98	98	98	98
Paved; open ditches (including right-of-way)		83	89	92	93
Gravel (including right-of-way)		76	85	89	91
Dirt (including right-of-way)		72	82	87	89
Western desert urban areas:					
Natural desert landscaping (pervious areas only) ^{4/}		63	77	85	88
Artificial desert landscaping (impervious weed barrier, desert shrub with 1- to 2-inch sand or gravel mulch and basin borders)		96	96	96	96
Urban districts:					
Commercial and business	85	89	92	94	95
Industrial	72	81	88	91	93
Residential districts by average lot size:					
1/8 acre or less (town houses)	65	77	85	90	92
1/4 acre	38	61	75	83	87
1/3 acre	30	57	72	81	86
1/2 acre	25	54	70	80	85
1 acre	20	51	68	79	84
2 acres	12	46	65	77	82
<i>Developing urban areas</i>					
Newly graded areas					
(pervious areas only, no vegetation) ^{5/}		77	86	91	94
Idle lands (CN's are determined using cover types similar to those in table 2-2c).					

¹ Average runoff condition, and $I_a = 0.2S$.² The average percent impervious area shown was used to develop the composite CN's. Other assumptions are as follows: impervious areas are directly connected to the drainage system, impervious areas have a CN of 98, and pervious areas are considered equivalent to open space in good hydrologic condition. CN's for other combinations of conditions may be computed using figure 2-3 or 2-4.³ CN's shown are equivalent to those of pasture. Composite CN's may be computed for other combinations of open space cover type.⁴ Composite CN's for natural desert landscaping should be computed using figures 2-3 or 2-4 based on the impervious area percentage (CN = 98) and the pervious area CN. The pervious area CN's are assumed equivalent to desert shrub in poor hydrologic condition.⁵ Composite CN's to use for the design of temporary measures during grading and construction should be computed using figure 2-3 or 2-4 based on the degree of development (impervious area percentage) and the CN's for the newly graded pervious areas.

Table 2-2b Runoff curve numbers for cultivated agricultural lands ^{1/}

Cover description			Curve numbers for hydrologic soil group			
Cover type	Treatment ^{2/}	Hydrologic condition ^{3/}	A	B	C	D
Fallow	Bare soil	—	77	86	91	94
	Crop residue cover (CR)	Poor	76	85	90	93
		Good	74	83	88	90
Row crops	Straight row (SR)	Poor	72	81	88	91
		Good	67	78	85	89
	SR + CR	Poor	71	80	87	90
		Good	64	75	82	85
	Contoured (C)	Poor	70	79	84	88
		Good	65	75	82	86
	C + CR	Poor	69	78	83	87
		Good	64	74	81	85
	Contoured & terraced (C&T)	Poor	66	74	80	82
		Good	62	71	78	81
Small grain	SR	Poor	65	76	84	88
		Good	63	75	83	87
	SR + CR	Poor	64	75	83	86
		Good	60	72	80	84
	C	Poor	63	74	82	85
		Good	61	73	81	84
	C + CR	Poor	62	73	81	84
		Good	60	72	80	83
	C&T	Poor	61	72	79	82
		Good	59	70	78	81
Close-seeded or broadcast legumes or rotation meadow	C&T+ CR	Poor	60	71	78	81
		Good	58	69	77	80
	SR	Poor	66	77	85	89
		Good	58	72	81	85
	C	Poor	64	75	83	85
		Good	55	69	78	83
	C&T	Poor	63	73	80	83
		Good	51	67	76	80

¹ Average runoff condition, and $I_a = 0.2S$ ² Crop residue cover applies only if residue is on at least 5% of the surface throughout the year.³ Hydraulic condition is based on combination factors that affect infiltration and runoff, including (a) density and canopy of vegetative areas, (b) amount of year-round cover, (c) amount of grass or close-seeded legumes, (d) percent of residue cover on the land surface (good $\geq 20\%$), and (e) degree of surface roughness.

Poor: Factors impair infiltration and tend to increase runoff.

Good: Factors encourage average and better than average infiltration and tend to decrease runoff.

Table 2-2c Runoff curve numbers for other agricultural lands ^{1/}

Cover description		Curve numbers for hydrologic soil group			
Cover type	Hydrologic condition	A	B	C	D
Pasture, grassland, or range—continuous forage for grazing. ^{2/}	Poor	68	79	86	89
	Fair	49	69	79	84
	Good	39	61	74	80
Meadow—continuous grass, protected from grazing and generally mowed for hay.	—	30	58	71	78
Brush—brush-weed-grass mixture with brush the major element. ^{3/}	Poor	48	67	77	83
	Fair	35	56	70	77
	Good	30 ^{4/}	48	65	73
Woods—grass combination (orchard or tree farm). ^{5/}	Poor	57	73	82	86
	Fair	43	65	76	82
	Good	32	58	72	79
Woods. ^{6/}	Poor	45	66	77	83
	Fair	36	60	73	79
	Good	30 ^{4/}	55	70	77
Farmsteads—buildings, lanes, driveways, and surrounding lots.	—	59	74	82	86

¹ Average runoff condition, and $I_a = 0.2S$.² *Poor*: <50% ground cover or heavily grazed with no mulch.*Fair*: 50 to 75% ground cover and not heavily grazed.*Good*: > 75% ground cover and lightly or only occasionally grazed.³ *Poor*: <50% ground cover.*Fair*: 50 to 75% ground cover.*Good*: >75% ground cover.⁴ Actual curve number is less than 30; use CN = 30 for runoff computations.⁵ CN's shown were computed for areas with 50% woods and 50% grass (pasture) cover. Other combinations of conditions may be computed from the CN's for woods and pasture.⁶ *Poor*: Forest litter, small trees, and brush are destroyed by heavy grazing or regular burning.*Fair*: Woods are grazed but not burned, and some forest litter covers the soil.*Good*: Woods are protected from grazing, and litter and brush adequately cover the soil.

Table 2-2d Runoff curve numbers for arid and semiarid rangelands ^{1/}

Cover description		Curve numbers for hydrologic soil group			
Cover type	Hydrologic condition ^{2/}	A ^{3/}	B	C	D
Herbaceous—mixture of grass, weeds, and low-growing brush, with brush the minor element.	Poor		80	87	93
	Fair		71	81	89
	Good		62	74	85
Oak-aspen—mountain brush mixture of oak brush, aspen, mountain mahogany, bitter brush, maple, and other brush.	Poor		66	74	79
	Fair		48	57	63
	Good		30	41	48
Pinyon-juniper—pinyon, juniper, or both; grass understory.	Poor		75	85	89
	Fair		58	73	80
	Good		41	61	71
Sagebrush with grass understory.	Poor		67	80	85
	Fair		51	63	70
	Good		35	47	55
Desert shrub—major plants include saltbush, greasewood, creosotebush, blackbrush, bursage, palo verde, mesquite, and cactus.	Poor	63	77	85	88
	Fair	55	72	81	86
	Good	49	68	79	84

¹ Average runoff condition, and $I_a = 0.2S$. For range in humid regions, use table 2-2c.² Poor: <30% ground cover (litter, grass, and brush overstory).

Fair: 30 to 70% ground cover.

Good: > 70% ground cover.

³ Curve numbers for group A have been developed only for desert shrub.



General Information

Homepage
Progress Reports
FAQ
Glossary

Precipitation Frequency

Data Server
GIS Grids
Maps
Time Series
Temporals
Documents

Probable Maximum Precipitation

Documents

Miscellaneous

Publications
Storm Analysis
Record Precipitation

Contact Us

Inquiries



Home Site Map Organization

Search ☒ NWS ☐ All NOAA

NOAA ATLAS 14 POINT PRECIPITATION FREQUENCY ESTIMATES: NJ

Data description

Data type: Units: Time series type:

Select location


1) Manually:

a) By location (decimal degrees, use "-" for S and W): Latitude: Longitude:

b) By station (list of NJ stations):

c) By address

2) Use map:



POINT PRECIPITATION FREQUENCY (PF) ESTIMATES
WITH 90% CONFIDENCE INTERVALS AND SUPPLEMENTARY INFORMATION
NOAA Atlas 14, Volume 2, Version 3

PF tabular

PF graphical

Supplementary information

Print page

PDS-based precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.341 (0.310-0.377)	0.408 (0.371-0.450)	0.485 (0.438-0.534)	0.541 (0.489-0.596)	0.610 (0.548-0.672)	0.661 (0.591-0.728)	0.712 (0.633-0.786)	0.759 (0.671-0.840)	0.818 (0.717-0.911)	0.864 (0.750-0.968)
10-min	0.545 (0.495-0.602)	0.652 (0.593-0.719)	0.776 (0.702-0.855)	0.865 (0.781-0.952)	0.972 (0.874-1.07)	1.05 (0.942-1.16)	1.13 (1.01-1.25)	1.20 (1.06-1.33)	1.29 (1.13-1.44)	1.36 (1.18-1.52)
15-min	0.682 (0.619-0.752)	0.819 (0.745-0.904)	0.982 (0.888-1.08)	1.09 (0.988-1.20)	1.23 (1.11-1.36)	1.33 (1.19-1.47)	1.43 (1.27-1.58)	1.52 (1.34-1.68)	1.63 (1.43-1.82)	1.71 (1.48-1.91)
30-min	0.934 (0.849-1.03)	1.13 (1.03-1.25)	1.40 (1.26-1.54)	1.58 (1.43-1.75)	1.83 (1.64-2.01)	2.01 (1.80-2.21)	2.19 (1.95-2.42)	2.36 (2.09-2.62)	2.59 (2.27-2.89)	2.76 (2.40-3.10)
60-min	1.16 (1.06-1.29)	1.42 (1.29-1.57)	1.79 (1.62-1.97)	2.06 (1.86-2.27)	2.43 (2.18-2.68)	2.72 (2.43-3.00)	3.02 (2.68-3.33)	3.31 (2.93-3.67)	3.72 (3.26-4.14)	4.04 (3.50-4.52)
2-hr	1.41 (1.28-1.56)	1.72 (1.56-1.90)	2.18 (1.97-2.40)	2.53 (2.28-2.79)	3.02 (2.70-3.32)	3.41 (3.04-3.75)	3.81 (3.37-4.20)	4.22 (3.72-4.67)	4.80 (4.17-5.34)	5.25 (4.53-5.89)
3-hr	1.55 (1.40-1.72)	1.89 (1.71-2.10)	2.39 (2.16-2.66)	2.79 (2.50-3.10)	3.34 (2.99-3.71)	3.79 (3.36-4.21)	4.26 (3.75-4.74)	4.75 (4.15-5.30)	5.43 (4.68-6.09)	5.99 (5.09-6.75)
6-hr	1.96 (1.77-2.19)	2.38 (2.15-2.66)	3.01 (2.71-3.35)	3.52 (3.15-3.92)	4.26 (3.78-4.74)	4.88 (4.30-5.43)	5.55 (4.84-6.18)	6.27 (5.40-6.99)	7.30 (6.18-8.19)	8.16 (6.82-9.22)
12-hr	2.38 (2.15-2.67)	2.88 (2.60-3.23)	3.66 (3.29-4.11)	4.33 (3.87-4.85)	5.32 (4.71-5.95)	6.19 (5.43-6.92)	7.14 (6.18-7.97)	8.19 (6.98-9.19)	9.76 (8.15-11.0)	11.1 (9.11-12.6)
24-hr	2.75 (2.54-3.00)	3.33 (3.07-3.63)	4.23 (3.90-4.60)	5.00 (4.59-5.43)	6.13 (5.59-6.65)	7.11 (6.42-7.70)	8.19 (7.34-8.87)	9.37 (8.31-10.2)	11.1 (9.72-12.1)	12.6 (10.9-13.8)
2-day	3.18 (2.93-3.48)	3.86 (3.55-4.22)	4.91 (4.50-5.37)	5.78 (5.28-6.32)	7.06 (6.41-7.69)	8.14 (7.34-8.86)	9.31 (8.33-10.1)	10.6 (9.38-11.6)	12.5 (10.9-13.7)	14.0 (12.1-15.4)
3-day	3.38 (3.12-3.68)	4.08 (3.77-4.45)	5.16 (4.76-5.63)	6.06 (5.66-6.59)	7.35 (6.71-7.98)	8.43 (7.65-9.15)	9.60 (8.65-10.4)	10.9 (9.70-11.8)	12.7 (11.2-13.9)	14.2 (12.4-15.6)
4-day	3.57 (3.30-3.87)	4.31 (3.98-4.68)	5.42 (5.01-5.89)	6.33 (5.84-6.87)	7.64 (7.00-8.28)	8.73 (7.96-9.45)	9.90 (8.96-10.7)	11.1 (10.0-12.1)	12.9 (11.5-14.1)	14.4 (12.7-15.7)

7-day	4.18 (3.86-4.55)	5.01 (4.63-5.46)	6.22 (5.75-6.77)	7.22 (6.65-7.85)	8.66 (7.94-9.40)	9.86 (8.99-10.7)	11.1 (10.1-12.1)	12.5 (11.2-13.5)	14.4 (12.9-15.7)	16.1 (14.2-17.5)
10-day	4.76 (4.43-5.14)	5.69 (5.29-6.14)	6.96 (6.47-7.51)	7.99 (7.41-8.62)	9.44 (8.71-10.2)	10.6 (9.77-11.4)	11.8 (10.8-12.8)	13.1 (12.0-14.2)	14.9 (13.5-16.2)	16.4 (14.7-17.8)
20-day	6.42 (6.04-6.84)	7.62 (7.17-8.12)	9.11 (8.56-9.70)	10.3 (9.65-11.0)	11.9 (11.1-12.6)	13.1 (12.3-14.0)	14.4 (13.4-15.3)	15.7 (14.5-16.7)	17.4 (16.0-18.6)	18.8 (17.1-20.1)
30-day	8.00 (7.57-8.45)	9.44 (8.92-9.97)	11.0 (10.4-11.7)	12.3 (11.6-13.0)	13.9 (13.1-14.7)	15.2 (14.3-16.0)	16.4 (15.4-17.3)	17.6 (16.5-18.6)	19.2 (17.9-20.4)	20.4 (18.9-21.7)
45-day	10.2 (9.69-10.7)	12.0 (11.4-12.6)	13.8 (13.1-14.5)	15.2 (14.4-16.0)	17.0 (16.1-17.9)	18.3 (17.3-19.2)	19.6 (18.4-20.6)	20.8 (19.5-21.9)	22.3 (20.9-23.5)	23.3 (21.8-24.7)
60-day	12.2 (11.7-12.8)	14.3 (13.7-15.0)	16.4 (15.6-17.2)	17.9 (17.0-18.8)	19.8 (18.8-20.8)	21.2 (20.1-22.2)	22.5 (21.3-23.6)	23.7 (22.5-24.9)	25.2 (23.8-26.5)	26.3 (24.7-27.7)
¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.										

Estimates from the table in CSV format: Precipitation frequency estimates Submit

Main Link Categories:
[Home](#) | [OWP](#)

US Department of Commerce
National Oceanic and Atmospheric Administration
National Weather Service
Office of Water Prediction (OWP)
1325 East West Highway
Silver Spring, MD 20910
Page Author: [HDSC webmaster](#)
Page last modified: April 21, 2017

Map Disclaimer
Disclaimer
Credits
Glossary

Privacy Policy
About Us
Career Opportunities

10. SUBSURFACE SOIL INVESTIGATION & REPORT

PREPARED: September 19, 2025

REVISED: December 15, 2025

300-356 ENTERPRISE AVE.
CITY OF TRENTON
BLOCK 23203, LOT 1
BLOCK 23102 LOTS 2 & 9
TOWNSHIP OF LAWRENCE
BLOCK 602, LOTS 1 & 2
MERCER COUNTY, NEW JERSEY

Principals

Anthony Castillo, PE
Fuad Dahan, PhD, PE, LSRP
Franz W. Laki, PE
John M. Nederfield, PE
Justin M. Protasiewicz, PE
Jose M. Rodriguez, PE
Michael St. Pierre, PE

June 5, 2025 *via email:* josh@redcomllc.com

Mr. Joshua Tiner, PE
REDCOM Design & Construction LLC
433 North Avenue East
Westfield NJ, 07090

RE:

**Preliminary Geotechnical Investigation Letter
Proposed Warehouse
310-356 Enterprise Avenue
Trenton, New Jersey, 08638
SESI Project No. 14039**

Dear Mr. Tiner:

In accordance with our Professional Service Agreement, dated March 10, 2025, we have performed a Seasonal High Water Table (SHWT) investigation for the proposed warehouse development located at 310–356 Enterprise Avenue, Trenton, New Jersey. This letter provides a summary of the site description and topography, our subsurface investigation, groundwater and SHGWT observations, and exploration logs. Additional recommendations for further investigations and any relevant comments or concerns are also included as necessary.

SITE DESCRIPTION

The project site is bounded to the north by Enterprise Avenue with industrial facilities beyond, to the west by Enterprise Avenue with industrial facilities, the Delaware and Raritan Canal and Route 1 beyond, to the south by Assunpink Creek, railroad tracks and the Whitehead Road Extension with warehouses beyond, and to the east by Assunpink Creek. The Assunpink Creek runs along the southern and eastern boundaries of the site, while the Delaware and Raritan Canal is approximately 500 feet northwest of the Site.

Based on a review of the drawing titled *Site Sketch 2* prepared by REDCOM Design & Construction dated April 15, 2025, the proposed stormwater management system at the Site will include four bioretention basins. Bioretention basins No. 1 through 3 are situated south of the proposed 236,178 square-foot warehouse, while bioretention basin No. 4 is located to the north. All proposed basins are positioned next to the loading and parking areas. The proposed development also includes parking, driveways, walkways, retaining walls, and ADA-accessible infrastructure. The existing elevations within the proposed basin areas generally range between EL 49.0 and EL 51.0, according to Boundary & Topographic Survey prepared by InSite Surveying, LLC dated March 12, 2025. Generally the site is flat along Enterprise Avenue, at EL 46± at the north and EL 49± at the south portion of the site. From East to West, the site is generally flat between EL.47 to EL.50, with a steep slope along the Assunpink Creek down to EL 37±. It should be noted there are several stockpiles and pits scattered throughout the site.

AVAILABLE INFORMATION REVIEW

We have reviewed the following documents in preparation for this letter:

- Deed notice prepared by Zigurds J Zingis LSRP from Sadat Associates, Inc. dated November 21, 2013.
- A letter titled Classification Exception Area/Well Restriction Area (CEA/WRA) prepared by the Department of Environmental Protection Bureau of Remedial Action Permitting dated May 23, 2014.
- A letter titled Soil Remedial Action Permit prepared by the Department of Environmental Protection Bureau of Remedial Action Permitting dated May 23, 2014.
- A letter titled Youngs Rubber Company prepared by the Department of Environmental Protection Bureau of Enforcement & Investigations dated September 11, 2014.
- A letter titled Response Action Outcome prepared by Sadat Associates, Inc. dated October 8, 2014.
- A letter titled Biennial Certification Form- Soil prepared by Sadat Associates, Inc. dated June 9, 2023.
- Sheet No. 2.01 titled Constraints Analysis Plan prepared by MidAtlantic Engineering Partners dated September 20, 2024.
- The Engineering Soil Map of Mercer County Sheet 2 of 4 prepared by the Joint Highway Research Project NJ State Highway Department and Rutgers University dated October 1953.(referenced in this letter as the Rutgers Soil Survey for Mercer County)
- USDA NRCS Web Soil Survey Report prepared for 310-356 Enterprise Avenue in Trenton New Jersey.
- FEMA Flood Map: We researched and reviewed the FEMA Flood Insurance Rate Map, Map Number 34021C0226F (effective as of July 20, 2016) which indicates that the Site is located within zone AE. Zone AE is determined to be inside a special flood hazard area with a base flood elevation of approximately EL. 44 to 46 expanding from the Assunpink Creek. A letter Map revision was issued August 9, 2018 with an effective date of December 21, 2018. The Map revision corresponds to changes south of the Site and does not indicate any changes for the Site.

Based on information provided to us, the Site has undergone a comprehensive environmental cleanup in response to contamination from historical industrial operations. Major environmental concerns included petroleum hydrocarbons (PHCs) from underground storage tanks, polychlorinated biphenyls (PCBs) from transformers, and widespread contamination from historic fill, including heavy metals (cadmium, lead, arsenic), asbestos-containing materials, and polycyclic aromatic hydrocarbons (PAHs). Soil remediation was conducted in phases, with over 21,000 tons of impacted soil removed and two deed-restricted areas established. A Soil Remedial Action Permit (RAP140001) was issued by NJDEP in 2014, requiring long-term monitoring, maintenance, and institutional controls to remain protective of human health and the environment.

Based on our understanding, a Classification Exception Area (CEA) was designated for cadmium-impacted groundwater attributed to historic fill, covering approximately 11 acres and extending to

a depth of 100 feet in the underlying crystalline rock aquifer. No further active groundwater remediation was required, given the regional nature of the contamination. A Deed Notice was filed in 2013 and supplemented by engineering controls such as perimeter fencing, signage, and placement of clean fill.

An analysis of updated Soil Remediation Standards (2021) showed no contaminants requiring revised action based on order-of-magnitude changes. Contaminants of emerging concern (e.g., PFAS, 1,4-dioxane) were evaluated and determined not to be present. This should be reviewed by the project environmental engineer or Licensed Site Remediation Professional (LSRP) for ongoing oversight.

We reviewed the Rutgers Soil Survey Map for Mercer County, which identifies the surficial geology at the Site as being mapped primarily as GO-24, a soil unit derived from stratified drift deposited by glacial meltwaters during the Wisconsin glacial period. These soils are predominantly composed of sand and silt with some pebbles and cobbles, typically occurring in well-defined layers or beds. The underlying formations north of Assunpink Creek, where the site is located, include Triassic shale, argillite, sandstone, diabase, and localized areas of Cambrian quartzite, gneiss, and gabbro.

We reviewed the USDA NRCS Web Soil Survey Report, for the Site, which identifies the surficial soils at the Site as primarily "Udorthents, gravelly substratum, 0 to 8 percent slopes (UdgB)." These soils are derived from loamy lateral spread deposits over gravelly layers and are commonly found on low hills with linear slope profiles. The soil profile typically consists of gravelly sand from 0 to 10 inches and gravelly coarse sand extending to 72 inches.

SUMMARY OF INVESTIGATION

This investigation was conducted for the purpose of identifying the subsurface stratigraphy and the hydrological characteristics of the Site, specifically the type of soils including hydraulically restrictive stratum, and the SHWT. The investigation was performed in accordance with the New Jersey Best Management Practice (NJ BMP) Manual, March 2024 edition. The results of our SHWT investigation are described below.

The investigation was completed on April 30, 2025, which was within the "wet season" as determined by the NJ BMP Manual. Per the NJ BMP Manual, the SHWT shall be taken as the highest level at which the mottling is observed, except when the water table is observed at a level higher than the level of the redoximorphic depletions or concentrations. Where mottling showing redoximorphic features is not observed, the SHWT shall be determined directly by measuring water levels within soil profile pits. Our investigation included the drilling of five (5) borings using a subcontracted 7822Dt Geoprobe, to depths ranging from approximately 10 to 27± feet below the ground surface. Boring B-1 was not explored due to consistent refusal at a few inches below the ground surface, after multiple attempts in the immediate area. Boring B-2 encountered refusal at 12 feet below the ground surface even after offsetting the boring location three times.

The approximate locations of the borings with the corresponding approximate SHWT elevation are shown on the **Exploration Location Plan**, which is included as **Drawing 1**. The individual boring logs, which describe the materials encountered along with a key to soil terminology are presented in **Appendix A**.

The fieldwork was performed under the direct technical observation of a geotechnical engineer from SESI Consulting Engineers. Our representative maintained continuous logs of the borings

and coordinated the soil sampling operations in order to develop the required subsurface information. All soil samples were taken to our soil's laboratory for additional classification.

All field work was conducted in accordance with the Site-Specific Health and Safety Plan (HASP) Rider prepared by SESI Consulting Engineers. The HASP outlined specific procedures to identify, mitigate, and respond to potential site hazards, including physical risks associated with heavy equipment, chemical exposure from historic fill materials, and heat or weather-related stressors. Field staff were trained in OSHA 1910.120 standards, utilized Modified Level D personal protective equipment, and followed strict communication, emergency response, and monitoring protocols throughout the duration of the investigation.

GENERALIZED SUBSURFACE CONDITIONS

The following subsurface conditions were encountered in order of increasing depth:

Surface Material Topsoil was encountered in all borings with thicknesses ranging from 2 to 6-inches. It should be noted that there are areas near and at Boring B-1 where topsoil was not observed, this area consisted of construction debris.

Fill: Fill material was encountered beneath the surface material in all completed borings and extended to depths ranging from 5± to 10± ft below ground surface (bgs). This correlates to ground surface elevations ranging from EL 39± to EL 42±. Other areas of uncontrolled fill may be present due to previous construction and remediation activities throughout the site.

The fill material generally consists of black, brown, dark brown, gray, light brown, yellow, and yellow-brown coarse/medium to fine sand with variable amounts of gravel, silt, and clay. Construction debris consisting of ashes, concrete and brick were encountered throughout all borings. Possible cobbles were encountered within the fill layer in boring B-6.

Based on the observed SPT N-values, the uncontrolled fill was generally found to be in a loose to dense consistency, which is typical for an uncontrolled fill.

Natural Soils: Natural glacial soils were encountered beneath the fill material in all borings. The natural soils extended to depths ranging from 10± to 27± ft bgs. This correlates to EL 22± to 38±.

The natural glacial soils encountered generally consisted of black, brown, dark green, gray, gray-brown, light brown and red-brown coarse to fine sand with variable amounts of gravel, silt, clay, and possible cobbles. A possible boulder was encountered in boring B-4 at 21 ft bgs. An approximately three (3) ± foot thick clayey silt layer was encountered in boring B-5 at a depth of 11 ft bgs.

Based on the observed SPT N-values, the glacial soils were generally found to be in a medium dense consistency, with the exception of boring B-6 which encountered a loose condition at 10 to 12 ft bgs. This is believed to be a result of an unbalanced hydraulic head, during the sampling as groundwater was encountered near this depth for boring B-6.

Groundwater: Groundwater was encountered in all borings at depths ranging from 5± to 10± ft bgs during the short period of time that the holes were left open. This correlates to approximate groundwater elevations of EL.37.5± to EL.43±. South of the site, the Assumpink Creek leads into Delaware River. Additionally, the Delaware Raritan Canal is located north of the Site and also leads into the Delaware River. Fluctuations of a few feet in the groundwater elevations should be anticipated based on the time of year and the amount of recent precipitation. We do not believe that the groundwater at the site is tidally impacted. Mottling was encountered in boring B-5 at a

depth of 15 ft bgs, corresponding to EL. 33, however, water was observed to be at a depth of 5 ft bgs.

CONCLUSIONS

Based on the results of our preliminary geotechnical study, from a soils standpoint, this Site can be considered fair with respect to providing satisfactory support for the proposed warehouse. The primary negative aspects of the Site soils are the varying thickness of the uncontrolled fill layer. The second is the amount of fines encountered in the fill, if planned to be reused on site during construction. Additional investigations should be performed throughout the building footprint to prepare foundation and site preparation recommendations for the development.

In general, the Site preparation procedures should consist of removing old building foundations (if present), demolition debris, stockpiles, topsoil, trees, and wooded overgrowth, where present, from within and at least five (5) feet beyond the limits of the proposed buildings and pavement areas. The former foundations and/or demolition debris should be excavated and staged on-Site until proper environmental evaluation is completed, and disposal can be arranged. As an alternative, concrete encountered on-Site can be crushed and reused on-Site as fill only if approved by the site LSRP.

Some of the uncontrolled fill was considered to be moisture sensitive. The reuse of the material will be affected by the weather and the presence of water in the fill layer. Moisture sensitive soils, when wet, will need to dry prior to being reused. The need to replace the moisture sensitive soil with non-moisture sensitive granular fill should be considered as part of the site preparation.

Based on the available information, the SHWT is estimated to slope down between elevations EL.41± to EL.43 ± for the Site. This estimate is supported by observed groundwater elevations recorded during the wet season, and a review of the FEMA Flood Map. Further review of the FEMA data indicates that the groundwater elevation trends from northeast to southwest, generally following the path of the Assunpink Creek.

For preliminary stormwater management system design purposes, the SHWT should be considered to be approximately EL. 41 ± south of the proposed warehouse and EL. 43 ± north of the proposed warehouse. We understand that in the area of boring B-5 permeable pavement may be proposed. SHWT was observed to be EL. 43 in the proposed area of the permeable pavement. Boring B-6 indicated an elevation of EL 37.5 for the SHWT. The lower SHWT elevation of EL 37.5 was recorded in the test pit located closer to Assunpink Creek, indicating a likely hydraulic connection between the groundwater and the adjacent surface water body. Since groundwater tends to flow toward lower elevations and discharge into nearby streams, it is reasonable to interpret the EL 37.5 reading as representative of actual groundwater conditions in that portion of the Site. Given that the boring B-6 location also coincides with the footprint of the proposed stormwater basin, it would be considered appropriate to adopt EL 37.5 as the SHWT for design purposes in that area. However, to maintain a conservative approach and account for potential variability in subsurface conditions observed across the site, we recommend using EL 41.0 as the design SHWT for the basin. This provides a balance between observed data and protective design considerations. We have provided a table on the next page for the SHWT Elevation for each basin.

Table 1: SHWT EL for Basin Design	
Basin No.	SHWT EL.
Bioretention Basin No. 1	41
Bioretention Basin No. 2	41
Bioretention Basin No. 3	41
Bioretention Basin No. 4	41

According to New Jersey law, stormwater infiltration is prohibited in areas with known or suspected groundwater contamination, as specified in the NJDEP Stormwater Management Rules (N.J.A.C. 7:8-5.4.3).

RECOMMENDATIONS

SESI recommends conducting further evaluations of the proposed BMPs and proposed warehouse development to meet the requirements outlined in Chapter 12 of the New Jersey BMP Manual. Additional test pits are necessary to satisfy the minimum number prescribed for each BMP system. We recommend performing these test pits once there is sufficient fill debris removed from the areas of interest. Furthermore, supplemental soil borings or test pits should be performed within the warehouse footprint to provide an adequate foundation design recommendation along with additional construction recommendations.

We hope the information provided aids in the preliminary design development for the Site's BMP system.

If you have any questions, please call.

Sincerely,

SESI CONSULTING ENGINEERS



Jose Rodriguez, PE
Principal




Michael B. Garcia
Assistant Project Engineer I

Attachments:


Drawing-1 – Exploration Location Plan
Appendix A – Soil Logs and Key to Soil Terminology

14039_shwt investigation summary letter_2025.06.05

N:\ACAD\14039\CAD\GEOTECH\LOCATION PLANS\14039.DWG.EXPO LOCATION PLAN.DWG 06/04/25 11:19:15AM, pinnacle, LAYOUT:DWG-1



NOTE:
THIS PLAN IS FOR LOCATING BORING LOCATIONS.
OTHER SITE WORK SHOWN HERE IS NOT INTENDED FOR CONSTRUCTION.



LEGEND:

- PROPOSED BIORETENTION SYSTEM
- B-5 - BORING NUMBER & APPROX. LOCATION
(EL. 43.0) APPROXIMATE ELEVATION FOR SHWT

© SESI CONSULTING ENGINEERS 2025
This drawing and all information contained here on is proprietary information of SESI CONSULTING ENGINEERS and may not be copied or reproduced, either in whole or in part, by any method, without written permission of SESI CONSULTING ENGINEERS.

REFERENCE

1. PROPOSED CONDITIONS & BOUNDARY LINES ARE TAKEN FROM "SITE SKETCH 2" PREPARED BY REDCOM DESIGN AND CONSTRUCTION, DATED APRIL 15, 2025

project:
PROPOSED REDEVELOPMENT
310 356 ENTERPRISE AVENUE
TRENTON, NEW JERSEY, 08638

title:
EXPLORATION LOCATION PLAN

job no: 14039
drawing no:

DWG-1

Cert of Auth #24GA27934700
SESI CONSULTING ENGINEERS
GEOTECHNICAL | ENVIRONMENTAL | SITE CIVIL
959 ROUTE 46E, 3RD FLOOR, PARSIPPANY, NJ 07054 PH: 973.808.9050


dwg by: EC
chk by: JMR
scale: AS NOTED
date: 06/04/25

Appendix A

Soil logs and Key to Soil Terminology

[illegible]

PROJECT LOCATION	310-356 Enterprise Avenue, Trenton, NJ		
ELEVATION DATUM	NAVD-88	GROUND ELEVATION	51.0±
DRILLING METHOD	HSA		
SAMPLE HAMMER	Auto		
AUGER INNER DIAMETER	3.25 in	OUTER DIAMETER	6.00 in
ROTARY BIT DIAMETER		DEPTH TO GROUNDWATER:	
CASING DIAMETER		▽ AT TIME OF DRILLING	10.00± ft
CASING DEPTH		▼ AT END OF DRILLING	Not Measured
FINAL DEPTH	12.0± ft	▽ 24 HR AFTER DRILLING	Not Measured

Material Symbol	EL (ft)	Sample Description	Depth (ft)	Sample Data							Remarks								
				Number	Type	Rec. (in)	Moisture	Blows/6-in Core time/ft	N-Value (Blows/ft)										
									20	40		60	80						
		4" Topsoil																	
		Fill: Light brown medium to fine SAND, trace Silt, trace coarse to fine Gravel, with trace Brick, Concrete		S-1		17	Moist	2-6-8-7 (14)											
		Fill: Light brown medium to fine SAND, trace Silt, trace fine Gravel, with Brick and Concrete fragments		S-2		12	Moist	8-6-3-5 (9)											
	46	...same as above	5	S-3		10	Moist	41-14-23-13 (37)											
		...same as above		S-4			Moist	6-7-6-8 (13)											
		...same as above		S-5			Moist	6-10-7-8 (17)											
	41	Brown coarse to fine SAND, trace Silt, trace fine Gravel	10	S-6			Wet	8-5-7-6 (12)											
	BORING COMPLETED AT 12± FEET																		
	36		15																
	31		20																
	26		25																
	21		30																
Boring B-2 encountered auger refusal at 15'. Boring was offset 5 ft south and encountered refusal at ±12 ft. Boring was offset west from original location and encountered refusal at ±12 ft.																			

PROJECT LOCATION	310-356 Enterprise Avenue, Trenton, NJ		
ELEVATION DATUM	NAVD-88	GROUND ELEVATION	49.8±
DRILLING METHOD	HSA		
SAMPLE HAMMER	Auto		
AUGER INNER DIAMETER	3.25 in	OUTER DIAMETER	6.00 in
ROTARY BIT DIAMETER		DEPTH TO GROUNDWATER:	
CASING DIAMETER		▽ AT TIME OF DRILLING	10.00± ft
CASING DEPTH		▼ AT END OF DRILLING	10.00± ft
FINAL DEPTH	10.0± ft	▽ 24 HR AFTER DRILLING	Not Measured

[illegible]

PROJECT NAME Proposed Warehouse
PROJECT NO. 14039
DATE STARTED 04-30-2025 **COMPLETED** 04-30-2025
DRILLING CONTRACTOR GPi
SAMPLER Split spoon
EQUIPMENT 7822DT
DRILLING FOREMAN Clay **HELPER** Jimmy
LOGGED BY M. Zwingle **CHECKED BY** M. Garcia
LATITUDE 40.239867 **LONGITUDE** -74.718539

PROJECT LOCATION 310-356 Enterprise Avenue, Trenton, NJ
ELEVATION DATUM NAVD-88 **GROUND ELEVATION** 49.0±
DRILLING METHOD HSA
SAMPLE HAMMER Auto
AUGER INNER DIAMETER 3.25 in **OUTER DIAMETER** 6.00 in
ROTARY BIT DIAMETER _____ **DEPTH TO GROUNDWATER:**
CASING DIAMETER _____ **AT TIME OF DRILLING** 8.00± ft
CASING DEPTH _____ **AT END OF DRILLING** 8.00± ft
FINAL DEPTH 27.0± ft **24 HR AFTER DRILLING** Not Measured

Material Symbol	EL (ft)	Sample Description	Depth (ft)	Sample Data							Remarks							
				Number	Type	Rec. (in)	Moisture	Blows/6-in Core time/ft	N-Value (Blows/ft)									
									20	40		60	80					
		4" Topsoil																
		Fill: Black to yellow-brown coarse to fine SAND, trace Silt		S-1		17	Moist	2-7-10-5 (17)										
		...same as above, trace Brick		S-2		7	Moist	2-2-1-1 (3)										
	44	No Recovery	5	S-3		0		2-9-7-10 (16)										
		Fill: Dark brown medium to fine Sand, trace Silt, little medium to fine Gravel		S-4		4	Moist	9-7-8-6 (15)										
		Fill: Dark brown medium to fine Sand, trace Silt, trace fine Gravel, trace Brick		S-5		4	Wet	5-7-11-15 (18)										
	39	Brown medium to fine SAND, some medium to fine Gravel, trace Silt	10	S-6		4	Wet	5-7-6-4 (13)										
	34	Brown medium to fine Sand, trace Silt	15	S-7		21	Wet	24-17-10-7 (27)										Auger to 15'
																		
	29	Light brown coarse to fine Sand, little medium Gravel, trace Silt	20	S-8		5	Wet	33-50/4"										Auger to 20' Broken rock in tip Possible boulder
	24	Gray-brown/dark green medium to fine Sand, trace Silt	25	S-9		19	Wet	6-9-16-22 (25)										Auger to 25' (possible fall in)
	BORING COMPLETED AT 27± FEET																	
	19		30															


Auger to 15'

Auger to 20'
Broken rock in tip
Possible boulder

Auger to 25' (possible fall in)

PROJECT NAME Proposed Warehouse
PROJECT NO. 14039
DATE STARTED 04-30-2025 **COMPLETED** 04-30-2025
DRILLING CONTRACTOR GPi
SAMPLER Split spoon
EQUIPMENT 7822DT
DRILLING FOREMAN Clay **HELPER** Jimmy
LOGGED BY M. Zwingle **CHECKED BY** M. Garcia
LATITUDE 40.242072 **LONGITUDE** -74.732581

PROJECT LOCATION 310-356 Enterprise Avenue, Trenton, NJ
ELEVATION DATUM NAVD-88 **GROUND ELEVATION** 48.0±
DRILLING METHOD HSA
SAMPLE HAMMER Auto
AUGER INNER DIAMETER 3.25 in **OUTER DIAMETER** 6.00 in
ROTARY BIT DIAMETER **DEPTH TO GROUNDWATER:**
CASING DIAMETER ∇ **AT TIME OF DRILLING** 6.00± ft
CASING DEPTH ▼ **AT END OF DRILLING** 5.00± ft
FINAL DEPTH 19.0± ft ▼ **24 HR AFTER DRILLING** Not Measured

Material Symbol	EL (ft)	Sample Description	Depth (ft)	Sample Data							Remarks			
				Number	Type	Rec. (in)	Moisture	Blows/6-in Core time/ft	N-Value (Blows/ft)					
									20	40		60	80	
	43	2" Topsoil Fill: Light brown medium to fine SAND, little Silt, trace fine Gravel, trace Brick, trace Concrete	5	S-1		18	Moist	3-10-12-10 (22)						Rig chatter at 3-4'
		S-2			16	Moist	6-5-3-2 (8)							
		S-3			11	Moist	2-1-4-1 (5)							
	38	Brown coarse to fine SAND, trace Silt, trace medium to fine Gravel	10	S-4		13	Wet	4-5-7-6 (12)						Auger to 15'
		S-5			14	Wet	6-7-7-2 (14)							
	33	Black/gray to gray Clayey Silt, trace medium to fine Sand, trace fine Gravel	15	S-6		23	Wet	3-6-8-9 (14)						Auger to 20' Distinct mottling from 15 ft
	28	No Recovery BORING COMPLETED AT 19± FEET DUE TO AUGER & SPLIT SPOON REFUSAL	20	S-7		0		50/0"						Hard drilling at 19' Attempt split spoon
	23		25											
	18		30											

Rig chatter at 3-4'

Auger to 15'

Auger to 20'
Distinct mottling from 15 ft

Hard drilling at 19'
Attempt split spoon

PROJECT LOCATION	310-356 Enterprise Avenue, Trenton, NJ		
ELEVATION DATUM	NAVD-88	GROUND ELEVATION	46.0±
DRILLING METHOD	HSA		
SAMPLE HAMMER	Auto		
AUGER INNER DIAMETER	3.25 in	OUTER DIAMETER	6.00 in
ROTARY BIT DIAMETER		DEPTH TO GROUNDWATER:	
CASING DIAMETER		▽ AT TIME OF DRILLING	10.00± ft
CASING DEPTH		▼ AT END OF DRILLING	8.50± ft
FINAL DEPTH	12.0± ft	▽ 24 HR AFTER DRILLING	Not Measured

[illegible]

SOILS CLASSIFICATION AND EXPLORATION LOG KEY

Our experience has shown that the following field identification system, which is patterned somewhat after the Burmister System, permits a more detailed breakdown of the components within a soil sample than other identification systems allow. It also compels the supervising technician to examine a sample quite closely in order to accurately describe the components within the sample.

Grain Size and Classifications

Gravel:

Coarse gravel ranges from 3-in to 1-in
Medium gravel ranges from 1-in to 3/8-in
Fine gravel ranges from 3/8-in to No. 10 sieve

Sand:

Coarse sand ranges from No. 10 to No. 30 sieve
Medium sand ranges from No. 30 to No. 60 sieve
Fine sand ranges from No. 60 to No. 200 sieve

Silt:

Material which passes the No. 200 sieve
Exhibits little to no plasticity

Clay:

Material which passes the No. 200 Sieve
Exhibits varying degrees of plasticity

Component Classification

CAPITALS More than 50% of the sample by weight

Proper Case Less than 50% of the sample by weight

Proportion Terms

and Component ranges from 35% to 50% of the sample by weight

some Component ranges from 20% to 35% of the sample by weight

little Component ranges from 10% to 20% of the sample by weight

trace Component ranges from 0% to 10% of the sample by weight

Gradation Designation

Coarse to fine (c-f) All fractions greater than 10% of the component

Coarse to Medium (c-m) Less than 10% of the component is fine

Medium to fine (m-f) Less than 10% of the component is coarse


Coarse (c) Less than 10% of the component is medium or fine

Medium (m) Less than 10% of the component is coarse or fine


Fine (f) Less than 10% of the component is coarse or medium

The subsurface information shown hereon was obtained for the design and estimating purposes for our client. It is made available to authorized users only that they may have access to the same information available to our client. It is presented in good faith, but it is not intended as a substitute for investigations, interpretations or judgement of such authorized users. Information on the logs should not be relied upon without the geotechnical engineer's recommendations contained in the report from which these logs were extracted.

Sampling Types






Generalized Stratum Types



Strata Separation



S:_0085\2505-31\CENTR - 310-356 ENTERPRISE AVE. TRENTON\ENGINEERING\REPORTS (IN HOUSE)\DRAINAGE REPORT\MAPS\CAD FILES



HORIZONTAL SCALE: 1"=100'

REVISIONS
1. 10/10/2025 REVISED FOR PSEG POLE RELOCATION REQ.

GREGORY J. REDINGTON, P.E.
NEW JERSEY PROFESSIONAL ENGINEER, LIC. NO. 37243

300- 356
ENTERPRISE AVE
BLOCK 23203, LOT 1
BLOCK 23102, LOTS 2 & 9
CITY OF TRENTON
BLOCK 602, LOTS 1 & 2
TOWNSHIP OF LAWRENCE
MERCER COUNTY
NEW JERSEY
300-356 ENTERPRISE AVE., TRENTON

EXISTING
DRAINAGE AREA
MAP



STATE OF NEW JERSEY CERTIFICATE OF AUTHORIZATION
24GA28221900 & 21AC00094500




433 NORTH AVE EAST
WESTFIELD, NJ 07090
T. 908.233.4030
F. 908.233.8857

DRAWN: APL
CHECKED: WMH
DATE: 09.22.2025
SCALE: 1" = 100'

WWW.REDCOMLLC.COM

ED

S:_005\2505-31\CENTR - 310-356 ENTERPRISE AVE. TRENTON\ENGINEERING\REPORTS (IN HOUSE)\DRAINAGE REPORT\MAPS\CAD FILES



HORIZONTAL SCALE: 1"=100'

REVISIONS	
1.	10/10/2025 REVISED FOR PSEG POLE RELOCATION REQ.
2.	12/12/2025 REVISED PER NJDEP REVIEW.


GREGORY J. REDINGTON, P.E.
NEW JERSEY PROFESSIONAL ENGINEER, L.C. No. 37243

**300- 356
ENTERPRISE AVE**
BLOCK 23203, LOT 1
BLOCK 23102, LOTS 2 & 9
CITY OF TRENTON
BLOCK 602, LOTS 1 & 2
TOWNSHIP OF LAWRENCE
MERCER COUNTY
NEW JERSEY
300-356 ENTERPRISE AVE., TRENTON

**PROPOSED
DRAINAGE AREA
MAP**



STATE OF NEW JERSEY CERTIFICATE OF AUTHORIZATION
24GA28221900 & 21AC00094500

433 NORTH AVE EAST
WESTFIELD, NJ 07090
T. 908.233.4030
F. 908.233.8837

DRAWN: AFL
CHECKED: WMH
DATE: 09.22.2025
SCALE: 1" = 100'

WWW.REDCOMLLC.COM

PD